

## MANUAL HANDLING - LOW-LEVEL RETAINING STRUCTURES

# **Description of Event**

A flat edge solution was designed as a low-level retaining structure without consideration for working area

### **Population at Risk**

Construction and Maintenance Workers, Inspectors and Travelling Members of Public (MoP)

### **Hazardous Activity and Residual Risk Description**

- Construction of low-level retaining structure using flag on edge with restricted site access requires manual handling with an assessed residual risk of 'an almost certain' likelihood of extreme harm incurred.
- A flag on edge retaining structure has a shorter design life than other solutions, increased construction period and requires a shorter interval between inspections.

### Potential consequences of this event

- In 2021 HSE estimated that there were 40,000 workers suffering with musculoskeletal disorders.
- The musculoskeletal disorder incident rate is 1.8%.
- Extended period of TTM required leading to greater exposure to workers and public.


### Safety Hub Alert Database

Sub-category 2 MoP TTM incursions has 8 alerts including 1 fatality.



Photo of flag on edge retaining structure

## **Potential Mitigation Measures**



#### Design

Eliminate manual handling of materials by designing a pre-cast concrete panel solution that requires mechanical handling.

#### Construction

Design temporary works for access and installation of precast panels to reduce TTM duration and reduce onsite manhours.



Photo precast concrete panels

### Maintenance / Operations

Periodically assess safety and serviceability at a reduced frequency when precast panels are used.

### **Further Guidance and Reading**

- RtB 8 Manual Handling
- RtB 26 Safety by Design
- DMRB GD 304 Designing health and safety into maintenance
- INDG 143 Manual handling at work a brief guide
- L23 Manual handling, Manual handling operations regulations 1992. Guidance on regulations.

