



sinclair

ZX SPECTRUM

BASIC programming

sinclair

SPECTRUM
ZX

by Steven Vickers
edited by Robin Bradbeer

Second Edition 1983

© 1982 by Sinclair Research

BASIC programming

Front cover illustration by John Harris of Young Artists

Contents

CHAPTER 1

Introduction *Page 5*

A guide to the ZX Spectrum keyboard and a description of the display

CHAPTER 2

Basic programming concepts *Page 11*

Programs, line numbers, editing programs using **↵**, **⬆** and **EDIT**, **RUN**, **LIST**, **GO TO**, **CONTINUE**, **INPUT**, **NEW**, **REM**, **PRINT**, **STOP** in **INPUT** data, **BREAK**

CHAPTER 3

Decisions *Page 23*

IF, **STOP**,
=, <, >, <=, >=, <>

CHAPTER 4

Looping *Page 29*

FOR, **NEXT**, **TO**, **STEP**

Introducing **FOR** – **NEXT** loops

CHAPTER 5

Subroutines *Page 35*

GO SUB, **RETURN**

CHAPTER 6

READ, **DATA**, **RESTORE** *Page 39*

CHAPTER 7

Expressions *Page 43*

Mathematical expressions using

+, −, *, /

scientific notation and variable names

CHAPTER 8

Strings *Page 49*

Handling strings and slicing

CHAPTER 9

Functions *Page 55*

User-definable functions and others readily available on the ZX Spectrum using **DEF**, **LEN**, **STR\$**, **VAL**, **SGN**, **ABS**, **INT**, **SQR**, **FN**

CHAPTER 10

Mathematical functions *Page 63*

including simple trigonometry

↑, **PI**, **EXP**, **LN**, **SIN**, **COS**, **TAN**, **ASN**,
ACS, **ATN**

CHAPTER 11

Random numbers *Page 71*

using **RANDOMIZE** and **RND**

CHAPTER 12

Arrays *Page 77*

String and numeric arrays

DIM

CHAPTER 13

Conditions *Page 83*

and logical expressions

AND, **OR**, **NOT**

CHAPTER 14

The character set *Page 89*

A look at the ZX Spectrum character set including graphics and how to construct your own graphic characters

CODE, **CHR\$**, **POKE**, **PEEK**, **USR**, **BIN**

CHAPTER 15

More about **PRINT** and **INPUT** *Page 99*

Some more complicated uses of these commands using separators **:**, **;**, **'**, **TAB**, **AT**, **LINE** and **CLS**

CHAPTER 16

Colours *Page 107*

INK, **PAPER**, **FLASH**, **BRIGHT**, **INVERSE**,
OVER, **BORDER**

CHAPTER 17

Graphics *Page 119*

PLOT, **DRAW**, **CIRCLE**, **POINT**

(cont. over)

CHAPTER 18

Motion *Page 127*

Animated graphics using

PAUSE, INKEY\$, and PEEK

CHAPTER 19

BEEP *Page 133*

The sound capabilities of the ZX Spectrum using **BEEP**

CHAPTER 20

Tape storage *Page 139*

How to store your programs on cassette tape

SAVE, LOAD, VERIFY, MERGE

CHAPTER 21

The ZX Printer *Page 149*

LLIST, LPRINT, COPY

CHAPTER 22

Other equipment *Page 153*

Connecting the ZX Spectrum to other machines and devices

CHAPTER 23

IN and OUT *Page 157*

Input/Output ports and their uses

IN, OUT

CHAPTER 24

The memory *Page 161*

A look at the internal workings of the ZX Spectrum

CLEAR

CHAPTER 25

The system variables *Page 171*

CHAPTER 26

Using machine code *Page 177*

Introducing **USR** with a numeric argument

APPENDICES

A The character set *Page 183*

B Reports *Page 189*

C (part 1) A description of the ZX Spectrum for reference *Page 193*

C (part 2) The BASIC *Page 197*

D Example programs *Page 209*

E Binary and hexadecimal *Page 217*

Index *Page 221*

CHAPTER

1

Introduction

Whether you read the Introductory book first, or came straight here, you should be aware that commands are obeyed straight away, and instructions begin with a line number and are stored away for later. You should also be aware of the commands: **PRINT**, **LET**, and **INPUT** (which can be used on all machines that use BASIC), and **BORDER**, **PAPER** and **BEEP** (which are used on the Spectrum).

This BASIC manual starts by repeating some things given in the introductory booklet, but in much more detail, telling you exactly what you can and cannot do. You will also find some exercises at the end of each chapter. Don't ignore these; many of them illustrate points that are hinted at in the text. Look through them, and do any that interest you, or that seem to cover ground that you don't understand properly.

Whatever else you do, keep using the computer. If you have the question "what does it do if I tell it such and such?" then the answer is easy: type it in and see. Whenever the manual tells you to type something in, always ask yourself, "what could I type instead?", and try out your replies. The more of your own programs you write, the better you will understand the computer.

At the end of this programming manual are some appendices. These include sections on the way the memory is organised, how the computer manipulates numbers, and a series of example programs illustrating the power of the ZX Spectrum.

The keyboard

ZX Spectrum characters comprise not only the single *symbols* (letters, digits, etc), but also the compound *tokens* (keywords, function names, etc) and all these are entered from the keyboard rather than being spelled out. To obtain all these functions and commands, some keys have five or more distinct meanings, given partly by shifting the keys (i.e. pressing either the **CAPS SHIFT** key or the **SYMBOL SHIFT** key at the same time as the required one) and partly by having the machine in different *modes*.

The mode is indicated by the *cursor*, a flashing letter that shows where the next character from the keyboard will be inserted.

K (for keywords) mode automatically replaces L mode when the machine is expecting a command or program line (rather than **INPUT** data), and from its position on the line it knows it should expect a line number or a keyword. This is at the beginning of the line, or just after **THEN**, or just after **:** (except in a string). If unshifted, the next key will be interpreted as either a keyword (written on the keys), or a digit.

L (for letters) mode normally occurs at all other times. If unshifted, the next key will be interpreted as the main symbol on that key, in lower case for letters.

In both K and L modes, **SYMBOL SHIFT** and a key will be interpreted as the subsidiary red character on the key and **CAPS SHIFT** with a digit key will be interpreted as the control function written in white above the key. **CAPS SHIFT** with other keys does not affect the keywords in K mode, and in L mode it converts lower case to capitals.

C (for capitals) mode is a variant of L mode in which all letters appear as capitals. **CAPS LOCK** causes a change from L mode to C mode or back again.




E (for extended) mode is used for obtaining further characters, mostly tokens. It occurs after both shift keys are pressed together, and lasts for one key depression only. In this mode, a letter gives one character or token (shown in green above it) if unshifted, and another (shown in red below it) if pressed with either shift. A digit key gives a token if pressed with **SYMBOL SHIFT**; otherwise it gives a colour control sequence.



G (for graphics) mode occurs after **GRAPHICS (CAPS SHIFT and 9)** is pressed, and lasts until it is pressed again or **9** is pressed on its own. A digit key will give a mosaic graphic, quit **GRAPHICS** or **DELETE**, and each of the letter keys apart from V, W, X, Y and Z, will give a user-defined graphic.

If any key is held down for more than about 2 or 3 seconds, it will start repeating.

Keyboard input appears in the bottom half of the screen as it is typed, each character (single symbol or compound token) being inserted just before the cursor. The cursor can be moved left with **CAPS SHIFT and 5**, or right with **CAPS SHIFT and 8**. The character before the cursor can be deleted with **DELETE (CAPS SHIFT and 0)**. (Note: the whole line can be deleted by typing **EDIT (CAPS SHIFT and 1)** followed by **ENTER**.)

When **ENTER** is pressed, the line is executed, entered into the program, or used as **INPUT** data as appropriate, unless it contains a syntax error. In this case a flashing **?** appears next to the error.

As program lines are entered, a listing is displayed in the top half of the screen. The last line entered is called the *current* line and is indicated by the symbol ; this can be moved by using the keys  (**CAPS SHIFT and 6**) and  (**CAPS SHIFT and 7**). If **EDIT (CAPS SHIFT and 1)** is pressed, the current line is brought down to the bottom part of the screen and can be edited.

When a command is executed or a program run, output is displayed in the top half of the screen and remains until a program line is entered, or **ENTER** is pressed with an empty line, or  or  is pressed. In the bottom part appears a report giving a code (digit or letter) referred to in Appendix B. The report remains on the screen until a key is pressed (and indicates K mode).

In certain circumstances, **CAPS SHIFT** with the **SPACE** key acts as a **BREAK**, stopping the computer with report **D** or **L**. This is recognised

- (i) at the end of a statement while a program is running, or
- (ii) while the computer is using the cassette recorder or printer.

The television screen

This has 24 lines, each 32 characters long, and is divided into two parts. The top part is at most 22 lines and displays either a listing or program output. When printing in the top part has reached the bottom, it all scrolls up one line; if this would involve losing a line that you have not had a chance to see yet, then the computer stops with the message **scroll?**. Pressing the keys **N**, **SPACE** or **STOP** will make the program stop with report **D BREAK – CONT repeats**; any other key will let the scrolling

continue. The bottom part is used for inputting commands, program lines, and **INPUT** data, and also for displaying reports. The bottom part starts off as two lines (the upper one blank), but it expands to accommodate whatever is typed in. When it reaches the current print position in the top half, further expansions will make the top half scroll up.

CHAPTER

2

Basic Programming Concepts

Summary

Programs

Line numbers

Editing programs using \blacktriangledown , \blacktriangleleft , and **EDIT**

RUN, LIST

GO TO, CONTINUE, INPUT, NEW, REM, PRINT


STOP in **INPUT** data

BREAK

Type in these two lines of a computer program to print out the sum of two numbers:

```
20 PRINT a
10 LET a=10
```

so that the screen looks like this:



As you already know, because these lines began with numbers, they were not obeyed immediately but stored away, as program lines. You will also have noticed here that the line numbers govern the order of the lines within the program: this is most important when the program is run, but it is also reflected in the order of the lines in the listing that you can see on the screen now.




So far you have only entered one number, so type



```
15 LET b=15
```

and in it goes. It would have been impossible to insert this line between the first two if they had been numbered 1 and 2 instead of 10 and 20 (line numbers must be whole numbers between 1 and 9999), so that is why, when first typing in a program, it is good practice to leave gaps between the line numbers.

Now you need to change line 20 to

20 PRINT a+b

You could type out the replacement in full, but it is easier to use the **EDIT** facility described in the introductory booklet. The  by line 15 is called the program cursor, and the line it points to is the current line. This is usually the last line that you entered, but you can use the  or  keys to move the program cursor down or up. (Try it, leaving the program cursor eventually at line 20.)


When you press the **EDIT** key, then a copy of the current line will be displayed at the bottom of the screen – in your case, a copy of line 20. Hold down the  key until the  cursor moves to the end of the line, and then type

+b (without **ENTER**)

The line at the bottom should now read

20 PRINT a+b

Type **ENTER** and it will replace the old line 20, so that the screen looks like this:



Run this program using **RUN** and **ENTER** and the sum will be displayed. Run the program again and then type

PRINT a, b

The variables are still there, even though the program has finished.

There is a useful method using **EDIT** to get rid of the bottom part of the screen. Type in a load of rubbish (without **ENTER**) and then decide that you don't want it after all. One way to delete it is to hold the **DELETE** key down until the line is gone; but another way is as follows. If you press **EDIT**, the rubbish at the bottom of the screen will be replaced by a copy of the current line. If you now press **ENTER**, the current line will be put back in the program unaltered, leaving the bottom part of the screen clear.

If you enter a line by mistake, say

12 LET b=8

it will go up into the program and you will realise your mistake. To delete this unnecessary line, type

12 (with **ENTER** of course)

You will notice with surprise that the program cursor has gone. You should imagine it as being hidden in between lines 10 and 15, so if you press **▲** it will move up to line 10, while if you press **▼** it will move down to line 15.

Type

12 (and **ENTER**)

Again, the program cursor will be hidden between lines 10 and 15. Now press **EDIT** and line 15 will come down: when the program cursor is hidden between two lines, **EDIT** brings down the next line following the new line number. Type **ENTER** to clear the bottom part of the screen.

Now type

30 (and **ENTER**)

This time, the program cursor is hidden after the end of the program: and if you press **EDIT**, then line 20 will be brought down.

Lastly, type

LIST 15

You will now see on the screen

15 LET b=15
20 PRINT a+b

Line 10 has vanished from the screen, but it is still in your program – which you can prove by pressing **ENTER**. The only effects of **LIST 15** are to produce a listing that

starts at line 15, and to put the program cursor at line 15. If you have a very long program, then **LIST** will probably be a more useful way of moving the program cursor than **↵** and **⬆**.

This illustrates another use of line numbers: they act as names for the program lines so that you can refer to them, rather like the way in which variables have names.

LIST on its own makes the listing start at the beginning of a program.

Another command seen in the introductory booklet is:

NEW

This erases any old programs and variables in the computer. Now carefully type in this program, which changes Fahrenheit temperatures to Centigrade.

```
10 REM temperature conversion  
20 PRINT "deg F", "deg C"  
30 PRINT  
40 INPUT "Enter deg F", F  
50 PRINT F,(F-32)*5/9  
60 GO TO 40
```

You will need to type the words in line 10. Also, although **GO TO** has a space in it, it is really all one keyword (on **G**).

Now run it. You will see the headings printed on the screen by line 20, but what happened to line 10? Apparently the computer has completely ignored it. Well, it has. **REM** in line 10 stands for remark, or reminder, and is there solely to remind you of what the program does. A **REM** command consists of **REM** followed by anything you like, and the computer will ignore it right up to the end of the line.

By now, the computer has got to the **INPUT** command on line 40 and is waiting for you to type in a value for the variable F – you can tell this because where you might have expected a **█** cursor there is instead an **␣** cursor. Enter a number; remember **ENTER**. Now the computer has displayed the result and is waiting for another number. This is because of line 60, **GO TO 40**, which means exactly what it says. Instead of running out of program and stopping, the computer jumps back to line 40 and starts again. So, enter another temperature.

After a few more of these you might be wondering if the machine will ever get bored with this, it won't. Next time it asks for another number, type **STOP**. The computer comes back with a report **H STOP in INPUT in line 40:1**, which tells you why it stopped, and where (in the first command of line 40).

If you want to continue the program type

CONTINUE

and the computer will ask you for another number.

When **CONTINUE** is used the computer remembers the line number in the last report that it sent you, as long as it was not **0 OK**, and jumps back to that line: in our

case, this involves jumping to line 40, the **INPUT** command.

Replace line 60 by **GO TO 31** – it will make no perceptible difference to the running of the program. If the line number in a **GO TO** command refers to a non-existent line, then the jump is to the next line after the given number. The same goes for **RUN**; in fact **RUN** on its own actually means **RUN 0**.

Now type in numbers until the screen starts getting full. When it is full, the computer will move the whole of the top half of the screen up one line to make room, losing the heading off the top. This is called scrolling.

When you are tired of this, stop the program using **STOP** and get the listing by pressing **ENTER**.

Look at the **PRINT** statement on line 50. The punctuation in this – the comma (,) – is very important, and you should remember that it follows much more definite rules than the punctuation in English.

Commas are used to make the printing start either at the left hand margin, or in the middle of the screen, depending on which comes next. Thus in line 50, the comma causes the centigrade temperature to be printed in the middle of the line. With a semicolon, on the other hand, the next number or string is printed immediately after the preceding one. You can see this in line 50, if the comma is replaced by a semicolon.

Another punctuation mark you can use like this in **PRINT** commands is the apostrophe ('). This makes whatever is printed next appear at the beginning of the next line on the screen but this happens anyway at the end of each **PRINT** command, so you will not need the apostrophe very much. This is why the **PRINT** command in line 50 always starts its printing on a new line, and it is also why the **PRINT** command in line 30 produces a blank line.

If you want to inhibit this, so that after one **PRINT** command the next one carries on on the same line, you can put a comma or semicolon at the end of the first. To see how this works, replace line 50 in turn by each of

```
50 PRINT F,  
50 PRINT F;
```

and

```
50 PRINT F'
```

and run each version – for good measure you could also try

```
50 PRINT F'
```

The one with the comma spreads everything out in two columns, that with the semicolon crams everything together, that without either allows a line for each number and so does that with the apostrophe – the apostrophe gives a new line of its own, but inhibits the automatic one.

Remember the difference between commas and semicolons in **PRINT** commands; also, do not confuse them with the colons (:) that are used to separate commands in a single line.

Now type in these extra lines:

```

100 REM this polite program remembers your name
110 INPUT n$
120 PRINT "Hello ";n$;"!"
130 GO TO 110

```

This is a separate program from the last one, but you can keep them both in the computer at the same time. To run the new one, type

```
RUN 100
```

Because this program inputs a string instead of a number, it prints out two string quotes – this is a reminder to you, and it usually saves you some typing as well. Try it once with any alias you care to make up for yourself.

Next time round, you will get two string quotes again, but you don't have to use them if you don't want to. Try this, for example. Rub them out (with **♦** and **DELETE** twice), and type

```
n$
```

Since there are no string quotes, the computer knows that it has to do some calculation: the calculation in this case is to find the value of the string variable called **n\$**, which is whatever name you happen to have typed in last time round. Of course, the **INPUT** statement acts like **LET n\$=n\$**, so the value of **n\$** is unchanged.

The next time round, for comparison, type

```
n$
```

again, this time without rubbing out the string quotes. Now, just to confuse you, the variable **n\$** has the value "n\$".

If you want to use **STOP** for string input, you must first move the cursor back to the beginning of the line, using **♦**.

Now look back at that **RUN 100** we had earlier on. That just jumps to line **100**, so couldn't we have said **GO TO 100** instead? In this case, it so happens that the answer is yes; but there is a difference. **RUN 100** first of all clears all the variables and the screen, and after that works just like **GO TO 100**. **GO TO 100** doesn't clear anything. There may well be occasions where you want to run a program without clearing any variables; here **GO TO** would be necessary and **RUN** could be disastrous, so it is better not to get into the habit of automatically typing **RUN** to run a program.

Another difference is that you can type **RUN** without a line number, and it starts off at the first line in the program. **GO TO** must always have a line number.

Both these programs stopped because you typed **STOP** in the input line; sometimes – by mistake – you write a program that you can't stop and won't stop itself. Type

```

200 GO TO 200
RUN 200

```

This looks all set to go on for ever unless you pull the plug out; but there is a less drastic remedy. Press **CAPS SHIFT** with the **SPACE** key, which has **BREAK** written above it. The program will stop, saying **L BREAK into program**.

At the end of every statement, the program looks to see if these keys are pressed; and if they are, then it stops. The **BREAK** key can also be used when you are in the middle of using the cassette recorder or the printer, or various other bits of machinery that you can attach to the computer – just in case the computer is waiting for them to do something but they're not doing it.

In these cases there is a different report, **D BREAK – CONT repeats. CONTINUE** in this case (and in fact in most other cases too) repeats the statement where the program was stopped; but after the report **L BREAK into program, CONTINUE** carries straight on with the next statement after allowing for any jumps to be made.

Run the name program again and when it asks you for input type

n\$ (after removing the quotes)

n\$ is an undefined variable and you get an error report **2 Variable not found**. If you now type

LET n\$="something definite"

(which has its own report of **0 OK, 0:1**) and

CONTINUE

you will find that you can use **n\$** as input data without any trouble.

In this case **CONTINUE** does a jump to the **INPUT** command in line 110. It disregards the report from the **LET** statement because that said 'OK', and jumps to the command referred to in the previous report, the first command in line 110. This is intended to be useful. If a program stops over some error then you can do all sorts of things to fix it, and **CONTINUE** will still work afterwards.

As we said before, the report **L BREAK into program** is special, because after it **CONTINUE** does not repeat the command where the program stopped.

The automatic listings (the ones that are not the result of a **LIST** command but occur after entering a new line) may well have you puzzled. If you type in a program with 50 lines, all **REM** statements,

```

1 REM
2 REM
3 REM
:
:
:
49 REM
50 REM

```

then you will be able to experiment.

The first thing to remember is that the current line (with **>**) will always appear on the screen, and usually near the middle.

Type

LIST (and **ENTER** of course)

and when it asks **scroll?** (because it has filled up the screen) press **n** for 'No'. The computer will give the report **D BREAK – CONT repeats** as though you had typed **BREAK**. You might at some stage find out what happens if you press **y** instead of **n**; **n**, **SPACE** and **STOP** count as No, while everything else counts as Yes.

Now press **ENTER** again to get an automatic listing and you should see lines 1 to 22 on the screen. Now type

23 REM

and you get lines 2 to 23 on the screen; type

28 REM

and you get lines 7 to 28. (In both cases, by typing a new line, you have moved the program cursor so that a new listing has been made.)

Maybe this looks a little arbitrary to you. It is actually trying to give you exactly what you want, although, humans being unpredictable creatures, it doesn't always guess right.

The computer keeps a record not only of the current line, the one that has to appear on the screen, but also the top line on the screen. When it tries to make a listing, the first thing it does is compare the top line to the current line.

If the top line comes after, then there is no point in starting there, so it uses the current line for a new top line and makes its listing.

Otherwise, its method is to start making the listing from the top line, and carry on until it has listed the current line, scrolling if necessary. However, it first does a rough calculation to see how long this would take, and if the answer is much too long, then it moves the top line down to be a lot closer to the current line. Now, having worked out its top line, it starts listing from there. If, when it reaches the end of the program or the bottom of the screen, the current line has been listed, then it stops. Otherwise, it scrolls until the current line is on the screen, and for each extra line that it lists it moves the top line down one so that the top line drifts into the neighbourhood of the current line.

Experiment with moving the current line about by typing

line number **REM**

LIST moves the current line but not the top line, so subsequent listings might be different. For instance, type

LIST

to get the **LIST** listing and then press **ENTER** again to make line 0 the top line. You should have lines 1 to 22 on the screen. Type

LIST 22

which gives you lines 22 to 43; when you press **ENTER** again, you get back lines 1 to 22. This tends to be more useful for short programs than for long ones.

Using the program full of **REMs** above, type

LIST

and then **n** when it asks you **scroll?**. Now type

CONTINUE

CONTINUE is a bit quirky here, because the bottom part of the screen goes blank; but you can restore normality with **BREAK**. The reason is that **LIST** was the first command in the line, so **CONTINUE** repeats this command. Unfortunately, the first command in the line is now **CONTINUE** itself so the computer just sits there doing **CONTINUE** over and over again until you stop it.

You can vary this by replacing **LIST** with

: LIST

for which **CONTINUE** gives **0 OK** (because **CONTINUE** jumps to the second command in the line, which is taken to be its end) or

:: LIST

for which **CONTINUE** gives **N Statement lost** (because **CONTINUE** jumps to the third command in the line, which no longer exists).

You have now seen the statements **PRINT**, **LET**, **INPUT**, **RUN**, **LIST**, **GO TO**, **CONTINUE**, **NEW** and **REM**, and they can all be used either as direct commands or in program lines – this is true of almost all commands in ZX Spectrum BASIC. **RUN**, **LIST**, **CONTINUE** and **NEW** are not usually of much use in a program, but they can be used.

Exercises

1. Put a **LIST** statement in a program, so that when you run it, it lists itself.
2. Write a program to input prices and print out the tax due (at 15 per cent). Put in **PRINT** statements so that the computer announces what it is going to do, and asks

for the input price with extravagant politeness. Modify the program so that you can also input the tax rate (to allow for zero ratings or future changes).

3. Write a program to print a running total of numbers you input. (Suggestion: have two variables called **total** – set to 0 to begin with – and **item**. Input **item**, add it to **total**, print them both, and go round again.)

4. What would **CONTINUE** and **NEW** do in a program? Can you think of any uses at all for this?

CHAPTER

3

Decisions

Summary

IF, STOP

=, <, >, <=, >=, <>

All the programs we have seen so far have been pretty predictable – they went straight through the instructions, and then went back to the beginning again. This is not very useful. In practice the computer would be expected to make decisions and act accordingly. The instruction used has the form . . . **IF** something is true, or not true **THEN** do something else.

For example, use **NEW** to clear the previous program from the computer and type in and run this program. (This is clearly meant for two people to play!)

```

10 REM Guess the number
20 INPUT a: CLS
30 INPUT "Guess the number", b
40 IF b=a THEN PRINT "That is correct": STOP
50 IF b<a THEN PRINT "That is too small, try again"
60 IF b>a THEN PRINT "That is too big, try again"
70 GO TO 30

```

You can see that an **IF** statement takes the form

IF condition **THEN** . . .

where the '. . .' stands for a sequence of commands, separated by colons in the usual way. The condition is something that is going to be worked out as either true or false: if it comes out as true then the statements in the rest of the line after **THEN** are executed, but otherwise they are skipped over, and the program executes the next instruction.

The simplest conditions compare two numbers or two strings: they can test whether two numbers are equal or whether one is bigger than the other; and they can test whether two strings are equal, or (roughly) one comes before the other in alphabetical order. They use the relations =, <, >, <=, >= and <>.

= means 'equals'. Although it is the same symbol as the = in a **LET** command, it is used in quite a different sense.

< (**SYMBOL SHIFT** with **R**) means 'is less than' so that

```

1<2
-2<-1
-3<1

```

are all true, but

1<0
0<-2

are false.

Line 40 compares **a** and **b**. If they are equal then the program is halted by the **STOP** command. The report at the bottom of the screen **9 STOP, statement, 30:3** shows that the third statement, or command, in line 30 caused the program to halt, i.e. **STOP**.

Line 50 determines whether **b** is less than **a**, and line 60 whether **b** is greater than **a**. If one of these conditions is true then the appropriate comment is printed, and the program works its way to line 70 which tells the computer to go back to line 30 and start all over again.

The **CLS**, clear screen, command in line 20 was to stop the other person seeing what you put in.

So > (**SYMBOL SHIFT** with **T**) means 'is greater than', and is just like < but the other way round. You can remember which is which, because the thin end points to the number that is supposed to be smaller.

<= (**SYMBOL SHIFT** with **Q** – do not type it as < followed by =) means 'is less than or equal to', so that it is like < except that it is true even if the two numbers are equal: thus 2<=2 is true, but 2<2 is false.

>= (**SYMBOL SHIFT** with **E**) means 'is greater than or equal to' and is similarly like >.

<> (**SYMBOL SHIFT** with **W**) means 'is not equal to', the opposite in meaning to =.

Mathematicians usually write <=, >= and <> as ≤, ≥ and ≠. They also write things like '2<3<4' to mean '2<3 and 3<4', but this is not possible in BASIC.

Note: in some versions of BASIC – but not on the ZX Spectrum – the **IF** statement can have the form

IF condition THEN line number

This means the same as

IF condition **THEN GO TO** line number

Exercises

1. Try this program:

```
10 PRINT "x": STOP: PRINT "y"
```

When you run it, it will display **x** and stop with report **9 STOP statement, 10:2**. Now type

```
CONTINUE
```

You might expect this to jump back to the **STOP** command – **CONTINUE** usually repeats the statement referred to in the report. However, here this would not be very useful, because the computer would just stop again without displaying **y**. Therefore, things are arranged so that after report 9 **CONTINUE** jumps to the command after the **STOP** command – so in our example, after **CONTINUE**, the computer prints **y** and reaches the end of the program.

CHAPTER

4

Looping

Summary FOR, NEXT TO, STEP

Suppose you want to input five numbers and add them together. One way (don't type this in unless you are feeling dutiful) is to write

```

10 LET total=0
20 INPUT a
30 LET total=total+a
40 INPUT a
50 LET total=total+a
60 INPUT a
70 LET total=total+a
80 INPUT a
90 LET total=total+a
100 INPUT a
110 LET total=total+a
120 PRINT total

```

This method is not good programming practice. It may be just about controllable for five numbers, but you can imagine how tedious a program like this to add ten numbers would be, and to add a hundred would be just impossible.

Much better is to set up a variable to count up to 5 and then stop the program, like this (which you should type in):

```

10 LET total=0
20 LET count=1
30 INPUT a
40 REM count=number of times that a has been input so far
50 LET total=total+a
60 LET count=count+1
70 IF count<=5 THEN GO TO 30
80 PRINT total

```

Notice how easy it would be to change line 70 so that this program adds ten numbers, or even a hundred.

This sort of counting is so useful that there are two special commands to make it easier: the **FOR** command and the **NEXT** command. They are always used together.

Using these, the program you have just typed in does exactly the same as

```

10 LET total=0
20 FOR c=1 TO 5
30 INPUT a
40 REM c=number of times that a has been input so far
50 LET total=total+a
60 NEXT c
80 PRINT total

```

(To get this program from the previous one, you just have to edit lines 20, 40, 60, and 70. **TO** is **SYMBOL SHIFT** with **F**.)

Note that we have changed **count** to **c**. The counting variable – or *control* variable – of a **FOR – NEXT** loop must have a single letter for its name.

The effect of this program is that **c** runs through the values 1 (the *initial* value), 2, 3, 4 and 5 (the *limit*), and for each one, lines 30, 40 and 50 are executed. Then, when **c** has finished its five values, line 80 is executed.

An extra subtlety to this is that the control variable does not have to go up by 1 each time: you can change this 1 to anything you like by using a **STEP** part in the **FOR** command. The most general form for a **FOR** command is

FOR control variable = initial value **TO** limit **STEP** step

where the control variable is a single letter, and the initial value, limit and step are all things that the computer can calculate as numbers – like the actual numbers themselves, or sums, or the names of numeric variables. So, if you replace line 20 in the program by

```

20 FOR c=1 TO 5 STEP 3/2

```

then **c** will run through the values 1, 2.5 and 4. Notice that you don't have to restrict yourself to whole numbers, and also that the control value does not have to hit the limit exactly – it carries on looping as long as it is less than or equal to the limit.

Try this program, to print out the numbers from 1 to 10 in reverse order.

```

10 FOR n=10 TO 1 STEP -1
20 PRINT n
30 NEXT n

```

We said before that the program carries on looping as long as the control variable is less than or equal to the limit. If you work out what this would mean in this case, you will see that it gives nonsense. The normal rule has to be modified: when the step is negative, the program carries on looping as long as the control variable is greater than or equal to the limit.

You must be careful if you are running two **FOR – NEXT** loops together, one inside

the other. Try this program, which prints out the numbers for a complete set of six spot dominoes.

```

10 FOR m=0 TO 6
20 FOR n=0 TO m
30 PRINT m;":";n;"";
40 NEXT n
50 PRINT
60 NEXT m

```

} n-loop }
} m-loop

You can see that the **n-loop** is entirely inside the **m-loop** – they are *properly nested*. What must be avoided is having two **FOR – NEXT** loops that overlap without either being entirely inside the other, like this:

```

5 REM this program is wrong
10 FOR m=0 TO 6
20 FOR n=0 TO m
30 PRINT m;":";n;"";
40 NEXT m
50 PRINT
60 NEXT n

```

} m-loop }
} n-loop

Two **FOR – NEXT** loops must either be one inside the other, or be completely separate.

Another thing to avoid is jumping into the middle of a **FOR – NEXT** loop from the outside. The control variable is only set up properly when its **FOR** statement is executed, and if you miss this out the **NEXT** statement will confuse the computer. You will probably get an error report saying **NEXT without FOR** or **variable not found**.

There is nothing whatever to stop you using **FOR** and **NEXT** in a direct command. For example, try:

```
FOR m=0 TO 10: PRINT m: NEXT m
```

You can sometimes use this as a (somewhat artificial) way of getting round the restriction that you cannot **GO TO** anywhere inside a command – because a command has no line number. For instance,

```
FOR m=0 TO 1 STEP 0: INPUT a: PRINT a: NEXT m
```

The step of zero here makes the command repeat itself forever.

This sort of thing is not really recommended, because if an error crops up then you have lost the command and will have to type it in again – and **CONTINUE** will not work.

Exercises

1. A control variable has not just a name and a value, like an ordinary variable, but also a limit, a step, and a reference to the statement after the corresponding **FOR** statement. Persuade yourself that when the **FOR** statement is executed all this information is available (using the initial value as the first value the variable takes), and also that this information is enough for the **NEXT** statement to know by how much to increase the value, whether to jump back, and if so where to jump back to.
2. Run the third program above and then type

PRINT c

Why is the answer 6, and not 5?

[Answer: the **NEXT** command in line 60 is executed five times, and each time 1 is added to **c**. The last time, **c** becomes 6; and then the **NEXT** command decides not to loop back, but to carry on, **c** being past its limit.]

What happens if you put **STEP 2** in line 20?

3. Change the third program so that instead of automatically adding five numbers, it asks you to input how many numbers you want adding. When you run this program, what happens if you input 0, meaning that you want no numbers adding? Why might you expect this to cause problems for the computer, even though it is clear what you mean? (The computer has to make a search for the command **NEXT c**, which is not usually necessary.) In fact this has all been taken care of.
4. In line 10 of the fourth program above, change **10** to **100** and run the program. It will print the numbers from 100 to 79 on the screen, and then say **scroll?** at the bottom. This is to give you a chance to see the numbers that are about to be scrolled off the top. If you press **n**, **STOP** or the **BREAK** key, the program will stop with the report **D BREAK – CONT repeats**. If you press any other key, then it will print another 22 lines and ask you again.
5. Delete line 30 from the fourth program. When you run the new curtailed program, it will print the first number and stop with the message **0 OK**. If you type

NEXT n

the program will go once round the loop, printing out the next number.

CHAPTER

5

Subroutines

Summary

GO SUB, RETURN

Sometimes different parts of the program will have rather similar jobs to do, and you will find yourself typing the same lines in two or more times; however this is not necessary. You can type the lines in once, in a form known as a subroutine, and then use, or call, them anywhere else in the program without having to type them in again.

To do this, you use the statements **GO SUB** (**GO** to **SUB**routine) and **RETURN**.

This takes the form

GO SUB n

where *n* is the line number of the first line in the subroutine. It is just like **GO TO n** except that the computer remembers where the **GO SUB** statement was so that it can come back again after doing the subroutine. It does this by putting the line number and the statement number within the line (together these constitute the *return address*) on top of a pile of them (the **GO SUB** stack);

RETURN

takes the top return address off the **GO SUB** stack, and goes to the statement after it.

As an example, let's look at the number guessing program again. Retype it as follows:

```

10 REM "A rearranged guessing game"
20 INPUT a: CLS
30 INPUT "Guess the number ",b
40 IF a=b THEN PRINT "Correct": STOP
50 IF a<b THEN GO SUB 100
60 IF a>b THEN GO SUB 100
70 GO TO 30
100 PRINT "Try again"
110 RETURN

```

The **GO TO** statement in line 70 is very important because otherwise the program will run on into the subroutine and cause an error (**7 RETURN without GO SUB**) when the **RETURN** statement is reached.

Here is another rather silly program illustrating the use of **GO SUB**.

```
100 LET x=10
110 GO SUB 500
120 PRINT s
130 LET x=x+4
140 GO SUB 500
150 PRINT s
160 LET x=x+2
170 GO SUB 500
180 PRINT s
190 STOP
500 LET s=0
510 FOR y=1 TO x
520 LET s=s+y
530 NEXT y
540 RETURN
```

When this program is run, see if you can work out what is happening. The subroutine starts at line 500.

A subroutine can happily call another, or even itself (a subroutine that calls itself is *recursive*), so don't be afraid of having several layers.

CHAPTER

6

READ, DATA, RESTORE

Summary

READ, DATA, RESTORE

In some previous programs we saw that information, or data, can be entered directly into the computer using the **INPUT** statement. Sometimes this can be very tedious, especially if a lot of the data is repeated every time the program is run. You can save a lot of time by using the **READ**, **DATA** and **RESTORE** commands. For example:

```

10 READ a,b,c
20 PRINT a,b,c
30 DATA 10,20,30
40 STOP

```

A **READ** statement consists of **READ** followed by a list of the names of variables, separated by commas. It works rather like an **INPUT** statement, except that instead of getting you to type in the values to give to the variables, the computer looks up the values in the **DATA** statement.

Each **DATA** statement is a list of expressions – numeric or string expressions – separated by commas. You can put them anywhere you like in a program, because the computer ignores them except when it is doing a **READ**. You must imagine the expressions from all the **DATA** statements in the program as being put together to form one long list of expressions, the **DATA list**. The first time the computer goes to **READ** a value, it takes the first expression from the **DATA list**; the next time, it takes the second; and thus as it meets successive **READ** statements, it works its way through the **DATA list**. (If it tries to go past the end of the **DATA list**, then it gives an error.)

Note that it's a waste of time putting **DATA** statements in a direct command, because **READ** will not find them. **DATA** statements have to go in the program.

Let's see how these fit together in the program you've just typed in. Line 10 tells the computer to read three pieces of data and give them the variables **a**, **b** and **c**. Line 20 then says **PRINT** these variables. The **DATA** statement in line 30 gives the values of **a**, **b** and **c**. Line 40 stops the program. To see the order in which things work change line 20 to:

```

20 PRINT b,c,a

```

The information in **DATA** can be part of a **FOR . . . NEXT** loop. Type in:

```

10 FOR n=1 TO 6
20 READ D
30 DATA 2,4,6,8,10,12
40 PRINT D
50 NEXT n
60 STOP

```

When this program is **RUN** you can see the **READ** statement moving through the **DATA** list. **DATA** statements can also contain string variables. For example:

```
10 READ d$
20 PRINT "The date is",d$
30 DATA "June 1st, 1982"
40 STOP
```

This is the simple way of fetching expressions from the **DATA** list: start at the beginning and work through until you reach the end. However, you can make the computer jump about in the **DATA** list, using the **RESTORE** statement. This has **RESTORE**, followed by a line number, and makes subsequent **READ** statements start getting their data from the first **DATA** statement at or after the given line number. (You can miss out the line number, in which case it is as though you had typed the line number of the first line in the program.)

Try this program:

```
10 READ a,b
20 PRINT a,b
30 RESTORE 10
40 READ x,y,z
50 PRINT x,y,z
60 DATA 1,2,3
70 STOP
```

In this program the data required by line 10 made **a**=1 and **b**=2. The **RESTORE 10** instruction reset the variables, and allowed **x**, **y** and **z** to be **READ** starting from the first number in the **DATA** statement. Rerun this program without line 30 and see what happens.

CHAPTER

7

Expressions

Summary

Operations: +, −, *, /

Expressions, scientific notation, variable names

You have already seen some of the ways in which the ZX Spectrum can calculate with numbers. It can perform the four arithmetic operations +, −, * and / (remember that * is used for multiplication, and / is used for division), and it can find the value of a variable, given its name.

The example:

LET tax=sum*15/100

gives just a hint of the very important fact that these calculations can be combined. Such a combination, like **sum*15/100**, is called an *expression*: so an expression is just a short-hand way of telling the computer to do several calculations, one after the other. In our example, the expression **sum*15/100** means 'look up the value of the variable called "sum", multiply it by 15, and divide by 100'.

If you haven't yet done so, we recommend that you look through the introductory booklet to see how the ZX Spectrum handles numbers, and the order in which it evaluates mathematical expressions.

To recap:

Multiplications and divisions are done first. They have *higher priority* than addition and subtraction. Relative to each other, multiplication and division have the same priority, which means that the multiplications and divisions are done in order from left to right. When they are dealt with, the additions and subtractions come next – these again have the same priority as each other, so we do them in order from left to right.

Although all you really need to know is whether one operation has a higher or lower priority than another, the computer does this by having a number between 1 and 16 to represent the priority of each operation: * and / have priority 8, and + and − have priority 6.

This order of calculation is absolutely rigid, but you can circumvent it by using brackets: anything in brackets is evaluated first and then treated as a single number.

Expressions are useful because, whenever the computer is expecting a number from you, you can give it an expression instead and it will work out the answer. The exceptions to this rule are so few that they will be stated explicitly in every case.

You can add together as many strings (or string variables) as you like in a single expression, and if you want, you can even use brackets.

We really ought to tell you what you can and cannot use as the names of variables. As we have already said, the name of a string variable has to be a single letter followed by \$; and the name of the control variable of a **FOR – NEXT** loop must be a single letter; but the names of ordinary numeric variables are much freer. They can use any letters or digits as long as the first one is a letter. You can put spaces in as

well to make it easier to read, but they won't count as part of the name. Also, it doesn't make any difference to the name whether you type it in capitals or lower case letters.

Here are some examples of the names of variables that are allowed:

x
t42
this name is so long that I shall never be able to type it out again without making a mistake
now we are six (these last two names are considered the same, and refer to the same variable)
nOWWeaReSiX

These are not allowed to be the names of variables:

2001 (it begins with a digit)
3 bears (begins with a digit)
M*A*S*H (* is not a letter or a digit)
Fotherington-Thomas (- is not a letter or a digit)

Numerical expressions can be represented by a number and exponent: again refer to the introductory booklet. Try the following to prove the point:

PRINT 2.34e0
PRINT 2.34e1
PRINT 2.34e2

and so on up to

PRINT 2.34e15

You will see that after a while the computer also starts using scientific notation. This is because no more than fourteen characters can be used to write a number. Similarly, try

PRINT 2.34e-1
PRINT 2.34e-2

and so on.

PRINT gives only eight significant digits of a number. Try

PRINT 4294967295, 4294967295-429e7

This proves that the computer can hold the digits of 4294967295, even though it is not prepared to display them all at once.

The ZX Spectrum uses floating point arithmetic, which means that it keeps

separate the digits of a number (its mantissa) and the position of the point (the exponent). This is not always exact, even for whole numbers. Type

PRINT 1e10+1-1e10,1e10-1e10+1

Numbers are held to about nine and a half digits accuracy, so $1e10$ is too big to be held exactly right. The inaccuracy (actually about 2) is more than 1, so the numbers $1e10$ and $1e10+1$ appear to the computer to be equal.

For an even more peculiar example, type

PRINT 5e9+1-5e9

Here the inaccuracy in $5e9$ is only about 1, and the 1 to be added on in fact gets *rounded up* to 2. The numbers $5e9+1$ and $5e9+2$ appear to the computer to be equal.

The largest integer (whole number) that can be held completely accurately is 1 less than $32 \cdot 2$'s multiplied together (or 4,294,967,295).

The string "" with no characters at all is called the *empty* or *null* string. Remember that spaces are significant and an empty string is not the same as one containing nothing but spaces.

Try

PRINT "Have you finished "Finnegans Wake" yet?"

When you press **ENTER**, you will get the flashing question mark that shows there is a mistake somewhere in the line. When the computer finds the double quotes at the beginning of "Finnegans Wake", it imagines that these mark the end of the string "have you finished", and it then can't work out what 'Finnegans Wake' means.

There is a special device to get over this: whenever you want to write a string quote symbol in the middle of a string, you must write it twice, like this:

PRINT "Have you finished ""Finnegans Wake"" yet?"

As you can see from what is printed on the screen, each double quote is only really there once; you just have to type it twice to get it recognized.

CHAPTER

8

Strings

Summary

Slicing, using **TO**. Note that this notation is not standard BASIC.

Given a string, a substring of it consists of some consecutive characters from it, taken in sequence. Thus "string" is a substring of "bigger string", but "b sting" and "big reg" are not.

There is a notation called *slicing* for describing substrings, and this can be applied to arbitrary string expressions. The general form is

string expression (start **TO** finish)

so that, for instance,

"abcdef"(2 TO 5)="bcde"

If you omit the start, then 1 is assumed; if you omit the finish then the length of the string is assumed. Thus

"abcdef"(TO 5)="abcdef"(1 TO 5)="abcde"
"abcdef"(2 TO)="abcdef"(2 TO 6)="bcdef"
"abcdef"(TO)="abcdef"(1 TO 6)="abcdef"

(You can also write this last one as **"abcdef"()**, for what it's worth.)

A slightly different form misses out the **TO** and just has one number.

"abcdef"(3)="abcdef"(3 TO 3)="c"

Although normally both start and finish must refer to existing parts of the string, this rule is overridden by another one: if the start is more than the finish, then the result is the empty string. So

"abcdef"(5 TO 7)

gives error **3 subscript wrong** because the string only contains 6 characters and 7 is too many, but

"abcdef"(8 TO 7)=""

and

"abcdef"(1 TO 0)=""

The start and finish must not be negative, or you get error **B integer out of range**. This next program is a simple one illustrating some of these rules.

```

10 LET a$="abcdef"
20 FOR n=1 TO 6
30 PRINT a$(n TO 6)
40 NEXT n
50 STOP

```

Type **NEW** when this program has been run and enter the next program:

```

10 LET a$="ABLE WAS I"
20 FOR n=1 TO 10
30 PRINT a$(n TO 10),a$((10-n) TO 10)
40 NEXT n
50 STOP

```

For string variables, we can not only extract substrings, but also assign to them. For instance, type

```

LET a$="I'm the ZX Spectrum"

```

and then

```

LET a$(5 TO 8)="*****"

```

and

```

PRINT a$

```

Notice how since the substring **a\$(5 TO 8)** is only 4 characters long, only the first four stars have been used. This is a characteristic of assigning to substrings: the substring has to be exactly the same length afterwards as it was before. To make sure this happens, the string that is being assigned to it is cut off on the right if it is too long, or filled out with spaces if it is too short – this is called Procrustean assignment after the inn-keeper Procrustes who used to make sure that his guests fitted the bed by either stretching them out on a rack or cutting their feet off.

If you now try

```

LET a$()="Hello there"

```

and

```

PRINT a$;"."

```

you will see that the same thing has happened again (this time with spaces put in) because `a$()` counts as a substring.

```
LET a$="Hello there"
```

will do it properly.

Complicated string expressions will need brackets round them before they can be sliced. For example,

```
"abc"+"def"(1 TO 2)="abcde"  
("abc"+"def")(1 TO 2)="ab"
```

Exercise

1. Try writing a program to print out the day of the week using string slicing. Hint: let the string be SunMonTuesWedThursFriSat.

CHAPTER

9

Functions

Summary

DEF

LEN, STR\$, VAL, SGN, ABS, INT, SQR

FN

Consider the sausage machine. You put a lump of meat in at one end, turn a handle, and out comes a sausage at the other end. A lump of pork gives a pork sausage, a lump of fish gives a fish sausage, and a load of beef a beef sausage.

Functions are practically indistinguishable from sausage machines but there is a difference: they work on numbers and strings instead of meat. You supply one value (called the *argument*), mince it up by doing some calculations on it, and eventually get another value, the *result*.

Meat in	→	Sausage Machine	→	Sausage out
Argument in	→	Function	→	Result out

Different arguments give different results, and if the argument is completely inappropriate the function will stop and give an error report.

Just as you can have different machines to make different products – one for sausages, another for dish cloths, and a third for fish-fingers and so on, different functions will do different calculations. Each will have its own value to distinguish it from the others.

You use a function in expressions by typing its name followed by the argument, and when the expression is evaluated the result of the function will be worked out.

As an example, there is a function called **LEN**, which works out the length of a string. Its argument is the string whose length you want to find, and its result is the length, so that if you type

PRINT LEN "Sinclair"

the computer will write the answer 8, the number of letters in 'Sinclair'. (To get **LEN**, as with most function names, you must use extended mode: press **CAPS SHIFT** and **SYMBOL SHIFT** at the same time to change the cursor from **I** to **E**, and then press the **K** key.)

If you mix functions and operations in a single expression, then the functions will be worked out before the operations. Again, however, you can circumvent this rule by using brackets. For instance, here are two expressions which differ only in the brackets, and yet the calculations are performed in an entirely different order in each case (although, as it happens, the end results are the same).

LEN "Fred"+	LEN "Bloggs"	LEN ("Fred"+"Bloggs")
4+ LEN "Bloggs"		LEN ("FredBloggs")
4+6		LEN "FredBloggs"
10		10

Here are some more functions.

STR\$ converts numbers into strings: its argument is a number, and its result is the string that would appear on the screen if the number were displayed by a **PRINT** statement. Note how its name ends in a **\$** sign to show that its result is a string. For example, you could say

LET a\$=STR\$ 1e2

which would have exactly the same effect as typing

LET a\$="100"

Or you could say

PRINT LEN STR\$ 100.0000

and get the answer 3, because **STR\$ 100.0000="100"**.

VAL is like **STR\$** in reverse: it converts strings into numbers. For instance,

VAL "3.5"=3.5

In a sense, **VAL** is the reverse of **STR\$**, because if you take any number, apply **STR\$** to it, and then apply **VAL** to it, you get back to the number you first thought of.

However, if you take a string, apply **VAL** to it, and then apply **STR\$** to it, you do not always get back to your original string.

VAL is an extremely powerful function, because the string which is its argument is not restricted to looking like a plain number – it can be any numeric expression. Thus, for instance,

VAL "2*3"= 6

or even,

VAL ("2"+"*3") = 6

There are two processes at work here. In the first, the argument of **VAL** is

evaluated as a string: the string expression `"2"+"*3"` is evaluated to give the string `"2*3"`. Then, the string has its double quotes stripped off, and what is left is evaluated as a number: so `2*3` is evaluated to give the number `6`.

This can get pretty confusing if you don't keep your wits about you; for instance,

```
PRINT VAL "VAL" "VAL" "2" "*****"
```

(Remember that inside a string a string quote must be written twice. If you go down into further depths of strings, then you find that string quotes need to be quadrupled, or even octupled.)

There is another function, rather similar to **VAL**, although probably less useful, called **VAL\$**. Its argument is still a string, but its result is also a string. To see how this works, recall how **VAL** goes in two steps: first its argument is evaluated as a string, then the string quotes stripped off this, and whatever is left is evaluated as a number. With **VAL\$**, the first step is the same, but after the string quotes have been stripped off in the second step, whatever is left is evaluated as another string. Thus

```
VAL$ "****Fruit punch****" = "Fruit punch"
```

(Notice how the string quotes proliferate again.) Do

```
LET a$="99"
```

and print out all of the following: **VAL a\$, VAL "a\$", VAL "****a\$****", VAL\$ a\$, VAL\$ "a\$" and VAL\$ "****a\$****"**. Some of these will work, and some of them won't; try to explain all the answers. (Keep a cool head.)

SGN is the *sign* function (sometimes called *signum*). It is the first function you have seen that has nothing to do with strings, because both its argument and its result are numbers. The result is +1 if the argument is positive, 0 if the argument is zero, and -1 if the argument is negative.

ABS is another function whose argument and result are both numbers. It converts the argument into a positive number (which is the result) by forgetting the sign, so that for instance

```
ABS -3.2 = ABS 3.2 = 3.2
```

INT stands for 'integer part' – an *integer* is a whole number, possibly negative. This function converts a fractional number into an integer by throwing away the fractional part, so that for instance,

```
INT 3.9 = 3
```

Be careful when you are applying it to negative numbers, because it always rounds down: thus, for instance,

```
INT -3.9 = -4
```

SQR calculates the *square root* of a number – the result that, when multiplied by itself, gives the argument. For instance,

SQR 4 = 2 because $2*2=4$
SQR 0.25 = 0.5 because $0.5*0.5=0.25$
SQR 2 = 1.4142136 (approximately)
 because $1.4142136*1.4142136=2.0000001$

If you multiply any number (even a negative one) by itself, the answer is always positive. This means that negative numbers do not have square roots, so if you apply **SQR** to a negative argument you get an error report **An Invalid Argument**.

You can also define functions of your own. Possible names for these are **FN** followed by a letter (if the result is a number) or **FN** followed by a letter followed by **\$** (if the result is a string). These are much stricter about brackets: the argument must be enclosed in brackets.

You define a function by putting a **DEF** statement somewhere in the program. For instance, here is the definition of a function **FN s** whose result is the square of the argument:

10 DEF FN s(x)=x*x: REM the square of x

DEF is obtained in extended mode, using **SYMBOL SHIFT** and **1**. When you type this, the computer will give you **FN** automatically, because in a **DEF** statement the **DEF** is always followed immediately by **FN**. After this, the **s** completes the name **FN s** of the function.

The **x** in brackets is a name by which you wish to refer to the argument of the function. You can use any single letter you like for this (or, if the argument is a string, a single letter followed by **\$**).

After the **=** sign comes the actual definition of the function. This can be any expression, and it can also refer to the argument using the name you've given it (in this case, **x**) as though it were an ordinary variable.

When you have entered this line, you can invoke the function just like one of the computer's own functions, by typing its name, **FN s**, followed by the argument. Remember that when you have defined a function yourself, the argument must be enclosed in brackets. Try it out a few times:

PRINT FN s(2)
PRINT FN s(3+4)
PRINT 1+INT FN s (LEN "chicken"/2+3)

Once you have put the corresponding **DEF** statement into the program, you can use your own functions in expressions just as freely as you can use the computer's.

Note: in some dialects of BASIC you must even enclose the argument of one of the computer's functions in brackets. This is not the case in ZX Spectrum BASIC.

INT always rounds down. To round to the nearest integer, add .5 first – you could write your own function to do this.

20 DEF FN r(x)=INT (x+0.5): REM gives x rounded to the nearest integer.

You will then get, for instance,

FN r(2.9) = 3 FN r(2.4) = 2
FN r(-2.9) = -3 FN r(-2.4) = -2

Compare these with the answers you get when you use **INT** instead of **FN r**. Type in and run the following:

10 LET x=0: LET y=0: LET a=10
20 DEF FN p(x,y)=a+x*y
30 DEF FN q()=a+x*y
40 PRINT FN p(2,3),FN q()

There are a lot of subtle points in this program.

First, a function is not restricted to just one argument: it can have more, or even none at all – but you must still always keep the brackets.

Second, it doesn't matter whereabouts in the program you put the **DEF** statements. After the computer has executed line 10, it simply skips over lines 20 and 30 to get to line 40. They do, however, have to be somewhere in the program. They can't be in a command.

Third, **x** and **y** are both the names of variables in the program as a whole, and the names of arguments for the function **FN p**. **FN p** temporarily forgets about the variables called **x** and **y**, but since it has no argument called **a**, it still remembers the variable **a**. Thus when **FN p(2,3)** is being evaluated, **a** has the value 10 because it is the variable, **x** has the value 2 because it is the first argument, and **y** has the value 3 because it is the second argument. The result is then, $10+2*3=16$. When **FN q()** is being evaluated, on the other hand, there are no arguments, so **a**, **x** and **y** all still refer to the variables and have values 10, 0 and 0 respectively. The answer in this case is $10+0*0=10$.

Now change line 20 to

20 DEF FN p(x,y)=FN q()

This time, **FN p(2,3)** will have the value 10 because **FN q** will still go back to the variables **x** and **y** rather than using the arguments of **FN p**.

Some BASICs (not the ZX Spectrum BASIC) have functions called **LEFT\$**, **RIGHT\$**, **MID\$** and **TL\$**.

LEFT\$(a\$,n) gives the substring of a\$ consisting of the first n characters.

RIGHT\$(a\$,n) gives the substring of a\$ consisting of the characters from n th on.

MID\$(a\$, n1, n2) gives the substring of a\$ consisting of $n2$ characters starting at the $n1$ th.

TL\$(a\$) gives the substring of a\$ consisting of all its characters except the first.

You can write some user-defined functions to do the same: e.g.

```
10 DEF FN t$(a$)=a$(2 TO ): REM TL$
20 DEF FN l$(a$,n)=a$( TO n): REM LEFT$
```

Check that these work with strings of length 0 or 1.

Note that our **FN l\$** has two arguments, one a number and the other a string. A function can have up to 26 numeric arguments (why 26?) and at the same time up to 26 string arguments.

Exercise

Use the function **FN s(x)=x*x** to test **SQR**: you should find that

```
FN s(SQR x)=x
```

if you substitute any positive number for **x**, and

```
SQR FN s(x)=ABS x
```

whether **x** is positive or negative (Why the **ABS**?).

CHAPTER

10

Mathematical functions

Summary

↑

PI, EXP, LN, SIN, COS, TAN, ASN, ACS, ATN

This chapter deals with the mathematics that the ZX Spectrum can handle. Quite possibly you will never have to use any of this at all, so if you find it too heavy going, don't be afraid of skipping it. It covers the operation ↑ (raising to a power), the functions **EXP** and **LN**, and the trigonometrical functions **SIN**, **COS**, **TAN** and their inverses **ASN**, **ACS**, and **ATN**.

↑ and **EXP**

You can raise one number to the power of another – that means 'multiply the first number by itself the second number of times'. This is normally shown by writing the second number just above and to the right of the first number; but obviously this would be difficult on a computer so we use the symbol ↑ instead. For example, the powers of 2 are

$$2 \uparrow 1 = 2$$

$$2 \uparrow 2 = 2 * 2 = 4 \quad (2 \text{ squared, normally written } 2^2)$$

$$2 \uparrow 3 = 2 * 2 * 2 = 8 \quad (2 \text{ cubed, normally written } 2^3)$$

$$2 \uparrow 4 = 2 * 2 * 2 * 2 = 16 \quad (2 \text{ to the power four, normally written } 2^4)$$

Thus at its most elementary level, ' $a \uparrow b$ ' means ' a multiplied by itself b times', but obviously this only makes sense if b is a positive whole number. To find a definition that works for other values of b , we consider the rule

$$a \uparrow (b+c) = a \uparrow b * a \uparrow c$$

(Notice that we give ↑ a higher priority than * and / so that when there are several operations in one expression, the ↑s are evaluated before the *s and /s.) You should not need much convincing that this works when b and c are both positive whole numbers; but if we decide that we want it to work even when they are not, then we find ourselves compelled to accept that

$$a \uparrow 0 = 1$$

$$a \uparrow (-b) = 1/a \uparrow b$$

$a \uparrow (1/b)$ = the b th root of a , which is to say, the number that you have to multiply by itself b times to get a

and

$$a \uparrow (b*c) = (a \uparrow b) \uparrow c$$

If you have never seen any of this before then don't try to remember it straight away; just remember that

$$a \uparrow (-1) = 1/a$$

and

$$a \uparrow (1/2) = \mathbf{SQR} a$$

and maybe when you are familiar with these the rest will begin to make sense.

Experiment with all this by trying this program:

```

10 INPUT a,b,c
20 PRINT a ↑ (b+c),a ↑ b*a ↑ c
30 GO TO 10
    
```

Of course, if the rule we gave earlier is true, then each time round the two numbers that the computer prints out will be equal. (Note – because of the way the computer works out \uparrow , the number on the left – **a** in this case – must never be negative.)

A rather typical example of what this function can be used for is that of compound interest. Suppose you keep some of your money in a building society and they give 15% interest per year. Then after one year you will have not just the 100% that you had anyway, but also the 15% interest that the building society have given you, making altogether 115% of what you had originally. To put it another way, you have multiplied your sum of money by 1.15, and this is true however much you had there in the first place. After another year, the same will have happened again, so that you will then have $1.15 * 1.15 = 1.15 \uparrow 2 = 1.3225$ times your original sum of money. In general, after **y** years, you will have **1.15 ↑ y** times what you started out with.

If you try this command

```

FOR y=0 TO 100: PRINT y,10*1.15 ↑ y: NEXT y
    
```

you will see that even starting off from just £10, it all mounts up quite quickly, and what is more, it gets faster and faster as time goes on. (Although even so, you might still find that it doesn't keep up with inflation.)

This sort of behaviour, where after a fixed interval of time some quantity multiplies itself by a fixed proportion, is called *exponential growth*, and it is calculated by raising a fixed number to the power of the time.

Suppose you did this:

```

10 DEF FN a(x)=a ↑ x
    
```

Here, *a* is more or less fixed, by **LET** statements: its value will correspond to the interest rate, which changes only every so often.

There is a certain value for **a** that makes the function **FN a** look especially pretty to the trained eye of a mathematician: and this value is called *e*. The ZX Spectrum has a function called **EXP** defined by

```

EXP x = e ↑ x
    
```

Unfortunately, e itself is not an especially pretty number: it is an infinite non-recurring decimal. You can see its first few decimal places by doing

PRINT EXP 1

because **EXP 1** = $e \uparrow 1 = e$. Of course, this is just an approximation. You can never write down e exactly.

LN

The inverse of an exponential function is a *logarithmic* function: the *logarithm* (to base a) of a number x is the power to which you have to raise a to get the number x , and it is written $\log_a x$. Thus by definition $a \uparrow \log_a x = x$; and it is also true that $\log(a \uparrow x) = x$.

You may well already know how to use base 10 logarithms for doing multiplications; these are called *common* logarithms. The ZX Spectrum has a function **LN** which calculates logarithms to the base e ; these are called *natural* logarithms. To calculate logarithms to any other base, you must divide the natural logarithm by the natural logarithm of the base:

$$\log_a x = \text{LN } x / \text{LN } a$$


PI

Given any circle, you can find its *perimeter* (the distance round its edge; often called its *circumference*) by multiplying its *diameter* (width) by a number called π . (π is a Greek p , and it is used because it stands for perimeter. Its name is **pi**.)

Like e , π is an infinite non-recurring decimal; it starts off as 3.141592653589 The word **PI** on the Spectrum (extended mode, then M) is taken as standing for this number – try **PRINT PI**.

SIN, COS and TAN; ASN, ACS and ATN


The *trigonometrical* functions measure what happens when a point moves round a circle. Here is a circle of radius 1 (1 what? It doesn't matter, as long as we keep to the same unit all the way through. There is nothing to stop you inventing a new unit of your own for every circle that you happen to be interested in) and a point moving round it. The point started at the 3 o'clock position, and then moved round in an anti-clockwise direction.



We have also drawn in two lines called *axes* through the centre of the circle. The one through 9 o'clock and 3 o'clock is called the *x-axis*, and the one through 6 o'clock and 12 o'clock is called the *y-axis*.

To specify where the point is, you say how far it has moved round the circle from its 3 o'clock starting position: let us call this distance a . We know that the circumference of the circle is 2π (because its radius is 1 and its diameter is thus 2): so when it has moved a quarter of the way round the circle, $a = \pi/2$; when it has moved halfway round, $a = \pi$; and when it has moved the whole way round, $a = 2\pi$.

Given the curved distance round the edge, a , two other distances you might like to know are how far the point is to the right of the *y-axis*, and how far it is above the *x-axis*. These are called, respectively, the *cosine* and *sine* of a . The functions **COS** and **SIN** on the computer will calculate these.



Note that if the point goes to the left of the y -axis, then the cosine becomes negative; and if the point goes below the x -axis, the sine becomes negative.

Another property is that once a has got up to 2π , the point is back where it started and the sine and cosine start taking the same values all over again:

$$\begin{aligned}\mathbf{SIN (a+2*PI) = SIN a} \\ \mathbf{COS (a+2*PI) = COS a}\end{aligned}$$

The *tangent* of a is defined to be the sine divided by the cosine; the corresponding function on the computer is called **TAN**.

Sometimes we need to work these functions out in reverse, finding the value of a that has given sine, cosine or tangent. The functions to do this are called *arcsine*

(**ASN** on the computer), *arccosine* (**ACS**) and *arctangent* (**ATN**).

In the diagram of the point moving round the circle, look at the radius joining the centre to the point. You should be able to see that the distance we have called a , the distance that the point has moved round the edge of the circle, is a way of measuring the angle through which the radius has moved away from the x-axis. When $a = \pi/2$, the angle is 90 degrees; when $a = \pi$ the angle is 180 degrees; and so round to when $a = 2\pi$, and the angle is 360 degrees. You might just as well forget about degrees, and measure the angle in terms of a alone: we say then that we are measuring the angle in *radians*. Thus $\pi/2$ radians = 90 degrees and so on.

You must always remember that on the ZX Spectrum **SIN**, **COS** and so on use radians and not degrees. To convert degrees to radians, divide by 180 and multiply by π ; to convert back from radians to degrees, you divide by π and multiply by 180.

CHAPTER

11

Random numbers

Summary RANDOMIZE RND

This chapter deals with the function **RND** and the keyword **RANDOMIZE**. They are both used in connection with random numbers, so you must be careful not to get them mixed up. They are both on the same key (**T**); **RANDOMIZE** has had to be abbreviated to **RAND**.

In some ways **RND** is like a function: it does calculations and produces a result. It is unusual in that it does not need an argument.

Each time you use it, its result is a new random number between 0 and 1. (Sometimes it can take the value 0, but never 1.)

Try

```
10 PRINT RND
20 GO TO 10
```

to see how the answer varies. Can you detect any pattern? You shouldn't be able to; 'random' means that there is no pattern.

Actually, **RND** is not truly random, because it follows a fixed sequence of 65536 numbers. However, these are so thoroughly jumbled up that there are at least no obvious patterns and we say that **RND** is *pseudo-random*.

RND gives a random number between 0 and 1, but you can easily get random numbers in other ranges. For instance, **5*RND** is between 0 and 5, and **1.3+0.7*RND** is between 1.3 and 2. To get whole numbers, use **INT** (remembering that **INT** always rounds down) as in **1+INT (RND*6)**, which we shall use in a program to simulate dice. **RND*6** is in the range 0 to 6, but since it never actually reaches 6, **INT (RND*6)** is 0,1,2,3,4 or 5.

Here is the program:

```
10 REM dice throwing program
20 CLS
30 FOR n=1 TO 2
40 PRINT 1+INT (RND*6);" ";
50 NEXT n
60 INPUT a$: GO TO 20
```

Press **ENTER** each time you want to throw the dice.

The **RANDOMIZE** statement is used to make **RND** start off at a definite place in its sequence of numbers, as you can see with this program:

```
10 RANDOMIZE 1
20 FOR n=1 TO 5: PRINT RND ,: NEXT n
30 PRINT : GO TO 10
```

After each execution of **RANDOMIZE 1**, the **RND** sequence starts off again with 0.0022735596. You can use other numbers between 1 and 65535 in the **RANDOMIZE** statement to start the **RND** sequence off at different places.

If you had a program with **RND** in it and it also had some mistakes that you had not found, then it would help to use **RANDOMIZE** like this so that the program behaved the same way each time you ran it.

RANDOMIZE on its own (and **RANDOMIZE 0** has the same effect) is different, because it really does randomize **RND** – you can see this in the next program.

```
10 RANDOMIZE
20 PRINT RND : GO TO 10
```

The sequence you get here is not very random, because **RANDOMIZE** uses the time since the computer was switched on. Since this has gone up by the same amount each time **RANDOMIZE** is executed, the next **RND** does more or less the same. You would get better randomness by replacing **GO TO 10** by **GO TO 20**.

Note: Most dialects of BASIC use **RND** and **RANDOMIZE** to produce random numbers, but not all use them in the same way.

Here is a program to toss coins and count the numbers of heads and tails.

```
10 LET heads=0: LET tails=0
20 LET coin=INT (RND*2)
30 IF coin=0 THEN LET heads=heads+1
40 IF coin=1 THEN LET tails=tails+1
50 PRINT heads;" ";tails,
60 IF tails<>0 THEN PRINT heads/tails;
70 PRINT : GO TO 20
```

The ratio of heads to tails should become approximately 1 if you go on long enough, because in the long run you expect approximately equal numbers of heads and tails.

Exercises

1. Test this rule:

Suppose you choose a number between 1 and 872 and type

```
RANDOMIZE your number
```

Then the next value of **RND** will be

$$(75*(\text{your number}+1)-1)/65536$$

2. (For mathematicians only.)

Let p be a (large) prime, and let a be a primitive root modulo p .

Then if b , is the residue of a^i modulo p ($1 \leq b_i \leq p-1$), the sequence

$$\frac{b_i-1}{p-1}$$

is a cyclical sequence of $p-1$ distinct numbers in the range 0 to 1 (excluding 1). By choosing a suitably, these can be made to look fairly random.

65537 is a Fermat prime, $2^{16}+1$. Because the multiplicative group of non-zero residues modulo 65537 has a power of 2 as its order, a residue is a primitive root if and only if it is not a quadratic residue. Use Gauss' law of quadratic reciprocity to show that 75 is a primitive root modulo 65537.

The ZX Spectrum uses $p=65537$ and $a=75$, and stores some b_i-1 in memory. **RND** entails replacing b_i-1 in memory by $b_{i+1}-1$, and yielding the result $(b_{i+1}-1)/(p-1)$. **RANDOMIZE** n (with $1 \leq n \leq 65535$) makes b_i equal to $n+1$.

RND is approximately uniformly distributed over the range 0 to 1.

CHAPTER

12

Arrays

Summary

Arrays (the way the ZX Spectrum handles string arrays is slightly non-standard).

DIM . . .

Suppose you have a list of numbers, for instance the marks of ten people in a class. To store them in the computer you could set up a single variable for each person, but you would find them very awkward. You might decide to call the variable Bloggs 1, Bloggs 2, and so on up to Bloggs 10, but the program to set up these ten numbers would be rather long and boring to type in.

How much nicer it would be if you could type this:

```

5 REM this program will not work
10 FOR n=1 TO 10
20 READ Bloggs n
30 NEXT n
40 DATA 10,2,5,19,16,3,11,1,0,6

```

Well you can't.

However, there is a mechanism by which you can apply this idea, and it uses *arrays*. An array is a set of variables, its elements, all with the same name, and distinguished only by a number (the *subscript*) written in brackets after the name. In our example the name could be *b* (like control variables of **FOR – NEXT** loops, the name of an array must be a single letter), and the ten variables would then be *b*(1), *b*(2), and so on up to *b*(10).

The elements of an array are called *subscripted* variables, as opposed to the *simple* variables that you are already familiar with.

Before you can use an array, you must reserve some space for it inside the computer, and you do this using a **DIM** (for dimension) statement.

```

DIM b(10)

```

sets up an array called *b* with dimension 10 (i.e. there are 10 subscripted variables *b*(1),..., *b*(10)), and initializes the 10 values to 0. It also deletes any array called *b* that existed previously. (But not a simple variable. An array and a simple numerical variable with the same name can coexist, and there shouldn't be any confusion between them because the array variable always has a subscript.)

The subscript can be an arbitrary numerical expression, so now you can write

```

10 FOR n=1 TO 10
20 READ b(n)
30 NEXT n
40 DATA 10,2,5,19,16,3,11,1,0,6

```

You can also set up arrays with more than one dimension. In a two dimensional array you need two numbers to specify one of the elements – rather like the line and column numbers to specify a character position on the television screen – so it has the form of a table. Alternatively, if you imagine the line and column numbers (two dimensions) as referring to a printed page, you could have an extra dimension for the page numbers. Of course, we are talking about numeric arrays; so the elements would not be printed characters as in a book, but numbers. Think of the elements of a three-dimensional array v as being specified by v (page number, line number, column number).

For example, to set up a two-dimensional array c with dimensions 3 and 6, you use a **DIM** statement

DIM c(3,6)

This then gives you $3 \times 6 = 18$ subscripted variables

```
c(1,1),c(1,2),...,c(1,6)
c(2,1),c(2,2),...,c(2,6)
c(3,1),c(3,2),...,c(3,6)
```

The same principle works for any number of dimensions.

Although you can have a number and an array with the same name, you cannot have two arrays with the same name, even if they have different numbers of dimensions.

There are also string arrays. The strings in an array differ from simple strings in that they are of fixed length and assignment to them is always Procrustean – chopped off or padded with spaces. Another way of thinking of them is as arrays (with one extra dimension) of single characters. The name of a string array is a single letter followed by **\$**, and a string array and a simple string variable cannot have the same name (unlike the case for numbers).

Suppose then, that you want an array **a\$** of five strings. You must decide how long these strings are to be – let us suppose that 10 characters each is long enough. You then say

DIM a\$(5,10) (type this in)

This sets up a 5×10 array of characters, but you can also think of each row as being a string:

```
a$(1)=a$(1,1) a$(1,2) ... a$(1,10)
a$(2)=a$(2,1) a$(2,2) ... a$(2,10)
: : : : :
a$(5)=a$(5,1) a$(5,2) ... a$(5,10)
```

If you give the same number of subscripts (two in this case) as there were

dimensions in the **DIM** statement, then you get a single character; but if you miss the last one out, then you get a fixed length string. So, for instance, `A$(2,7)` is the 7th character in the string `A$(2)`; using the slicing notation, we could also write this as `A$(2)(7)`. Now type

```
LET a$(2)=""1234567890"
and
PRINT a$(2),a$(2,7)
```

You get

```
1234567890 7
```

For the last subscript (the one you can miss out), you can also have a slicer, so that for instance

```
a$(2,4 TO 8)=a$(2)(4 TO 8)=""45678"
```

Remember:

In a string array, all the strings have the same, fixed length.

The **DIM** statement has an extra number (the last one) to specify this length.

When you write down a subscripted variable for a string array, you can put in an extra number, or a slicer, to correspond with the extra number in the **DIM** statement.

You can have string arrays with no dimensions. Type

```
DIM a$(10)
```

and you will find that `a$` behaves just like a string variable, except that it always has length 10, and assignment to it is always procrustean.

Exercises

1. Use **READ** and **DATA** statements to set up an array `m$` of twelve strings in which `m$(n)` is the name of the `n`th month. (Hint: the **DIM** statement will be **DIM m\$(12,9)**. Test it by printing out all the `m$(n)` (use a loop)).

Type

```
PRINT "now is the month of ";m$(5);"ing";" when merry lads
are playing"
```

What can you do about all those spaces?

CHAPTER

13

Conditions

Summary

AND, OR

NOT

We saw in Chapter 3 how an **IF** statement takes the form

IF condition **THEN** . . .

The conditions there were the relations (=, <, >, <=, >= and <>), which compare two numbers or two strings. You can also combine several of these, using the logical operations, **AND**, **OR** and **NOT**.

One relation **AND** another relation is true whenever both relations are true, so you could have a line like:

IF a\$="yes" AND x>0 THEN PRINT x

in which **x** only gets printed if **a\$="yes"** and **x>0**. The BASIC here is so close to English that it hardly seems worth spelling out the details. As in English, you can join lots of relations together with **AND**, and then the whole lot is true if all the individual relations are.

One relation **OR** another is true whenever at least one of the two relations is true. (Remember that it is still true if both the relations are true; this is something that English doesn't always imply.)

The **NOT** relationship turns things upside down. The **NOT** relation is true whenever the relation is false, and false whenever it is true!

Logical expressions can be made with relations and **AND**, **OR** and **NOT**, just as numerical expressions can be made with numbers and +, - and so on; you can even put them in brackets if necessary. They have priorities in the same way as the usual operations +, -, *, / and ↑, do: **OR** has the lowest priority, then **AND**, then **NOT**, then the relations, and the usual operations.

NOT is really a function, with an argument and a result, but its priority is much lower than that of other functions. Therefore its argument does not need brackets unless it contains **AND** or **OR** (or both). **NOT a=b** means the same as **NOT (a=b)** (and the same as **a<>b**, of course).

<> is the negation of = in the sense that it is true if, and only if, = is false. In other words,

a<>b is the same as **NOT a=b**

and also

NOT a<>b is the same as **a=b**

Persuade yourself that >= and <= are the negations of < and > respectively: thus you can always get rid of **NOT** from in front of a relation by changing the relation.

Also,

NOT (a first logical expression **AND** a second)

is the same as

NOT (the first) **OR NOT** (the second)

and

NOT (a first logical expression **OR** a second)

is the same as

NOT (the first) **AND NOT** (the second).

Using this you can work **NOT**s through brackets until eventually they are all applied to relations, and then you can get rid of them. Logically speaking, **NOT** is unnecessary, although you might still find that using it makes a program clearer.

The following section is quite complicated, and can be skipped by the faint-hearted!

Try

PRINT 1=2,1<>2

which you might expect to give a syntax error. In fact, as far as the computer is concerned, there is no such thing as a logical value: instead it uses ordinary numbers, subject to a few rules.

(i) =, <, >, <=, >= and <> all give numeric results: 1 for true, and 0 for false. Thus the **PRINT** command above printed 0 for '1=2', which is false, and 1 for '1<>2', which is true.

(ii) In

IF condition **THEN** . . .

the condition can be actually any numeric expression. If its value is 0, then it counts as false, and any other value (including the value of 1 that a true relation gives) counts as true. Thus the **IF** statement means exactly the same as

IF condition <>0 **THEN** . . .

(iii) **AND**, **OR** and **NOT** are also number-valued operations.

x AND y has the value $\begin{cases} x, & \text{if } y \text{ is true (non-zero)} \\ 0 \text{ (false),} & \text{if } y \text{ is false (zero)} \end{cases}$

x OR y has the value $\begin{cases} 1 \text{ (true),} & \text{if } y \text{ is true (non zero)} \\ x, & \text{if } y \text{ is false (zero)} \end{cases}$

NOT x has the value $\begin{cases} 0 \text{ (false),} & \text{if } x \text{ is true (non-zero)} \\ 1 \text{ (true),} & \text{if } x \text{ is false (zero)} \end{cases}$

(Notice that 'true' means 'non-zero' when we're checking a given value, but it means '1' when we're producing a new one.)

Read through the chapter again in the light of this revelation, making sure that it all works.

In the expressions **x AND y**, **x OR y** and **NOT x**, **x** and **y** will usually take the values 0 and 1 for false and true. Work out the ten different combinations (four for **AND**, four for **OR** and two for **NOT**) and check that they do what the chapter leads you to expect them to do.

Try this program:

```

10 INPUT a
20 INPUT b
30 PRINT (a AND a>=b)+(b AND a<b)
40 GO TO 10

```

Each time it prints the larger of the two numbers **a** and **b**.

Convince yourself that you can think of

x AND y

as meaning

x if **y** (else the result is 0)

and of

x OR y

as meaning

x unless **y** (in which case the result is 1)

An expression using **AND** or **OR** like this is called a *conditional* expression. An example using **OR** could be

LET total price=price less tax*(1.15 OR v\$="zero rated")

Notice how **AND** tends to go with addition (because its default value is 0), and **OR** tends to go with multiplication (because its default value is 1).

You can also make string valued conditional expressions, but only using **AND**.

x\$ AND y has the value $\begin{cases} x\$ & \text{if } y \text{ is non-zero} \\ "" & \text{if } y \text{ is zero} \end{cases}$

so it means **x\$** if **y** (else the empty string).

Try this program, which inputs two strings and puts them in alphabetical order.

```

10 INPUT "type in two strings" a$,b$
20 IF a$>b$ THEN LET c$=a$: LET a$=b$: LET b$=c$
30 PRINT a$;" ";(" <" AND a$<b$)+(" = " AND a$=b$);" ";b$
40 GO TO 10

```

Exercise

1. BASIC can sometimes work along different lines from English. Consider, for instance, the English clause 'If *a* doesn't equal *b* or *c*'. How would you write this in BASIC? The answer is not

IF A<>B OR C

nor is it

IF A<>B OR A<>C

CHAPTER

14

The Character Set

Summary

CODE, CHR\$

POKE, PEEK

USR

BIN

The letters, digits, punctuation marks and so on that can appear in strings are called *characters*, and they make up the alphabet, or *character set*, that the ZX Spectrum uses. Most of these characters are single *symbols*, but there are some more, called *tokens*, that represent whole words, such as **PRINT**, **STOP**, **<>** and so on.

There are 256 characters, and each one has a code between 0 and 255. There is a complete list of them in Appendix A. To convert between codes and characters, there are two functions, **CODE** and **CHR\$**.

CODE is applied to a string, and gives the code of the first character in the string (or 0 if the string is empty).

CHR\$ is applied to a number, and gives the single character string whose code is that number.

This program prints out the entire character set

































```
10 FOR a=32 TO 255: PRINT CHR$ a;: NEXT a
```

At the top you can see a space, 15 symbols and punctuation marks, the ten digits, seven more symbols, the capital letters, six more symbols, the lower case letters and five more symbols. These are all (except **£** and **©**) taken from a widely-used set of characters known as ASCII (standing for American Standard Codes for Information Interchange); ASCII also assigns numeric codes to these characters, and these are the codes that the ZX Spectrum uses.

The rest of the characters are not part of ASCII, and are peculiar to the ZX Spectrum. First amongst them are a space and 15 patterns of black and white blobs. These are called the *graphics* symbols and can be used for drawing pictures. You can enter these from the keyboard, using what is called *graphics mode*. If you press **GRAPHICS (CAPS SHIFT with 9)** then the cursor will change to **G**. Now the keys for the digits 1 to 8 will give the graphics symbols: on their own they give the symbols drawn on the keys; and with either shift pressed they give the same symbol but inverted, i.e. black becomes white, and vice versa.

Regardless of shifts, digit 9 takes you back to normal (L) mode and digit 0 is **DELETE**.


Here are the sixteen graphics symbols:

Symbol	Code	How obtained	Symbol	Code	How obtained
	128	 8		143	 shifted 8
	129	 1		142	 shifted 1
	130	 2		141	 shifted 2
	131	 3		140	 shifted 3
	132	 4		139	 shifted 4
	133	 5		138	 shifted 5
	134	 6		137	 shifted 6
	135	 7		136	 shifted 7

After the graphics symbols, you will see what appears to be another copy of the alphabet from A to U. These are characters that you can redefine yourself, although when the machine is first switched on they are set as letters – they are called *user-defined* graphics. You can type these in from the keyboard by going into graphics mode, and then using the letters keys from A to U.

To define a new character for yourself, follow this recipe – it defines a character to show π .

(i) Work out what the character looks like. Each character has an 8x8 square of dots, each of which can show either the paper colour or the ink colour (see the introductory booklet). You'd draw a diagram something like this, with black squares for the ink colour:



We've left a 1 square margin round the edge because the other letters all have one (except for lower case letters with tails, where the tail goes right down to the bottom).

(ii) Work out which user-defined graphic is to show π – let's say the one corresponding to P, so that if you press P in graphics mode you get π .

(iii) Store the new pattern. Each user-defined graphic has its pattern stored as eight numbers, one for each row. You can write each of these numbers as **BIN** followed by eight 0's or 1's – 0 for paper, 1 for ink – so that the eight numbers for our π character are

```

BIN 00000000
BIN 00000000
BIN 00000010
BIN 00111100
BIN 01010100
BIN 00010100
BIN 00010100
BIN 00000000

```

(If you know about binary numbers, then it should help you to know that **BIN** is used to write a number in binary instead of the usual decimal.)

These eight numbers are stored in memory, in eight places, each of which has an *address*. The address of the first byte, or group of eight digits, is **USR "P"** (P because that is what we chose in (ii)), that of the second is **USR "P"+1**, and so on up to the eighth, which has address **USR "P"+7**.

USR here is a function to convert a string argument into the address of the first byte in memory for the corresponding user-defined graphic. The string argument must be a single character which can be either the user-defined graphic itself or the corresponding letter (in upper or lower case). There is another use for **USR**, when its argument is a number, which will be dealt with.

Even if you don't understand this, the following program will do it for you:

```
10 FOR n=0 TO 7
20 INPUT row: POKE USR "P"+n,row
30 NEXT n
```

It will stop for **INPUT** data eight times to allow you to type in the eight **BIN** numbers above – type them in the right order, starting with the top row.

The **POKE** statement stores a number directly in memory location, bypassing the mechanisms normally used by the BASIC. The opposite of **POKE** is **PEEK**, and this allows us to look at the contents of a memory location although it does not actually alter the contents of that location. They will be dealt with properly in Chapter 24.

After the user-defined graphics come the tokens.

You will have noticed that we have not printed out the first 32 characters, with codes 0 to 31. These are *control* characters. They don't produce anything printable, but have some less tangible effect on the television, or they are used for controlling something other than the television, and the television prints ? to show that it doesn't understand them. They are described more fully in Appendix A.

Three that the television uses are those with codes 6, 8 and 13; on the whole, **CHR\$ 8** is the only one you are likely to find useful.

CHR\$ 6 prints spaces in exactly the same way as a comma does in a **PRINT** statement for instance

```
PRINT 1; CHR$ 6;2
```

does the same as

```
PRINT 1,2
```

Obviously this is not a very clear way of using it. A more subtle way is to say

```
LET a$="1"+CHR$ 6+"2"
PRINT a$
```

CHR\$ 8 is 'backspace': it moves the print position back one place – try

```
PRINT "1234"; CHR$ 8;"5"
```

which prints up **1235**

CHR\$ 13 is 'newline': it moves the print position on to the beginning of the next line.

The television also uses those with codes 16 to 23; these are explained in Chapters 15 and 16. All the control characters are listed in Appendix A.

Using the codes for the characters we can extend the concept of 'alphabetical ordering' to cover strings containing any characters, not just letters. If instead of thinking in terms of the usual alphabet of 26 letters we use the extended alphabet of 256 characters, in the same order as their codes, then the principle is exactly the same. For instance, these strings are in their ZX Spectrum alphabetical order. (Notice the rather odd feature that lower case letters come after all the capitals: so "a" comes after "Z"; also, spaces matter.)

CHR\$ 3+"ZOOLOGICAL GARDENS"
CHR\$ 8+"AARDVARK HUNTING"
" AAAARGH!"
"(Parenthetical remark)"
"100"
"129.95 inc. VAT"
"AASVOGEL"
"Aardvark"
"PRINT"
"Zoo"
"[interpolation]"
"aardvark"
"aasvogel"
"zoo"
"zoology"

Here is the rule for finding out which order two strings come in. First, compare the first characters. If they are different, then one of them has its code less than the other, and the string it came from is the earlier (lesser) of the two strings. If they are the same, then go on to compare the next characters. If in this process one of the strings runs out before the other, then that string is the earlier; otherwise they must be equal.

The relations =, <, >, <=, >= and <> are used for strings as well as for numbers: < means 'comes before' and > means 'comes after', so that

"AA man"<"AARDVARK"
"AARDVARK">"AA man"

are both true.

<= and >= work the same way as they do for numbers, so that

"The same string"<="The same string"

is true, but

“The same string” < “The same string”

is false.

Experiment on all this using the program here, which inputs two strings and puts them in order.

```

10 INPUT "Type in two strings:",a$,b$
20 IF a$>b$ THEN LET c$=a$: LET a$=b$: LET b$=c$
30 PRINT a$;" ";
40 IF a$<b$ THEN PRINT "<";: GO TO 60
50 PRINT "="
60 PRINT " ";b$
70 GO TO 10

```

Note how we have to introduce **c\$** in line 20 when we swap over **a\$** and **b\$**,

```

LET a$=b$: LET b$=a$

```

would not have the desired effect.

This program sets up user-defined graphics to show chess pieces:

P for pawn
R for rook
N for knight
B for bishop
K for king
Q for queen

Chess pieces

```

5 LET b=BIN 01111100: LET c=BIN
00111000: LET d=BIN 00010000
10 FOR n=1 TO 6: READ p$: REM 6 pieces
20 FOR f=0 TO 7: REM read piece into 8 bytes
30 READ a: POKE USR p$+f,a
40 NEXT f
50 NEXT n
100 REM bishop
110 DATA "b",0,d, BIN 00101000, BIN 01000100
120 DATA BIN 01101100,c,b,0
130 REM king
140 DATA "k",0,d,c,d
150 DATA c, BIN 01000100,c,0
160 REM rook
170 DATA "r",0, BIN 01010100,b,c

```

```

180 DATA c,b,b,0
190 REM queen
200 DATA "q",0, BIN 01010100, BIN 00101000,d
210 DATA BIN 01101100,b,b,0
220 REM pawn
230 DATA "p",0,0,d,c
240 DATA c,d,b,0
250 REM knight
260 DATA "n",0,d,c, BIN 01111000
270 DATA BIN 00011000,c,b,0

```

Note that 0 can be used instead of **BIN 00000000**.

When you have run the program, look at the pieces by going into graphics mode.

Exercises

1. Imagine the space for one symbol divided up into four quarters like a Battenburg cake: Then if each quarter can be either black or white, there are $2 \times 2 \times 2 \times 2 = 16$ possibilities. Find them all in the character set.
2. Run this program:

```

10 INPUT a
20 PRINT CHR$ a;
30 GO TO 10

```

If you experiment with it, you'll find that **CHR\$ a** is *rounded* to the nearest whole number; and if **a** is not in the range 0 to 255 then the program stops with error report **B integer out of range**.

3. Which of these two is the lesser?

```

"EVIL"
"evil"

```

4. Work out how to modify the program to set up user-defined graphics so that it uses **READ** and **DATA** statements instead of the **INPUT** statement.

CHAPTER

15

More about PRINT and INPUT

Summary

CLS

PRINT items: nothing at all

Expressions (numeric or string type): **TAB** numeric expression, **AT** numeric expression, numeric expression

PRINT separators: , ; ' "

INPUT items: variables (numeric or string type)

LINE string variable

Any **PRINT** item not beginning with a letter. (Tokens are not considered as beginning with a letter.)

Scrolling.

SCREEN\$

You have already seen **PRINT** used quite a lot, so you will have a rough idea of how it is used. Expressions whose values are printed are called **PRINT items**, and they are separated by commas or semicolons, which are called **PRINT separators**. A **PRINT** item can also be nothing at all, which is a way of explaining what happens when you use two commas in a row.

There are two more kinds of **PRINT** items, which are used to tell the computer not what, but where to print. For example **PRINT AT 11,16;"*"** prints a star in the middle of the screen.

AT line, column

moves the **PRINT** position (the place where the next item is to be printed) to the line and column specified. Lines are numbered from 0 (at the top) to 21, and columns from 0 (on the left) to 31.


SCREEN\$ is the reverse function to **PRINT AT**, and will tell you (within limits) what character is at a particular position on the screen. It uses line and column numbers in the same way as **PRINT AT**, but enclosed in brackets: for instance

PRINT SCREEN\$ (11,16)

will retrieve the star you printed in the paragraph above.

Characters taken from tokens print normally, as single characters, and spaces return as spaces. Lines drawn by **PLOT**, **DRAW** or **CIRCLE**, user-defined characters and graphics characters return as a null (empty) string, however. The same applies if **OVER** has been used to create a composite character.

You cannot normally **PRINT** or **PLOT** on the bottom two lines



TAB column

prints enough spaces to move the **PRINT** position to the column specified. It stays on the same line, or, if this would involve backspacing, moves on to the next one. Note that the computer reduces the column number 'modulo 32' (it divides by 32 and takes the remainder); so **TAB 33** means the same as **TAB 1**.

As an example,

```
PRINT TAB 30;1;TAB 12;"Contents"; AT 3,1;"CHAPTER";TAB
24;"page"
```

is how you might print out the heading of a contents page on page 1 of a book.

Try running this:

```
10 FOR n=0 TO 20
20 PRINT TAB 8*n;n;
30 NEXT n
```

This shows what is meant by the **TAB** numbers being reduced modulo 32.

For a more elegant example, change the 8 in line 20 to a 6.

Some small points:

(i) These new items are best terminated with semicolons, as we have done above. You can use commas (or nothing, at the end of the statement), but this means that after having carefully set up the **PRINT** position you immediately move it on again – not usually terribly useful.

(ii) You cannot print on the bottom two lines (22 and 23) on the screen because they are reserved for commands, **INPUT** data, reports and so on. References to 'the bottom line' usually mean line 21.

(iii) You can use **AT** to put the **PRINT** position even where there is already something printed; the old stuff will be obliterated when you print more.

Another statement connected with **PRINT** is **CLS**. This clears the whole screen, something that is also done by **CLEAR** and **RUN**.

When the printing reaches the bottom of the screen, it starts to scroll upwards rather like a typewriter. You can see this if you do

```
CLS: FOR n=1 TO 22: PRINT n: NEXT n
```

and then do

```
PRINT 99
```

a few times.

If the computer is printing out reams and reams of stuff, then it takes great care to make sure that nothing is scrolled off the top of the screen until you have had a chance to look at it properly. You can see this happening if you type

CLS: FOR n=1 TO 100: PRINT n: NEXT n

When it has printed a screen full, it will stop, writing **scroll?** at the bottom of the screen. You can now inspect the first 22 numbers at your leisure. When you have finished with them, press **y** (for 'yes') and the computer will give you another screen full of numbers. Actually, any key will make the computer carry on except **n** (for 'no'), **STOP** (**SYMBOL SHIFT** and **a**), or **SPACE** (the **BREAK** key). These will make the computer stop running the program with a report **D BREAK – CONT repeats**.

The **INPUT** statement can do much more than we have told you so far. You have already seen **INPUT** statements like

INPUT "How old are you?", age

in which the computer prints the caption **How old are you?** at the bottom of the screen, and then you have to type in your age.

In fact, an **INPUT** statement is made up of items and separators in exactly the same way as a **PRINT** statement is, so **How old are you?** and **age** are both **INPUT** items. **INPUT** items are generally the same as **PRINT** items, but there are some very important differences.

First, an obvious extra **INPUT** item is the variable whose value you are to type in – **age** in our example above. The rule is that if an **INPUT** item begins with a letter, it must be a variable whose value is to be input.

Second, this would seem to mean that you can't print out the values of variables as part of a caption; however, you can get round this by putting brackets round the variable. Any expression that starts with a letter must be enclosed in brackets if it is to be printed as part of a caption.

Any kind of **PRINT** item that is not affected by these rules is also an **INPUT** item. Here is an example to illustrate what's going on:

LET my age = INT (RND * 100): INPUT ("I am ";my age; ". ");"How old are you?", your age

my age is contained in brackets, so its value gets printed out. **your age** is not contained in brackets, so you have to type its value in.

Everything that an **INPUT** statement writes goes to the bottom part of the screen, which acts somewhat independently of the top half. In particular, its lines are numbered relative to the top line of the bottom half, even if this has moved up the actual television screen (which it does if you type lots and lots of **INPUT** data).

To see how **AT** works in **INPUT** statements, try running this:

**10 INPUT "This is line 1.",a\$; AT 0,0;"This is line 0.",a\$; AT 2,0;
"This is line 2.",a\$; AT 1,0;"This is still line 1.",a\$**

(just press **ENTER** each time it stops.) When **This is line 2.** is printed, the lower part of the screen moves up to make room for it; but the numbering moves up as well, so

that the lines of text keep their same numbers.

Now try this:

```
10 FOR n=0 TO 19: PRINT AT n,0;n;: NEXT n
20 INPUT AT 0,0;a$; AT 1,0;a$; AT 2,0;a$; AT 3,0;a$; AT 4,0;a$;
AT 5,0;a$;
```

As the lower part of the screen goes up and up, the upper part is undisturbed until the lower part threatens to write on the same line as the **PRINT** position. Then the upper part starts scrolling up to avoid this.

Another refinement to the **INPUT** statement that we haven't seen yet is called **LINE** input and is a different way of inputting string variables. If you write **LINE** before the name of a string variable to be input, as in

```
INPUT LINE a$
```

then the computer will not give you the string quotes that it normally does for a string variable, although it will pretend to itself that they are there. So if you type in

```
cat
```

as the **INPUT** data, **a\$** will be given the value **cat**. Because the string quotes do not appear on the string, you cannot delete them and type in a different sort of string expression for the **INPUT** data. Remember that you cannot use **LINE** for numeric variables.

The control characters **CHR\$ 22** and **CHR\$ 23** have effects rather like **AT** and **TAB**. They are rather odd as control characters, because whenever one is sent to the television to be printed, it must be followed by two more characters that do not have their usual effect: they are treated as numbers (their codes) to specify the line and column (for **AT**) or the tab position (for **TAB**). You will almost always find it easier to use **AT** and **TAB** in the usual way rather than the control characters, but they might be useful in some circumstances. The **AT** control character is **CHR\$ 22**. The first character after it specifies the line number and the second the column number, so that

```
PRINT CHR$ 22+CHR$ 1+CHR$ c;
```

has exactly the same effect as

```
PRINT AT 1,c;
```

This is so even if **CHR\$ 1** or **CHR\$ c** would normally have a different meaning (for instance if **c=13**); the **CHR\$ 22** before them overrides that.

The **TAB** control character is **CHR\$ 23** and the two characters after it are used to

give a number between 0 and 65535 specifying the number you would have in a **TAB** item:

```
PRINT CHR$ 23+CHR$ a+CHR$ b;
```

has the same effect as

```
PRINT TAB a+256*b;
```

You can use **POKE** to stop the computer asking you **scroll?** by doing

```
POKE 23692,255
```

every so often. After this it will scroll up 255 times before stopping with **scroll?**. As an example, try

```
10 FOR n=0 TO 10000  
20 PRINT n: POKE 23692,255  
30 NEXT n
```

and watch everything whizz off the screen!

Exercises

1. Try this program on some children, to test their multiplication tables.

```
10 LET m$=""  
20 LET a=INT (RND*12)+1: LET b=INT (RND*12)+1  
30 INPUT (m$) ' "what is ";(a);" * ";(b);"?" ;c  
100 IF c=a*b THEN LET m$="Right.": GO TO 20  
110 LET m$="Wrong. Try again.": GO TO 30
```

If they are perceptive, they might manage to work out that they do not have to do the calculation themselves. For instance, if the computer asks them to type the answer to $2*3$, all they have to type in is **2*3**.

One way of getting round this is to make them input strings instead of numbers. Replace **c** in line 30 by **c\$**, and in line 100 by **VAL c\$**, and insert a line

```
40 IF c$<> STR$ VAL c$ THEN LET m$="Type it properly, as  
a number.": GO TO
```

That will fool them. After a few more days, however, one of them may discover that they can get round this by rubbing out the string quotes and typing in **STR\$ (2*3)**. To stop up this loophole, you can replace **c\$** in line 30 by **LINE c\$**.

CHAPTER

16

Colours

Summary

**INK, PAPER, FLASH, BRIGHT, INVERSE, OVER
BORDER**

Run this program:

```

10 FOR m=0 TO 1: BRIGHT m
20 FOR n=1 TO 10
30 FOR c=0 TO 7
40 PAPER c: PRINT "  "; REM 4 coloured spaces
50 NEXT c: NEXT n: NEXT m
60 FOR m=0 TO 1: BRIGHT m: PAPER 7
70 FOR c=0 TO 3
80 INK c: PRINT c;" ";
90 NEXT c: PAPER 0
100 FOR c=4 TO 7
110 INK c: PRINT c;" ";
120 NEXT c: NEXT m
130 PAPER 7: INK 0: BRIGHT 0

```


This shows the eight colours (including white and black) and the two levels of brightness that the ZX Spectrum can produce on a colour television. (If your television is black and white, then you will just see various shades of grey.) Here is a list of them for reference; they are also written over the appropriate number keys.

- 0 – black
- 1 – blue
- 2 – red
- 3 – purple, or magenta
- 4 – green
- 5 – pale blue, technically called cyan
- 6 – yellow
- 7 – white

On a black and white television, these numbers are in order of brightness.

To use these colours properly, you need to understand a bit about how the picture is arranged.

The picture is divided up into 768 (24 lines of 32) positions where characters can be



printed, and each character is printed as an 8×8 square of dots like that above for **a**. This should remind you of the user-defined graphics in Chapter 14, where we had 0s for the white dots and 1s for the black dots.

The character position also has associated with it two colours: the *ink*, or foreground colour, which is the colour for the black dots in our square, and the *paper*, or background colour, which is used for the white dots. To start off with, every position has black ink and white paper so writing appears as black on white.

The character position also has a brightness (normal or extra bright) and something to say whether it flashes or not – flashing is done by swapping the ink and paper colours. This can all be coded into numbers, so a character position then has

- (i) an 8×8 square of 0s and 1s to define the shape of the character, with 0 for paper and 1 for ink,
- (ii) ink and paper colours, each coded into a number between 0 and 7,
- (iii) a brightness – 0 for normal, 1 for extra bright and
- (iv) a flash number – 0 for steady, 1 for flashing.

Note that since the ink and paper colours cover a whole character position, you cannot possibly have more than two colours in a given block of 64 dots. The same goes for the brightness and flash number: they refer to the whole character position, not individual dots. The colours, brightness and flash number at a given position are called *attributes*.

When you print something on the screen, you change the dot pattern at that position; it is less obvious, but still true, that you also change the attributes at that position. To start off with you do not notice this because everything is printed with black ink on white paper (and normal brightness and no flashing), but you can vary this with the **INK**, **PAPER**, **BRIGHT** and **FLASH** statements. Try

PAPER 5

and then print a few things: they will all appear on cyan paper, because as they are printed the paper colours at the positions they occupy are set to cyan (which has code 5).

The others work the same way, so after

	PAPER	number between 0 and 7	
	INK	number between 0 and 7	
or	BRIGHT	0 or 1	} Think of 0 as off and 1 as on
	FLASH	0 or 1	

any printing will set the corresponding attribute at all the character positions it uses. Try some of these out. You should now be able to see how the program at the beginning worked (remember that a space is a character that has **INK** and **PAPER** the same colour).

There are some more numbers you can use in these statements that have less direct effects.

8 can be used in all four statements, and means 'transparent' in the sense that the old attribute shows through. Suppose, for instance, that you do

PAPER 8

No character position will ever have its paper colour set to 8 because there is no such colour; what happens is that when a position is printed on, its paper colour is left the same as it was before. **INK 8**, **BRIGHT 8** and **FLASH 8** work the same way for the other attributes.

9 can be used only with **PAPER** and **INK**, and means 'contrast'. The colour (ink or paper) that you use it with is made to contrast with the other by being made white if the other is a dark colour (black, blue, red or magenta), and black if the other is a light colour (green, cyan, yellow or white).

Try this by doing

INK 9: FOR c=0 TO 7: PAPER c: PRINT c: NEXT c

A more impressive display of its power is to run the program at the beginning to make coloured stripes, and then doing

**INK 9: PAPER 8: PRINT AT 0,0:: FOR n=1 TO 1000: PRINT n::
NEXT n**

The ink colour here is always made to contrast with the old paper colour at each position.

Colour television relies on the rather curious fact that the human eye can only really see three colours – the primary colours, blue, red and green. The other colours are mixtures of these. For instance, magenta is made by mixing blue with red – which is why its code, 3, is the sum of the codes for blue and red.

To see how all eight colours fit together, imagine three rectangular spotlights, coloured blue, red and green, shining at not quite the same place on a piece of white paper in the dark. Where they overlap you will see mixtures of colours, as shown by this program (note that ink spaces are obtained by using either **SHIFT** with **8** when in G mode):


```

10 BORDER 0: PAPER 0: INK 7: CLS
20 FOR a=1 TO 6
30 PRINT TAB 6; INK 1; "██████████": REM 18 ink
   squares
40 NEXT a
50 LET dataline=200
60 GO SUB 1000
70 LET dataline=210
80 GO SUB 1000
90 STOP
200 DATA 2,3,7,5,4
210 DATA 2,2,6,4,4
1000 FOR a=1 TO 6
1010 RESTORE dataline
1020 FOR b=1 TO 5
1030 READ c: PRINT INK c;"██████████"; REM 6 ink squares
1040 NEXT b: PRINT : NEXT a
1050 RETURN

```

There is a function called **ATTR** that finds out what the attributes are at a given position on the screen. It is a fairly complicated function, so it has been relegated to the end of this chapter.

There are two more statements, **INVERSE** and **OVER**, which control not the attributes, but the dot pattern that is printed on the screen. They use the numbers 0 for off and 1 for on in the same way as **FLASH** and **BRIGHT** do, but those are the only possibilities. If you do **INVERSE 1**, then the dot patterns printed will be the inverse of their usual form: paper dots will be replaced by ink dots and vice versa. Thus **a** would be printed as



If (as at switch-on) we have black ink and white paper, then this **a** will appear as white on black – but we still have black ink and white paper at that character position. It is the dots that have changed.

The statement

OVER 1

sets into action a particular sort of overprinting. Normally when something is written into a character position it completely obliterates what was there before; but now the new character will simply be added in on top of the old one (but see Exercise 1). This can be particularly useful for writing composite characters, like letters with accents on them, as in this program to print out German letters – an 'o' with an umlaut above it. (Do **NEW** first.)

```
10 OVER 1
20 FOR n=1 TO 32
30 PRINT "o"; CHR$ 8;"";
40 NEXT n
```

(notice the control character **CHR\$ 8** which backs up one space.)

There is another way of using **INK**, **PAPER** and so on which you will probably find more useful than having them as statements. You can put them as items in a **PRINT** statement (followed by ;), and they then do exactly the same as they would have done if they had been used as statements on their own, except that their effect is only temporary: it lasts as far as the end of the **PRINT** statement that contains them. Thus if you type

```
PRINT PAPER 6;"x";: PRINT "y"
```

then only the x will be on yellow.

INK and the rest when used as statements do not affect the colours of the lower part of the screen, where commands and **INPUT** data are typed in. The lower part of the screen uses the colour of the border for its paper colour and code 9 for contrast for its **INK** colour, has flashing off, and everything at normal brightness. You can change the border colour to any of the eight normal colours (not 8 or 9) using statement

BORDER colour

When you type in **INPUT** data, it follows this rule of using contrasting ink on border coloured paper; but you can change the colour of the captions written by the computer by using **INK** and **PAPER** (and so on) items in the **INPUT** statement, just as you would in a **PRINT** statement. Their effect lasts either to the end of the statement, or until some **INPUT** data is typed in, whichever comes first. Try

```
INPUT FLASH 1; INK 1;"What is your number?";n
```

There is one more way of changing the colours by using control characters – rather like the control characters for **AT** and **TAB** in Chapter 15.

CHR\$ 16 corresponds to **INK**
CHR\$ 17 corresponds to **PAPER**
CHR\$ 18 corresponds to **FLASH**
CHR\$ 19 corresponds to **BRIGHT**
CHR\$ 20 corresponds to **INVERSE**
CHR\$ 21 corresponds to **OVER**

These are each followed by one character that shows a colour by its code: so (for instance)

PRINT CHR\$ 16+CHR\$ 9; . . .

has the same effect as

PRINT INK 9; . . .

On the whole, you would not bother to use these control characters because you might just as well use the colour items. However, one very useful thing you can do with them is put them in programs: this results in different parts being listed in different colours, to set them apart from each other or even just to look pretty. You must put them in after the line number, or they will just get lost.

To get these into the program, you have to enter them from the keyboard, mostly using extended mode with the digits.

The digits 0 to 7 set the corresponding colour – ink if **CAPS SHIFT** is also pressed, paper if it is not. More precisely, if you are in E mode and you press a digit (let us say 6 for yellow; at any rate it has to be between 0 and 7 – not 8 or 9) then two characters are inserted: first **CHR\$ 17** for **PAPER**, and **CHR\$ 6** meaning 'set it to yellow'. If you had been pressing **CAPS SHIFT** when you pressed the digit, you would have got **CHR\$ 16** meaning 'set ink colour' instead of **CHR\$ 17**.

Since these are two characters you can get some odd effects when you rub them out – you must press **DELETE** twice, and after the first time you will often get a question mark or even odder things appearing. Do not worry; just press **DELETE** again.

◆ and ◆ can also behave strangely while the cursor is moving past the control characters.

Still in extended mode,

8 gives **CHR\$ 19** and **CHR\$ 0** for normal brightness

9 gives **CHR\$ 19** and **CHR\$ 1** for extra brightness

CAPS SHIFT with 8 gives **CHR\$ 18** and **CHR\$ 0** for no flashing

CAPS SHIFT with 9 gives **CHR\$ 18** and **CHR\$ 1** for flashing

There are a couple more in ordinary (L) mode:

CAPS SHIFT with 3 gives **CHR\$ 20** and **CHR\$ 0** for normal characters
CAPS SHIFT with 4 gives **CHR\$ 20** and **CHR\$ 1** for inverse characters

To summarize, here is a complete description of the top row on the keyboard:

		MODE		SHIFT																		
E	SYMBOL	DEF FN	FN	LINE	OPEN #	CLOSE #	MOVE	ERASE	POINT	CAT	FORMAT	NONE	Paper blue	Paper red	Paper magenta	Paper green	Paper cyan	Paper yellow	Paper white	Normal brightness	Extra bright	Paper black
	CAPS	Ink blue	Ink red	Ink magenta	Ink green	Ink cyan	Ink yellow	Ink white	Flash off	Flash on	Ink black											
G	SYMBOL	DEF FN	FN	LINE	OPEN #	CLOSE #	MOVE	ERASE	POINT	CAT	FORMAT	NONE	EITHER	NONE	EDIT	CAPS LOCK	TRUE VIDEO	INVERSE VIDEO	EXIT GRAPHICS	EXIT GRAPHICS	DELETE	
	CAPS	Ink blue	Ink red	Ink magenta	Ink green	Ink cyan	Ink yellow	Ink white	Flash off	Flash on	Ink black											
K,L OR C	SYMBOL	DEF FN	FN	LINE	OPEN #	CLOSE #	MOVE	ERASE	POINT	CAT	FORMAT	NONE	i	@	#	\$	%	&	'	()	—
	CAPS	Ink blue	Ink red	Ink magenta	Ink green	Ink cyan	Ink yellow	Ink white	Flash off	Flash on	Ink black											

The **ATTR** function has the form

ATTR (line column)

Its two arguments are the line and column numbers that you would use in an **AT** item, and its result is a number that shows the colours and so on at the corresponding character position on the television screen. You can use this as freely in expressions as you can any other function.

The number that is the result is the sum of four other numbers as follows:

128 if the character position is flashing, 0 if it is steady

64 if the character position is bright, 0 if it is normal

8* the code for the paper colour

the code for the ink colour

For instance, if the character position is flashing and normal with yellow paper and blue ink then the four numbers that we have to add together are 128, 0, 8*6=48 and 1, making 177 altogether. Test this with

PRINT AT 0,0; FLASH 1; PAPER 6; INK 1;" "; ATTR (0,0)

Exercises

1. Try

PRINT "B"; CHR\$ 8; OVER 1;"I";

Where the *I* has cut through the B, it has left a white dot. This is the way overprinting works on the ZX Spectrum: two papers or two inks give a paper, one of each gives an ink. This has the interesting property that if you overprint with the same thing twice you get back what you started off with. If you now type

PRINT CHR\$ 8; OVER 1;"I"

why do you recover an unblemished **B**?

2. Type

PAPER 0: INK 0

– isn't it just as well that these don't affect the lower part of the screen?

Now type

BORDER 0

and see how well the computer looks after you!

3. Run this program:

```

10 POKE 22527+RND*704, RND*127
20 GO TO 10

```

Never mind how this works; it is changing the colours of squares on the television screen and the **RND**s should ensure that this happens randomly. The diagonal stripes that you eventually see are a manifestation of the hidden pattern in **RND** – the pattern that makes it pseudorandom instead of truly random.

4. Type or **LOAD** in the chess piece characters in Chapter 14, and then type in this program which draws a diagram of a chess position using them.

```

5 REM draw blank board
10 LET bb=1: LET bw=2: REM red and blue for board
15 PAPER bw: INK bb: CLS
20 PLOT 79,128: REM border
30 DRAW 65,0: DRAW 0,-65
40 DRAW -65,0: DRAW 0,65
50 PAPER bb
60 REM board
70 FOR n=0 TO 3: FOR m=0 TO 3
80 PRINT AT 6+2*n, 11+2*m;" "
90 PRINT AT 7+2*n, 10+2*m;" "
100 NEXT m: NEXT n
110 PAPER 8
120 LET pw=6: LET pb=5: REM colours of white and black pieces
200 DIM b$(8,8): REM positions of pieces
205 REM set up initial positions
210 LET b$(1)="rnbqkbnr"
220 LET b$(2)="pppppppp"
230 LET b$(7)="PPPPPPPP"
240 LET b$(8)="RNBQKBNR"
300 REM display board
310 FOR n=1 TO 8: FOR m=1 TO 8
320 LET bc=CODE b$(n,m): INK pw
325 IF bc=CODE" " THEN GO TO 350: REM space
330 IF bc>CODE"Z" THEN INK pb: LET bc=bc-32: REM lower
case for black
340 LET bc=bc+79: REM convert to graphics
350 PRINT AT 5+n, 9+m; CHR$ bc
360 NEXT m: NEXT n
400 PAPER 7: INK 0

```


CHAPTER

17

Graphics

Summary

PLOT, DRAW, CIRCLE POINT

pixels

In this chapter we shall see how to draw pictures on the ZX Spectrum. The part of the screen you can use has 22 lines and 32 columns, making $22 \times 32 = 704$ character positions. As you may remember from Chapter 16, each of these character positions is made of an 8 by 8 square of dots, and these are called pixels (picture elements).

A pixel is specified by two numbers, its *coordinates*. The first, its *x coordinate*, says how far it is across from the extreme left-hand column. (Remember, x is a cross), the second, its *y coordinate*, says how far it is up from the bottom (wise up). These coordinates are usually written as a pair in brackets, so (0,0), (255,0), (0,175) and (255,175) are the bottom left-, bottom right-, top left- and top right-corners.

The statement

PLOT x coordinate, y coordinate

inks in the pixel with these coordinates, so this measles program

```
10 PLOT INT (RND*256), INT (RND*176): INPUT a$: GO TO 10
```

plots a random point each time you press **ENTER**.

Here is a rather more interesting program. It plots a graph of the function **SIN** (a sine wave) for values between 0 and 2π .

```
10 FOR n=0 TO 255  
20 PLOT n,88+80*SIN (n/128*PI)  
30 NEXT n
```

This next program plots a graph of **SQR** (part of a parabola) between 0 and 4:

```
10 FOR n=0 TO 255  
20 PLOT n,80*SQR (n/64)  
30 NEXT n
```

Notice that pixel coordinates are rather different from the line and column in an **AT** item. You may find the diagram in Chapter 15 useful when working out pixel coordinates and line and column numbers.

To help you with your pictures, the computer will draw straight lines, circles and parts of circles for you, using the **DRAW** and **CIRCLE** statements.

The statement **DRAW** to draw a straight line takes the form

DRAW x,y

The starting place of the line is the pixel where the last **PLOT**, **DRAW** or **CIRCLE** statement left off (this is called the **PLOT** position; **RUN**, **CLEAR**, **CLS** and **NEW** reset it to the bottom left hand corner, at $(0,0)$), and the finishing place is x pixels to the right of that and y pixels up. The **DRAW** statement on its own determines the length and direction of the line, but not its starting point.

Experiment with a few **PLOT** and **DRAW** commands, for instance

```
PLOT 0,100: DRAW 80,-35
PLOT 90,150: DRAW 80,-35
```

Notice that the numbers in a **DRAW** statement can be negative, although those in a **PLOT** statement can't.

You can also plot and draw in colour, although you have to bear in mind that colours always cover the whole of a character position and cannot be specified for individual pixels. When a pixel is plotted, it is set to show the full ink colour, and the whole of the character position containing it is given the current ink colour. This program demonstrates this:

```
10 BORDER 0: PAPER 0: INK 7: CLS : REM black out screen
20 LET x1=0: LET y1=0: REM start of line
30 LET c=1: REM for ink colour, starting blue
40 LET x2=INT (RND*256): LET y2=INT (RND*176): REM
    random finish of line
50 DRAW INK c;x2-x1,y2-y1
60 LET x1=x2: LET y1=y2: REM next line starts where last one
    finished
70 LET c=c+1: IF c=8 THEN LET c=1: REM new colour
80 GO TO 40
```

The lines seem to get broader as the program goes on, and this is because a line changes the colours of all the inked in pixels of all the character positions that it passes through. Note that you can embed **PAPER**, **INK**, **FLASH**, **BRIGHT**, **INVERSE** and **OVER** items in a **PLOT** or **DRAW** statement just as you could with **PRINT** and **INPUT**. They go between the key word and the coordinates, and are terminated by either semicolons or commas.

An extra frill with **DRAW** is that you can use it to draw parts of circles instead of straight lines, by using an extra number to specify an angle to be turned through: the form is

```
DRAW x,y,a
```


x and y are used to specify the finishing point of the line just as before and a is the number of radians that it must turn through as it goes – if a is a positive it turns to the left, while if a is a negative it turns to the right. Another way of seeing a is as showing the fraction of a complete circle that will be drawn: a complete circle is 2π radians, so

if $a=\pi$ it will draw a semicircle, if $a=0.5*\pi$ a quarter of a circle, and so on.

For instance suppose $a=\pi$. Then whatever values x and y take, a semicircle will be drawn. Run

10 PLOT 100,100: DRAW 50,50, PI

which will draw this:



The drawing starts off in a south-easterly direction, but by the time it stops it is going north-west: in between it has turned round through 180 degrees, or π radians (the value of a).

Run the program several times, with **PI** replaced by various other expressions – e.g. **-PI, PI/2, 3*PI/2, PI/4, 1, 0**.

The last statement in this chapter is the **CIRCLE** statement, which draws an entire circle. You specify the coordinates of the centre and the radius of the circle using

CIRCLE x coordinate, y coordinate, radius

Just as with **PLOT** and **DRAW**, you can put the various sorts of colour items in at the beginning of a **CIRCLE** statement.

The **POINT** function tells you whether a pixel is ink or paper colour. It has two arguments, the coordinates of the pixel (and they must be enclosed in brackets); and its result is 0 if the pixel is paper colour, 1 if it is ink colour. Try

CLS : PRINT POINT (0,0): PLOT 0,0: PRINT POINT (0,0)

Type

PAPER 7: INK 0

and let us investigate how **INVERSE** and **OVER** work inside a **PLOT** statement. These two affect just the relevant pixel, and not the rest of the character positions. They are normally off (0) in a **PLOT** statement, so you only need to mention them to turn them on (1).

Here is a list of the possibilities for reference:

PLOT; – this is the usual form. It plots an ink dot, i.e. sets the pixel to show the ink colour.

PLOT INVERSE 1; – this plots a dot of ink eradicator, i.e. it sets the pixel to show the paper colour.

PLOT OVER 1; – this changes the pixel over from whatever it was before: so if it was ink colour it becomes paper colour, and vice versa.

PLOT INVERSE 1; OVER 1; – this leaves the pixel exactly as it was before; but note that it also changes the **PLOT** position, so you might use it simply to do that.

As another example of using the **OVER** statement fill the screen up with writing using black on white, and then type

PLOT 0,0: DRAW OVER 1;255,175

This will draw a fairly decent line, even though it has gaps in it wherever it hits some writing. Now do exactly the same command again. The line will vanish without leaving any traces whatsoever. This is the great advantage of **OVER 1**. If you had drawn the line using

PLOT 0,0: DRAW 255,175

and erased it using

PLOT 0,0: DRAW INVERSE 1;255,175

then you would also have erased some of the writing.

Now try

PLOT 0,0: DRAW OVER 1;250,175

and try to undraw it by

DRAW OVER 1;–250,–175

This doesn't quite work, because the pixels the line uses on the way back are not quite the same as the ones that it used on the way down. You must undraw a line in exactly the same direction as you drew it.

One way to get unusual colours is to speckle two normal ones together in a single square, using a user-defined graphic. Run this program:

```
1000 FOR n=0 TO 6 STEP 2  
1010 POKE USR "a"+n, BIN 01010101: POKE USR "a"+n+1,  
      BIN 10101010  
1020 NEXT n
```

which gives the user-defined graphic corresponding to a chessboard pattern. If you print this character (graphics mode, then **a**) in red ink on yellow paper, you will find it

gives a reasonably acceptable orange.

Exercises

1. Play about with **PAPER**, **INK**, **FLASH** and **BRIGHT** items in a **PLOT** statement. These are the parts that affect the whole of the character position containing the pixel. Normally it is as though the **PLOT** statement had started off

PLOT PAPER 8; FLASH 8; BRIGHT 8; . . .

and only the ink colour of a character position is altered when something is plotted there, but you can change this if you want.

Be especially careful when using colours with **INVERSE 1**, because this sets the pixel to show the paper colour, but changes the ink colour and this might not be what you expect.

2. Try to draw circles using **SIN** and **COS** (if you have read Chapter 10, try to work out how). Run this:

```
10 FOR n=0 TO 2*PI STEP PI /180
20 PLOT 100+80*COS n,87+80*SIN n
30 NEXT n
40 CIRCLE 150,87,80
```

You can see that the **CIRCLE** statement is much quicker, even if less accurate.

3. Try

CIRCLE 100,87,80: DRAW 50,50

You can see from this that the **CIRCLE** statement leaves the **PLOT** position at a rather indeterminate place – it is always somewhere about half way up the right hand side of the circle. You will usually need to follow the **CIRCLE** statement with a **PLOT** statement before you do any more drawing.

4. Here is a program to draw the graph of almost any function. It first asks you for a number **n**; it will plot the graph for values from **-n** to **+n**. It then asks you for the function itself, input as a string. The string should be an expression using **x** as the argument of the function.

```

10 PLOT 0,87: DRAW 255,0
20 PLOT 127,0: DRAW 0,175
30 INPUT s,e$
35 LET t=0
40 FOR f=0 TO 255
50 LET x=(f-128)*s/128: LET y=VAL e$
60 IF ABS y>87 THEN LET t=0: GO TO 100
70 IF NOT t THEN PLOT f,y+88: LET t=1: GO TO 100
80 DRAW 1,y-old y
100 LET old y=INT (y+.5)
110 NEXT f

```

Run it, and, as an example, type in **10** for the number **n** and **10*TAN x** for the function. It will plot a graph of $\tan x$ as x ranges from -10 to $+10$.

CHAPTER

18

Motion

Summary

PAUSE, INKEY\$, PEEK

Quite often you will want to make the program take a specified length of time, and for this you will find the **PAUSE** statement useful.

PAUSE n

stops computing and displays the picture for n frames of the television (at 50 frames per second in Europe or 60 in America). n can be up to 65535, which gives you just under 22 minutes; if $n=0$ then it means '**PAUSE** for ever'.

A pause can always be cut short by pressing a key (note that a **CAPS SHIFTED** space will cause a break as well). You have to press the key down after the pause has started.

This program works the second hand of a clock:

```

10 REM First we draw the clock face
20 FOR n=1 TO 12
30 PRINT AT 10-10*COS (n/6*PI),16+10*SIN (n/6*PI);n
40 NEXT n
50 REM Now we start the clock
60 FOR t=0 TO 200000: REM t is the time in seconds
70 LET a=t/30*PI : REM a is the angle of the second hand in
   radians
80 LET sx=80*SIN a: LET sy=80*COS a
200 PLOT 128,88: DRAW OVER 1;sx,sy: REM draw second hand
210 PAUSE 42
220 PLOT 128,88: DRAW OVER 1;sx,sy: REM erase second hand
400 NEXT t

```

This clock will run down after about 55.5 hours because of line 60, but you can easily make it run longer. Note how the timing is controlled by line 210. You might expect **PAUSE 50** to make it tick one a second, but the computing takes a bit of time as well and has to be allowed for. This is best done by trial and error, timing the computer clock against a real one, and adjusting line 210 until they agree. (You can't do this very accurately; an adjustment of one frame in one second is 2% or half an hour in a day.)

There is a much more accurate way of measuring time. This uses the contents of certain memory locations. The data stored is retrieved by using **PEEK**. Chapter 25 explains what we're looking at in detail. The expression used is

(65536*PEEK 23674+256*PEEK 23673+PEEK 23672)/50

This gives the number of seconds since the computer was turned on (up to about 3 days and 21 hours, when it goes back to 0).

Here is a revised clock program to make use of this:

```

10 REM First we draw the clock face
20 FOR n=1 TO 12
30 PRINT AT 10-10*COS (n/6*PI),16+10*SIN (n/6*PI);n
40 NEXT n
50 DEF FN t()=INT ((65536*PEEK 23674+256*PEEK 23673+
    PEEK 23672)/50): REM number of seconds since start
100 REM Now we start the clock
110 LET t1=FN t()
120 LET a=t1/30*PI : REM a is the angle of the second hand in
    radians
130 LET sx=72*SIN a: LET sy=72*COS a
140 PLOT 131,91: DRAW OVER 1;sx,sy: REM draw hand
200 LET t=FN t()
210 IF t<=t1 THEN GO TO 200: REM wait until time for next
    hand
220 PLOT 131,91: DRAW OVER 1;sx,sy: REM rub out old hand
230 LET t1=t: GO TO 120

```

The internal clock that this method uses should be accurate to about .01% as long as the computer is just running its program, or 10 seconds per day; but it stops temporarily whenever you do **BEEP**, or a cassette tape operation, or use the printer or any of the other extra pieces of equipment you can use with the computer. All these will make it lose time.

The numbers **PEEK 23674**, **PEEK 23673** and **PEEK 23672** are held inside the computer and used for counting in 50ths of a second. Each is between 0 and 255, and they gradually increase through all the numbers from 0 to 255; after 255 they drop straight back to 0.

The one that increases most often is **PEEK 23672**. Every 1/50 second it increases by 1. When it is at 255, the next increase takes it to 0, and at the same time it nudges **PEEK 23673** by up to 1. When (every 256/50 seconds) **PEEK 23673** is nudged from 255 to 0, it in turn nudges **PEEK 23674** up by 1. This should be enough to explain why the expression above works.

Now, consider carefully: suppose our three numbers are 0 (for **PEEK 23674**), 255 (for **PEEK 23673**) and 255 (for **PEEK 23672**). This means that it is about 21 minutes after switch-on – our expression ought to yield

$$(65536*0+256*255+255)/50=1310.7$$

But there is a hidden danger. The next time there is a 1/50 second count, the three numbers will change to 1, 0 and 0. Every so often, this will happen when you are half way through evaluating the expression: the computer would evaluate **PEEK 23674** as

0, but then change the other two to 0 before it can peek them. The answer would then be

$$(65536*0+256*0+0)/50=0$$

which is hopelessly wrong.

A simple rule to avoid this problem is *evaluate the expression twice in succession and take the larger answer.*

If you look carefully at the program above you can see that it does this implicitly. Here is a trick to apply the rule. Define functions

```
10 DEF FN m(x,y)=(x+y+ABS (x-y))/2: REM the larger of x and y
20 DEF FN u()=(65536*PEEK 23674+256*PEEK 23673+PEEK
23672)/50: REM time, may be wrong
30 DEF FN t()=FN m(FN u(), FN u()): REM time, right
```

You can change the three counter numbers so that they give the real time instead of the time since the computer was switched on. For instance, to set the time at 10.00am, you work out that this is $10*60*60*50=1800000$ fiftieths of a second, and that

$$1800000=65536*27+256*119+64$$

To set the three numbers to 27, 119 and 64, you do

```
POKE 23674,27: POKE 23673,119: POKE 23672,64
```

In countries with mains frequencies of 60 Hertz these programs must replace '50' by '60' where appropriate.

The function **INKEY\$** (which has no argument) reads the keyboard. If you are pressing exactly one key (or a **SHIFT** key and just one other key) then the result is the character that that key gives in L mode; otherwise the result is the empty string.

Try this program, which works like a typewriter.

```
10 IF INKEY$ <>" " THEN GO TO 10
20 IF INKEY$ =" " THEN GO TO 20
30 PRINT INKEY$;
40 GO TO 10
```

Here line 10 waits for you to lift your finger off the keyboard and line 20 waits for you to press a new key.

Remember that unlike **INPUT**, **INKEY\$** doesn't wait for you. So you don't type **ENTER**, but on the other hand if you don't type anything at all then you've missed your chance.

Exercises

1. What happens if you miss out line 10 in the typewriter program?
2. Another way of using **INKEY\$** is in conjunction with **PAUSE**, as in this alternative typewriter program.

```
10 PAUSE 0  
20 PRINT INKEY$;  
30 GO TO 10
```

To make this work, why is it essential that a pause should not finish if it finds you already pressing a key when it starts?

3. Adapt the second hand program so that it also shows minute and hour hands, drawing them every minute. If you're feeling ambitious, arrange so that every quarter of an hour it puts on some kind of show – you could produce the Big Ben chimes with **BEEP**. (See next chapter.)
4. (For sadists.) Try this:

```
10 IF INKEY$ = "" THEN GO TO 10  
20 PRINT AT 11,14;"OUCH!"  
30 IF INKEY$ <> "" THEN GO TO 30  
40 PRINT AT 11,14;" "  
50 GO TO 10
```

CHAPTER

19

BEEP

Summary BEEP


If you haven't already discovered that the ZX Spectrum has a loudspeaker built into it, read the Introductory booklet before carrying on.

The loudspeaker is sounded by using the **BEEP** statement,

BEEP duration, pitch

where, as usual, 'duration' and 'pitch' represent any numerical expressions. The duration is given in seconds, and the pitch is given in semitones above middle C – using negative numbers for notes below middle C.

Here is a diagram to show the pitch values of all the notes in one octave on the piano:



To get higher or lower notes, you have to add or subtract 12 for each octave that you go up or down.

If you have a piano in front of you when you are programming a tune, this diagram will probably be all that you need to work out the pitch values. If, however, you are transcribing straight from some written music, then we suggest that you draw a diagram of the staff with the pitch value written against each line and space, taking the key into account.

For example, type:

```

10 PRINT "Frere Gustav"
20 BEEP 1,0: BEEP 1,2: BEEP .5,3: BEEP .5,2: BEEP 1,0
30 BEEP 1,0: BEEP 1,2: BEEP .5,3: BEEP .5,2: BEEP 1,0
40 BEEP 1,3: BEEP 1,5: BEEP 2,7
50 BEEP 1,3: BEEP 1,5: BEEP 2,7
60 BEEP .75,7: BEEP .25,8: BEEP .5,7: BEEP .5,5: BEEP .5,3:
   BEEP .5,2: BEEP 1,0
70 BEEP .75,7: BEEP .25,8: BEEP .5,7: BEEP .5,5: BEEP .5,3:
   BEEP .5,2: BEEP 1,0
80 BEEP 1,0: BEEP 1,-5: BEEP 2,0
90 BEEP 1,0: BEEP 1,-5: BEEP 2,0

```


(You will probably want to give **crotchet** and **key** shorter names.)

By giving **crotchet** appropriate values, you can easily vary the speed of the piece.

Remember that because there is only one loudspeaker in the computer you can only play one note at a time, so you are restricted to unharmonized tunes. If you want any more you must sing it yourself.

Try programming tunes in for yourself – start off with fairly simple ones like ‘Three Blind Mice’. If you have neither piano nor written music, get hold of a very simple instrument like a tin whistle or a recorder, and work the tunes out on that. You could make a chart showing the pitch value for each note that you can play on this instrument.

Type:

```
FOR n=0 TO 1000: BEEP .5,n: NEXT n
```

This will play notes as high as it can, and then stop with error report **B integer out of range**. You can print out n to find out how high it did actually get.

Try the same thing, but going down into the low notes. The very lowest notes will just sound like clicks; in fact the higher notes are also made of clicks in the same way, but faster, so that the ear cannot distinguish them.

Only the middle range of notes are really any good for music; the low notes sound too much like clicks, and the high notes are thin and tend to warble a bit.

Type in this program line:

```
10 BEEP .5,0: BEEP .5,2: BEEP .5,4: BEEP .5,5: BEEP .5,7:  
BEEP .5,9: BEEP .5,11: BEEP .5,12: STOP
```

This plays the scale of C major, which uses all the white notes on the piano from middle C to the next C up. The way this scale is tuned is exactly the same as on a piano, and is called even-tempered tuning because the pitch interval of a semitone is the same all the way up the scale. A violinist, however, would play the scale very slightly differently, adjusting all the notes to make them sound more pleasing to the ear. He can do this just by moving his fingers very slightly up or down the string in a way that a pianist can't.

The natural scale, which is what the violinist plays, comes out like this:

```
20 BEEP .5,0: BEEP .5,2.039: BEEP .5,3.86: BEEP .5,4.98:  
BEEP .5,7.02: BEEP .5,8.84: BEEP .5,10.88: BEEP .5,12: STOP
```

You may or may not be able to detect any difference between these two; some people can. The first noticeable difference is that the third note is slightly flatter in the naturally tempered scale. If you are a real perfectionist, you might like to program your tunes to use this natural scale instead of the even-tempered one. The disadvantage is that although it works perfectly in the key of C, in other keys it works less well – they all have their own natural scales – and in some keys it works very badly indeed. The even-tempered scale is only slightly off, and works equally well in all keys.

This is less of a problem on the computer, of course, because you can use the trick of adding on a variable **key**.

Some music – notably Indian music – uses intervals of pitch smaller than a semitone. You can program these into the **BEEP** statement without any trouble; for instance the quartertone above middle C has a pitch value of .5.

You can make the keyboard beep instead of clicking by

POKE 23609,255

The second number in this determines the length of the beep (try various values between 0 and 255). When it is 0, the beep is so short that it sounds like a soft click.

If you are interested in doing more with sound from the Spectrum, like hearing the sound that **BEEP** makes on something other than the internal speaker, you will find that the signal is present on both the 'MIC' and the 'EAR' sockets. It will be at a higher level on the 'EAR' socket, but otherwise they are the same. You may use this to connect an earphone or a pair of headphones to your Spectrum. This will not cut out the internal loudspeaker. If you are really keen to make a lot of noise you could connect it up to an amplifier – the 'MIC' socket will probably give about the right level – or you could record the sound onto tape and get the Spectrum to play along with itself.

You will not damage the Spectrum even if you short-circuit the 'MIC' or 'EAR' sockets, so experiment to find which gives the best output for what you want to do.

Exercise

1. Rewrite the Mahler program so that it uses **FOR** loops to repeat the bars.

Program the computer so that it plays not only the funeral march, but also the rest of Mahler's first symphony.

CHAPTER

20

Tape storage

Summary

LOAD, SAVE, VERIFY, MERGE

The basic methods for using the cassette recorder to **SAVE**, **LOAD** and **VERIFY** programs are given in the Introductory booklet. This section should be read, and the procedures tried out before reading any further here.

We have seen that **LOAD** deletes the old program and variables in the computer before loading in the new ones from tape; there is another statement, **MERGE**, that does not. **MERGE** only deletes an old program line or variable if it has to because there is a new one with the same line number or name. Type in the 'dice' program in Chapter 11 and save it on tape, as "**dice**". Now enter and run the following:

```
1 PRINT 1
2 PRINT 2
10 PRINT 10
20 LET x=20
```

and then proceed as for the verification, but replacing **VERIFY "dice"** with

```
MERGE "dice"
```

If you list the program you can see that lines 1 and 2 have survived, but lines 10 and 20 have been replaced by those from the dice program. **x** has also survived (try **PRINT x**).

You have now seen simple forms of the four statements used with the cassette tape:

SAVE records the program and variables on to cassette.

VERIFY checks the program and variables on cassette against those already in the computer.

LOAD clears the computer of all its program and variables, and replaces them with new ones read in from cassette.

MERGE is like **LOAD** except that it does not clear out an old program line or variable unless it has to because its line number or name is the same as that of a new one from cassette.

In each of these, the keyword is followed by a string: for **SAVE** this provides a name for the program on tape, while for the other three it tells the computer which program to search for. While it is searching, it prints up the name of each program it comes across. There are a couple of twists to all this.

For **VERIFY**, **LOAD** and **MERGE** you can provide the empty string as the name to search for: then the computer does not care about the name, but takes the first program it comes across.

something you have made up for yourself. It is shown using the word **CODE**, as in

SAVE "picture" CODE 16384,6912

The unit of storage in memory is the *byte* (a number between 0 and 255), and each byte has an *address* (which is a number between 0 and 65535). The first number after **CODE** is the address of the first byte to be stored on tape, and the second is the number of bytes to be stored. In our case, 16384 is the address of the first byte in the display file (which contains the television picture) and 6912 is the number of bytes in it, so we are saving a copy of the television screen – try it. The name **"picture"** works just like the names for programs.

To load it back, use

LOAD "picture" CODE

You can put numbers after **CODE** in the form

LOAD name CODE start, length

Here *length* is just a safety measure; when the computer has found the bytes on tape with the right name, it will still refuse to load them in if there are more than *length* of them – since there is obviously more data than you expected it could otherwise overwrite something you had not intended to be overwritten. It gives the error report **R Tape loading error**. You can miss out *length*, and then the computer will read in the bytes however many there are.

Start shows the address where the first byte is to be loaded back to – this can be different from the address it was saved from, although if they are the same you can miss out *start* in the **LOAD** statement.

CODE 16384,6912 is so useful for saving and loading the picture that you can replace it with **SCREEN\$** – for instance,

SAVE "picture" SCREEN\$

LOAD "picture" SCREEN\$

This is a rare case for which **VERIFY** will not work – **VERIFY** writes up the names of what it finds on tape, so that by the time it gets round to the verification the display file has been changed and the verification fails. In all other cases you should use **VERIFY** whenever you use **SAVE**.

Below, is a complete summary of the four statements used in this chapter.

Name stands for any string expression, and refers to the name under which the information is stored on cassette. It should consist of ASCII printing characters, of which only the first 10 are used.

There are four sorts of information that can be stored on tape: program and variables (together), number arrays, character arrays, and straight bytes.

When **VERIFY**, **LOAD** and **MERGE** are searching the tape for information with a given name and of a given sort, they print up on the screen the sort and name of all the information they find. The sort is shown by 'Program:', 'Number array:', 'Character array:' or 'Bytes:'. If *name* was the empty string, they take the first lot of information of the right sort, regardless of its name.

SAVE

Saves information on tape under the given name. Error F occurs when name is empty or has 11 or more characters.

SAVE always puts up a message **Start tape, then press any key**, and waits for a key to be pressed before saving anything.

1. Program and variables:

SAVE name **LINE** line number

saves the program and variables in such a way that **LOAD** automatically follows with

GO TO line number

2. Bytes:

SAVE name **CODE** start, length

saves *length* bytes starting at address *start*.

SAVE name **SCREEN\$**

is equivalent to

SAVE name **CODE 16384,6912**

and saves the television picture.

3. Arrays:

SAVE name **DATA** letter ()

or

SAVE name **DATA** letter \$ ()

saves the array whose name is *letter* or *letter \$* (this need bear no relation to *name*).

VERIFY

Checks the information on tape against the information already in memory. Failure to verify gives error **R Tape loading error**.

1. Program and variables:

VERIFY name

2. Bytes:

VERIFY name **CODE** start, length

If the bytes *name* on tape are more than *length* in number, then gives error R. Otherwise, checks them against the bytes in memory starting at address *start*.

VERIFY name **CODE** start

checks the bytes *name* on tape against those in memory starting at address *start*.

VERIFY name **CODE**

checks the bytes *name* on tape against those in memory starting at the address from which the first cassette byte was saved.

VERIFY name **SCREEN\$**

is equivalent to

VERIFY name **CODE 16384,6912**

but will almost certainly fail to verify.

3. Arrays:

VERIFY name **DATA** letter ()

or

VERIFY name **DATA** letter \$ ()

checks the array *name* on tape against the array *letter* or *letter \$* in memory.

LOAD

Loads new information from tape, deleting the old information from memory.

1. Program and variables:

LOAD name

deletes the old program and variables and loads in program and variables *name* from cassette; if the program was saved using **SAVE** name **LINE** it performs an automatic jump.

Error **4 Out of memory** occurs if there is no room for the new program and variables. In this case the old program and variables are not deleted.

2. Bytes:

LOAD name **CODE** start, length

If the bytes *name* from tape are more than *length* in number then gives error R. Otherwise, loads them into memory starting at address *start*, and overwriting whatever was there previously.

LOAD name **CODE** start

loads the bytes *name* from tape into memory, starting at address *start* and overwriting whatever was there previously.

LOAD name **CODE**

loads the bytes *name* from tape into memory starting at the address from which the first tape byte was saved and overwriting the bytes that were there in memory before.

3. Arrays:

LOAD name **DATA** letter ()

or

LOAD name **DATA** letter \$ ()

deletes any array already called *letter* or *letter \$* (as appropriate) and forms a new one from the array stored on cassette.

Error **4 Out of memory** occurs if no room for new arrays. Old arrays are not deleted.

MERGE

Loads new information from cassette without deleting old information from memory.

1. Program and variables:

MERGE name

merges the program *name* in with the one already in memory, overwriting any program lines or variables in the old program whose line numbers or names conflict with ones on the new program.

Error **4 Out of memory** occurs unless there is enough room in memory for all of the old program and variables *and* all of the new program and variables being loaded from tape.

2. Bytes:

Not possible

3. Arrays:

Not possible

Exercises

1. Make a cassette on which the first program, when loaded, prints a *menu* (a list of the other programs on the cassette), asks you to choose a program, and then loads it.

2. Get the chess piece graphics from Chapter 14, and then type **NEW**: they will survive this. However, they will not survive having the computer turned off: if you want to keep them, you must save them on tape, using **SAVE** with **CODE**. The easiest way is to save all twenty-one user-defined graphics by

SAVE "chess" CODE USR "a",21*8

followed by

VERIFY "chess" CODE

This is the system of *bytes* saving that was used for saving the picture. The address of the first byte to be saved is **USR "a"**, the address of the first of the eight

bytes that determine the pattern of the first user-defined graphic, and the number of bytes to be saved is $21 * 8$ – eight bytes for each of 21 graphics.

To load back you would normally use

LOAD "chess" CODE

However, if you are loading back into a Spectrum with a different amount of memory, or if you have moved the user-defined graphics to a different address (you have to do this deliberately using more advanced techniques), you have to be more careful and use

LOAD "chess" CODE USR "a"

USR allows for the fact that the graphics must be loaded back to a different address.

CHAPTER

21

The ZX printer

Summary

LPRINT, LLIST, COPY

Note: None of these statements is standard BASIC, although **LPRINT** is used by some other computers.

If you have a ZX printer, you will have some operating instructions with it. This chapter covers the BASIC statements needed to make it work.

The first two, **LPRINT** and **LLIST**, are just like **PRINT** and **LIST**, except that they use the printer instead of the television. (The L is an historical accident. When BASIC was invented it usually used an electric typewriter instead of a television, so **PRINT** really did mean print. If you wanted masses of output you would use a very fast line printer attached to the computer, and an **LPRINT** statement meaning 'Line printer **PRINT**'.)

Try this program for example.

```

10 LPRINT "This program".
20 LLIST
30 LPRINT "'prints out the character set.'"
40 FOR n=32 TO 255
50 LPRINT CHR$ n;
60 NEXT n

```

The third statement, **COPY**, prints out a copy of the television screen. For instance, type **LIST** to get a listing on the screen of the program above, and type

COPY

Note that **COPY** doesn't work with one of the listings that the computer puts up automatically, because that is cleared whenever a command is obeyed. You must either use **LIST** first, or use **LLIST** and forget about **COPY**.

You can always stop the printer when it is running by pressing the **BREAK** key (**CAPS SHIFT** and **SPACE**).

If you execute these statements without the printer attached, it should lose all the output and carry on with the next statement.

Try this:

```

10 FOR n=31 TO 0 STEP -1
20 PRINT AT 31-n,n; CHR$ (CODE "0"+n);
30 NEXT n

```

You will see a pattern of characters working down diagonally from the top right-hand corner until it reaches the bottom of the screen, when the program asks if

you want to scroll.

Now change **AT 31-n,n** in line 20 to **TAB n**. The program will have exactly the same effect as before.

Now change **PRINT** in line 20 to **LPRINT**. This time there will be no **scroll?**, which should not occur with the printer, and the pattern will carry straight on with the letters F to O.

Now change **TAB n** to **AT 31-n,n** still using **LPRINT**. This time you will get just a single line of symbols. The reason for the difference is that the output from **LPRINT** is not printed straight away, but arranges in a buffer store a picture one line long of what the computer will send to the printer when it gets round to it. The printing takes place

- (i) when the buffer is full,
- (ii) after an **LPRINT** statement that does not end in a comma or semicolon,
- (iii) when a comma, apostrophe or **TAB** item requires a new line, or
- (iv) at the end of a program, if there is anything left unprinted.

(iii) explains why our program with **TAB** works the way it does. As for **AT**, the line number is ignored and the **LPRINT** position (like the **PRINT** position, but for the printer instead of the television) is changed to the column number. An **AT** item can never cause a line to be sent to the printer.

Exercise

1. Make a printed graph of **SIN** by running the program in Chapter 17 and then using **COPY**.

CHAPTER

22

Other Equipment

There is other equipment that you will be able to attach to the Spectrum.

The ZX Microdrive is a high speed mass storage device, and is much more flexible in the way it can be used than a cassette recorder. It will operate not only with **SAVE**, **VERIFY**, **LOAD** and **MERGE**, but also with **PRINT**, **LIST**, **INPUT** and **INKEY\$**.

The network is used for connecting several Spectrums so that they can talk to each other – one of the uses of this is that you then need only one Microdrive to serve several computers.

The RS232 interface is a standard connection that allows you to link a Spectrum with keyboards, printers, computers and various other machines even if they were not designed specifically for the Spectrum.

These will use some extra keywords that are on the keyboard, but cannot be used without the extra attachments: they are **OPEN#**, **CLOSE#**, **MOVE**, **ERASE**, **CAT** and **FORMAT**.

CHAPTER

23

IN and OUT

Summary

OUT

IN

The processor can read from and (at least with RAM) write to memory by using **PEEK** and **POKE**. The processor itself does not really care whether memory is ROM, RAM or even nothing at all; it just knows that there are 65536 memory addresses, and it can read a byte from each one (even if it's nonsense), and write a byte to each one (even if it gets lost). In a completely analogous way there are 65536 of what are called *I/O ports* (standing for Input/Output ports). These are used by the processor for communicating with things like the keyboard or the printer, and they can be controlled from the BASIC by using the **IN** function and the **OUT** statement.

IN is a function like **PEEK**.

IN address

It has one argument, the port address, and its result is a byte read from that port.

OUT is a statement like **POKE**.

OUT address, value

writes the given value to the port with the given address. How the address is interpreted depends very much on the rest of the computer; quite often, many different addresses will mean the same. On the Spectrum it is most sensible to imagine the address being written in binary, because the individual bits tend to work independently. There are 16 bits, which we shall call (using A for *address*)

A15, A14, A13, A12,....., A2, A1, A0

Here A0 is the 1s bit, A1 the 2s bit, A2 the 4s bit and so on. Bits A0, A1, A2, A3 and A4 are the important ones. They are normally 1, but if any one of them is 0 this tells the computer to do something specific. The computer cannot cope with more than one thing at a time, so no more than one of these five bits should be 0. Bits A6 and A7 are ignored, so if you are a wizard with electronics you can use them yourself. The best addresses to use are those that are 1 less than a multiple of 32, so that A0,...A4 are all 1. Bits A8, A9 and so on are sometimes used to give extra information.

The byte read or written has 8 bits, and these are often referred to (using D for *data*) as D7, D6,...., D1, D0. Here is a list of the port addresses used.

There is a set of input addresses that read the keyboard and also the EAR socket.

The keyboard is divided up into 8 half rows of 5 keys each.

- IN 65278** reads the half row **CAPS SHIFT** to **V**
- IN 65022** reads the half row **A** to **G**
- IN 64510** reads the half row **Q** to **T**
- IN 63486** reads the half row **1** to **5**
- IN 61438** reads the half row **0** to **6**
- IN 57342** reads the half row **P** to **7**
- IN 49150** reads the half row **ENTER** to **H**
- IN 32766** reads the half row **SPACE** to **B**

(These addresses are $254 + 256 * (255 - 2 \uparrow n)$ as n goes from 0 to 7.)

In the byte read in, bits D0 to D4 stand for the five keys in the given half row – D0 for the outside key, D4 for the one nearest the middle. The bit is 0 if the key is pressed, 1 if it is not. D6 is the value at the EAR socket.

Port address 254 in output drives the loudspeaker (D4) and the MIC socket (D3), and also sets the border colour (D2, D1 and D0).

Port address 251 runs the printer, both in reading and writing: reading finds out whether the printer is ready for more, and writing sends out dots to be printed.

Port addresses 254, 247 and 239 are used for the extra devices mentioned in Chapter 22.

Run this program

```

10 FOR n=0 TO 7: REM half-row number
20 LET a=254+256*(255-2 ↑ n)
30 PRINT AT 0,0; IN a: GO TO 30
    
```


and play around by pressing keys. When you get bored with each half-row, press **BREAK** and then type

```

NEXT n
    
```

The control, data and address busses are all exposed at the back of the Spectrum, so you can do almost anything with a Spectrum that you can with a Z80. Sometimes, though, the Spectrum hardware might get in the way. Here is a diagram of the exposed connections at the back:

COMPONENT SIDE



UNDERSIDE

CHAPTER

24


The memory

Summary

CLEAR

Deep inside the computer, everything is stored as bytes, i.e. numbers between 0 and 255. You may think you have stored away the price of wool or the address of your fertilizer suppliers, but it has all been converted into collections of bytes and bytes are what the computer sees.

Each place where a byte can be stored has an address, which is a number between 0 and FFFFh (so an address can be stored as two bytes), so you might think of the memory as a long row of numbered boxes, each of which can contain a byte. Not all the boxes are the same, however. In the standard 16K RAM machine, the boxes from 8000h to FFFFh are simply missing altogether. The boxes from 4000h to 7FFFh are RAM boxes, which means you can open the lid and alter the contents, and those from 0 to 3FFFh are ROM boxes, which have glass tops but cannot be opened. You just have to read whatever was put in them when the computer was made.



To inspect the contents of a box, we use the **PEEK** function: its argument is the address of the box, and its result is the contents. For instance, this program prints out the first 21 bytes in ROM (and their addresses):

```

10 PRINT "Address"; TAB 8; "Byte"
20 FOR a=0 TO 20
30 PRINT a; TAB 8; PEEK a
40 NEXT a

```

All these bytes will probably be quite meaningless to you, but the processor chip understands them to be instructions telling it what to do.

To change the contents of a box (if it is RAM), we use the **POKE** statement. It has the form

POKE address, new contents

where 'address' and 'new contents' stand for numeric expressions. For instance, if you say

POKE 31000,57

the byte at address 31000 is given the new value 57 – type

PRINT PEEK 31000

to prove this. (Try poking in other values, to show that there is no cheating.) The new value must be between –255 and +255, and if it is negative then 256 is added to it.

The ability to poke gives you immense power over the computer if you know how to wield it; and immense destructive possibilities if you don't. It is very easy, by poking the wrong value in the wrong address, to lose vast programs that took you hours to type in. Fortunately, you won't do the computer any permanent damage.

We shall now take a more detailed look at how the RAM is used but don't bother to read this unless you're interested.




The memory is divided into different areas (shown on the big diagram) for storing different kinds of information. The areas are only large enough for the information that they actually contain, and if you insert some more at a given point (for instance by adding a program line or variable) space is made by shifting up everything above that point. Conversely, if you delete information then everything is shifted down.

The display file stores the television picture. It is rather curiously laid out, so you probably won't want to **PEEK** or **POKE** in it. Each character position on the screen has an 8×8 square of dots, and each dot can be either 0 (paper) or 1 (ink): and by using binary notation we can store the pattern as 8 bytes, one for each row. However, these 8 bytes are not stored together. The corresponding rows in the 32 characters of a single line are stored together as a scan of 32 bytes, because this is what the electron beam in the television needs as it scans from the left hand side of the screen to the other. Since the complete picture has 24 lines of 8 scans each, you might expect the total of 172 scans to be stored in order, one after the other; you'd be wrong. First come the top scans of lines 0 to 7, then the next scans of lines 0 to 7, and so on to the bottom scans of lines 0 to 7; then the same for lines 8 to 15; and then the same for lines 16 to 23. The upshot of all this is that if you're used to a computer that uses **PEEK** and **POKE** on the screen, you'll have to start using **SCREEN\$** and **PRINT AT** instead, or **PLOT** and **POINT**.

The attributes are the colours and so on for each character position, using the format of **ATTR**. These are stored line by line in the order you'd expect.

The printer buffer stores the characters destined for the printer.


The system variables contain various pieces of information that tell the computer what sort of state the computer is in. They are listed fully in the next chapter, but for the moment note that there are some (called **CHANS**, **PROG**, **VAR\$**, **E__LINE** and so on) that contain the addresses of the boundaries between the various areas in memory. These are not BASIC variables, and their names will not be recognized by the computer.



The Microdrive maps are only used with the Microdrive. Normally there is nothing there.

The channel information contains information about the input and output devices, namely the keyboard (with the lower half of the screen), the upper half of the screen, and the printer.

Each line of BASIC program has the form:




Note that, in contrast with all other cases of two-byte numbers in the Z80, the line number here is stored with its more significant byte first: that is to say, in the order that you write them down in.


A numerical constant in the program is followed by its binary form, using the character **CHR\$ 14** followed by five bytes for the number itself.

The variables have different formats according to their different natures. The letters in the names should be imagined as starting off in lower case.


Number whose name is one letter only:



Number whose name is longer than one letter:



Array of numbers:




The order of the elements is:

- first, the elements for which the first subscript is 1
- next, the elements for which the first subscript is 2
- next, the elements for which the first subscript is 3
- and so on for all possible values of the first subscript.


The elements with a given first subscript are ordered in the same way using the second subscript, and so on down to the last.

As an example, the elements of the 3*6 array b in Chapter 12 are stored in the order b(1,1) b(1,2) b(1,3) b(1,4) b(1,5) b(1,6) b(2,1) b(2,2) b(2,6) b(3,1) b(3,2) ... b(3,6).


Control variable of a **FOR-NEXT** loop:



String:



Array of characters:



The calculator is the part of the BASIC system that deals with arithmetic, and the numbers on which it is operating are held mostly in the calculator stack.

The spare part contains the space so far unused.

The machine stack is the stack used by the Z80 processor to hold return addresses and so on.

The **GOSUB** stack was mentioned in Chapter 5.

The byte pointed to by RAMTOP has the highest address used by the BASIC system. Even **NEW**, which clears the RAM out, only does so as far as this – so it doesn't change the user-defined graphics. You can change the address RAMTOP by putting a number in a clear statement:

CLEAR new RAMTOP

This

- (i) clears out all the variables
- (ii) clears the display file (like **CLS**)
- (iii) resets the **PLOT** position to the bottom left-hand corner
- (iv) does **RESTORE**
- (v) clears the **GOSUB** stack and puts it at the new RAMTOP – assuming that this

lies between the calculator stack and the physical end of RAM; otherwise it leaves RAMTOP as it was.

RUN also does **CLEAR**, although it never changes RAMTOP.

Using **CLEAR** in this way, you can either move RAMTOP up to make more room for the BASIC by overwriting the user-defined graphics, or you can move it down to make more RAM that is preserved from **NEW**.

Type **NEW**, then **CLEAR 23800** to get some idea of what happens to the machine when it fills up.

One of the first things you will notice if you start typing in a program is that after a while the computer stops accepting any more and buzzes at you. It means the computer is chock-a-block and you will have to empty it slightly. There are also two error messages with roughly the same meaning, **4 Memory full** and **G No room for line**.

The buzz also occurs when you type in a line longer than 23 lines – then your typing is not being ignored, though you cannot see it; but the buzz sounds to discourage you from doing any more.

You can adjust the length of the buzz by poking a number into address 23608. The usual length has number 64.

Any number (except 0) can be written uniquely as

$$\pm m \times 2^e$$

where \pm is the sign,

m is the *mantissa*, and lies between $\frac{1}{2}$ and 1 (it cannot be 1),

and e is the *exponent*, a whole number (possibly negative).

Suppose you write m in the binary scale. Because it is a fraction, it will have a *binary point* (like the decimal point in the scale of ten) and then a binary fraction (like a decimal fraction): so in binary,

a half is written .1

a quarter is written .01

three quarters is written .11

a tenth is written .000110011001100110011 . . . and so on. With our number m , because it is less than 1, there are no bits before the binary point, and because it is at least $\frac{1}{2}$, the bit immediately after the binary point is a 1.

To store the number in the computer, we use five bytes, as follows:

(i) write the first eight bits of the mantissa in the second byte (we know that the first bit is 1), the second eight bits in the third byte, the third eight bits in the fourth byte and the fourth eight bits in the fifth byte,


(ii) replace the first bit in the second byte – which we know is 1 – by the sign: 0 for plus, 1 for minus,

(iii) write the exponent +128 in the first byte. For instance, suppose our number is $1/10$

$$1/10 = 4/5 \times 2^{-3}$$

Thus the mantissa m is .11001100110011001100110011001100 in binary (since

the 33rd bit is 1, we shall round the 32nd up from 0 to 1), and the exponent e is -3 . Applying our three rules gives the five bytes



There is an alternative way of storing whole numbers between -65535 and $+65535$:

- (i) the first byte is 0,
- (ii) the second byte is 0 for a positive number, FFh for a negative one,
- (iii) the third and fourth bytes are the less and more significant bytes of the number (or the number +131072 if it is negative),
- (iv) the fifth byte is 0.

CHAPTER

25

The system variables

The bytes in memory from 23552 to 23733 are set aside for specific uses by the system. You can peek them to find out various things about the system, and some of them can be usefully poked. They are listed here with their uses.

These are called *system variables*, and have names, but do not confuse them with the variables used by the BASIC. The computer will not recognize the names as referring to system variables, and they are given solely as mnemonics for we humans.

The abbreviations in column 1 have the following meanings:

- X The variables should not be poked because the system might crash.
- N Poking the variable will have no lasting effect.

The number in column 1 is the number of bytes in the variable. For two bytes, the first one is the less significant byte – the reverse of what you might expect. So to poke a value **v** to a two-byte variable at address **n**, use

POKE n,v-256*INT (v/256)

POKE n+1,INT (v/256)

and to peek its value, use the expression

PEEK n+256*PEEK (n+1)

<i>Notes</i>	<i>Address</i>	<i>Name</i>	<i>Contents</i>
N8	23552	KSTATE	Used in reading the keyboard.
N1	23560	LAST K	Stores newly pressed key.
1	23561	REPDEL	Time (in 50ths of a second – in 60ths of a second in N. America) that a key must be held down before it repeats. This starts off at 35, but you can POKE in other values.
1	23562	REPPER	Delay (in 50ths of a second – in 60ths of a second in N. America) between successive repeats of a key held down: initially 5.
N2	23563	DEFADD	Address of arguments of user-defined function if one is being evaluated; otherwise 0.
N1	23565	K DATA	Stores 2nd byte of colour controls entered from keyboard.
N2	23566	TVDATA	Stores bytes of colour, AT and TAB controls going to television.
X38	23568	STRMS	Addresses of channels attached to streams.
2	23606	CHARS	256 less than address of character set (which starts with space and carries on to the copyright symbol). Normally in ROM, but you can set up your own in RAM and make CHARS point to it.

<i>Notes</i>	<i>Address</i>	<i>Name</i>	<i>Contents</i>
1	23608	RASP	Length of warning buzz.
1	23609	PIP	Length of keyboard click.
1	23610	ERR NR	1 less than the report code. Starts off at 255 (for - 1) so PEEK 23610 gives 255.
X1	23611	FLAGS	Various flags to control the BASIC system.
X1	23612	TV FLAG	Flags associated with the television.
X2	23613	ERR SP	Address of item on machine stack to be used as error return.
N2	23615	LIST SP	Address of return address from automatic listing.
N1	23617	MODE	Specifies K, L, C, E or G cursor.
2	23618	NEWPPC	Line to be jumped to.
1	23620	NSPPC	Statement number in line to be jumped to. Poking first NEWPPC and then NSPPC forces a jump to a specified statement in a line.
2	23621	PPC	Line number of statement currently being executed.
1	23623	SUBPPC	Number within line of statement being executed.
1	23624	BORDCR	Border colour * 8; also contains the attributes normally used for the lower half of the screen.
2	23625	E PPC	Number of current line (with program cursor).
X2	23627	VARS	Address of variables.
N2	23629	DEST	Address of variable in assignment.
X2	23631	CHANS	Address of channel data.
X2	23633	CURCHL	Address of information currently being used for input and output.
X2	23635	PROG	Address of BASIC program.
X2	23637	NXTLIN	Address of next line in program.
X2	23639	DATADD	Address of terminator of last DATA item.
X2	23641	E LINE	Address of command being typed in.
2	23643	K CUR	Address of cursor.
X2	23645	CH ADD	Address of the next character to be interpreted: the character after the argument of PEEK , or the NEWLINE at the end of a POKE statement.
2	23647	X PTR	Address of the character after the ? marker.
X2	23649	WORKSP	Address of temporary work space.
X2	23651	STKBOT	Address of bottom of calculator stack.
X2	23653	STKEND	Address of start of spare space.
N1	23655	BREG	Calculator's b register.
N2	23656	MEM	Address of area used for calculator's memory. (Usually MEMBOT, but not always.)
1	23658	FLAGS2	More flags.

<i>Notes</i>	<i>Address</i>	<i>Name</i>	<i>Contents</i>
X1	23659	DF SZ	The number of lines (including one blank line) in the lower part of the screen.
2	23660	S TOP	The number of the top program line in automatic listings.
2	23662	OLDPPC	Line number to which CONTINUE jumps.
1	23664	OSPCC	Number within line of statement to which CONTINUE jumps.
N1	23665	FLAGX	Various flags.
N2	23666	STRLEN	Length of string type destination in assignment.
N2	23668	T ADDR	Address of next item in syntax table (very unlikely to be useful).
2	23670	SEED	The seed for RND . This is the variable that is set by RANDOMIZE .
3	23672	FRAMES	3 byte (least significant first), frame counter. Incremented every 20ms. See Chapter 18.
2	23675	UDG	Address of 1st user-defined graphic. You can change this for instance to save space by having fewer user-defined graphics.
1	23677	COORDS	x-coordinate of last point plotted.
1	23678		y-coordinate of last point plotted.
1	23679	P POSN	33-column number of printer position.
1	23680	PR CC	Less significant byte of address of next position for LPRINT to print at (in printer buffer).
1	23681		Not used.
2	23682	ECHO E	33-column number and 24-line number (in lower half) of end of input buffer.
2	23684	DF CC	Address in display file of PRINT position.
2	23686	DFCCL	Like DF CC for lower part of screen.
X1	23688	S POSN	33-column number for PRINT position.
X1	23689		24-line number for PRINT position.
X2	23690	SPOSNL	Like S POSN for lower part.
1	23692	SCR CT	Counts scrolls: it is always 1 more than the number of scrolls that will be done before stopping with scroll? . If you keep poking this with a number bigger than 1 (say 255), the screen will scroll on and on without asking you.
1	23693	ATTR P	Permanent current colours, etc (as set up by colour statements).
1	23694	MASK P	Used for transparent colours, etc. Any bit that is 1 shows that the corresponding attribute bit is taken not from ATTR P, but from what is already on the screen.

<i>Notes</i>	<i>Address</i>	<i>Name</i>	<i>Contents</i>
N1	23695	ATTR T	Temporary current colours, etc (as set up by colour items).
N1	23696	MASK T	Like MASK P, but temporary.
1	23697	P FLAG	More flags.
N30	23698	MEMBOT	Calculator's memory area; used to store numbers that cannot conveniently be put on the calculator stack.
2	23728		Not used.
2	23730	RAMTOP	Address of last byte of BASIC system area.
2	23732	P-RAMT	Address of last byte of physical RAM.

This program tells you the first 22 bytes of the variables area:

```
10 FOR n=0 TO 21
20 PRINT PEEK (PEEK 23627+256*PEEK 23628+n)
30 NEXT n
```

Try to match up the control variable **n** with the descriptions above.
Now change line 20 to

```
20 PRINT PEEK (23755+n)
```

This tells you the first 22 bytes of the program area. Match these up with the program itself.

CHAPTER

26

Using machine code

Summary

USR with numeric argument

This chapter is written for those who understand *Z80 machine code*, the set of instructions that the Z80 processor chip uses. If you do not, but would like to, there are plenty of books about it. You want to get one called something along the lines of 'Z80 Machine code (or assembly language) for the absolute beginner', and if it mentions the Spectrum, so much the better.

These programs are normally written in *assembly language*, which, although cryptic, are not too difficult to understand with practice. (You can see the assembly language instructions in Appendix A.) However, to run them on the computer you need to code the program into a sequence of bytes – in this form it is called *machine code*. This translation is usually done by the computer itself, using a program called an *assembler*. There is no assembler built in to the Spectrum, but you may well be able to buy one on cassette. Failing that, you will have to do the translation yourself, provided that the program is not too long.


Let's take as an example the program

```
ld bc, 99
ret
```

which loads the bc register pair with 99. This translates into the four machine code bytes 1, 99, 0 (for ld bc, 99) and 201 (for ret). (If you look up 1 and 201 in Appendix A, you will find ld bc, NN – where NN stands for any two-byte number – and ret.)

When you have got your machine code program, the next step is to get it into the computer. (An assembler would probably do this automatically.) You need to decide whereabouts in memory to put it, and the best thing is to make extra space for it between the BASIC area and the user-defined graphics.


Suppose, for instance, that you have a 16K Spectrum. To start off with, the top end of RAM has



If you type

CLEAR 32499

this will give you a space of 100 (for good measure) bytes starting at address 32500.



To put in the machine code program, you would run a BASIC program something like

```

10 LET a=32500
20 READ n: POKE a,n
30 LET a=a+1: GO TO 20
40 DATA 1,99,0,201

```

(This will stop with report **E Out of DATA** when it has filled in the four bytes you specified.)

To run the machine code, you use the function **USR** – but this time with a numeric argument, the starting address. Its result is the value of the bc register on return from the machine code program, so if you do

```

PRINT USR 32500

```

you get the answer 99.

The return address to the BASIC is stacked in the usual way, so return is by a Z80 ret instruction. You should not use the iy and i registers in a machine code routine.

You can save your machine code program easily enough with

```

SAVE "some name" CODE 32500,4

```

On the face of it, there is no way of saving it so that when loaded it automatically runs itself, but you can get round this by using a BASIC program.

```

10 LOAD "" CODE 32500,4
20 PRINT USR 32500

```

Do first

```

SAVE "some name" LINE

```

and then

```
SAVE "xxxx" CODE 32500,4  
LOAD "some name"
```

will then load and automatically run the BASIC program, and the BASIC program will load and run the machine code.

The character set

This is the complete Spectrum character set, with codes in decimal and hex. If one imagines the codes as being Z80 machine code instructions, then the right hand columns give the corresponding assembly language mnemonics. As you are probably aware if you understand these things, certain Z80 instructions are compounds starting with CBh or EDh; the two right hand columns give these.

Code	Character	Hex	Z80 Assembler	– after CB	– after ED
0		00	nop	rlc b	
1	} not used	01	ld bc,NN	rlc c	
2		02	ld (bc),a	rlc d	
3		03	inc bc	rlc e	
4		04	inc b	rlc h	
5		05	dec b	rlc l	
6	PRINT comma	06	ld b,N	rlc (hl)	
7	EDIT	07	rlca	rlc a	
8	cursor left	08	ex af,af'	rrc b	
9	cursor right	09	add hl,bc	rrc c	
10	cursor down	0A	ld a,(bc)	rrc d	
11	cursor up	0B	dec bc	rrc e	
12	DELETE	0C	inc c	rrc h	
13	ENTER	0D	dec c	rrc l	
14	number	0E	ld c,N	rrc (hl)	
15	not used	0F	rrca	rrc a	
16	INK control	10	djnz DIS	rl b	
17	PAPER control	11	ld de,NN	rl c	
18	FLASH control	12	ld (de),a	rl d	
19	BRIGHT control	13	inc de	rl e	
20	INVERSE control	14	inc d	rl h	
21	OVER control	15	dec d	rl l	
22	AT control	16	ld d,N	rl (hl)	
23	TAB control	17	rla	rl a	
24	} not used	18	jr DIS	rr b	
25		19	add hl,de	rr c	
26		1A	ld a,(de)	rr d	
27		1B	dec de	rr e	
28		1C	inc e	rr h	
29		1D	dec e	rr l	
30		1E	ld e,N	rr (hl)	
31		1F	rra	rr a	
32	space	20	jr nz,DIS	sla b	
33	!	21	ld hl,NN	sla c	
34	"	22	ld (NN),hl	sla d	
35	#	23	inc hl	sla e	
36	\$	24	inc h	sla h	
37	%	25	dec h	sla l	

Appendix A

<i>Code</i>	<i>Character</i>	<i>Hex</i>	<i>Z80 Assembler</i>	<i>– after CB</i>	<i>– after ED</i>
38	&	26	ld h,N	sla (hl)	
39	'	27	daa	sla a	
40	(28	jr z,DIS	sra b	
41)	29	add hl,hl	sra c	
42	*	2A	ld hl,(NN)	sra d	
43	+	2B	dec hl	sra e	
44	,	2C	inc l	sra h	
45	–	2D	dec l	sra l	
46	.	2E	ld l,N	sra (hl)	
47	/	2F	cpl	sra a	
48	0	30	jr nc,DIS		
49	1	31	ld sp,NN		
50	2	32	ld (NN),a		
51	3	33	inc sp		
52	4	34	inc (hl)		
53	5	35	dec (hl)		
54	6	36	ld (hl),N		
55	7	37	scf		
56	8	38	jr c,DIS	srl b	
57	9	39	add hl,sp	srl c	
58	:	3A	ld a,(NN)	srl d	
59	;	3B	dec sp	srl e	
60	<	3C	inc a	srl h	
61	=	3D	dec a	srl l	
62	>	3E	ld a,N	srl (hl)	
63	?	3F	ccf	srl a	
64	@	40	ld b,b	bit 0,b	in b,(c)
65	A	41	ld b,c	bit 0,c	out (c),b
66	B	42	ld b,d	bit 0,d	sbc hl,bc
67	C	43	ld b,e	bit 0,e	ld (NN),bc
68	D	44	ld b,h	bit 0,h	neg
69	E	45	ld b,l	bit 0,l	retn
70	F	46	ld b,(hl)	bit 0,(hl)	im 0
71	G	47	ld b,a	bit 0,a	ld i,a
72	H	48	ld c,b	bit 1,b	in c,(c)
73	I	49	ld c,c	bit 1,c	out (c),c
74	J	4A	ld c,d	bit 1,d	adc hl,bc
75	K	4B	ld c,e	bit 1,e	ld bc,(NN)
76	L	4C	ld c,h	bit 1,h	
77	M	4D	ld c,l	bit 1,l	reti
78	N	4E	ld c,(hl)	bit 1,(hl)	
79	O	4F	ld c,a	bit 1,a	ld r,a
80	P	50	ld d,b	bit 2,b	in d,(c)
81	Q	51	ld d,c	bit 2,c	out (c),d

<i>Code</i>	<i>Character</i>	<i>Hex</i>	<i>Z80 Assembler</i>	<i>– after CB</i>	<i>– after ED</i>
82	R	52	ld d,d	bit 2,d	sbc hl,de
83	S	53	ld d,e	bit 2,e	ld (NN),de
84	T	54	ld d,h	bit 2,h	
85	U	55	ld d,l	bit 2,l	
86	V	56	ld d,(hl)	bit 2,(hl)	im 1
87	W	57	ld d,a	bit 2,a	ld a,i
88	X	58	ld e,b	bit 3,b	in e,(c)
89	Y	59	ld e,c	bit 3,c	out (c),e
90	Z	5A	ld e,d	bit 3,d	adc hl,de
91	[5B	ld e,e	bit 3,e	ld de,(NN)
92	/	5C	ld e,h	bit 3,h	
93]	5D	ld e,l	bit 3,l	
94	↑	5E	ld e,(hl)	bit 3,(hl)	im 2
95	—	5F	ld e,a	bit 3,a	ld a,r
96	£	60	ld h,b	bit 4,b	in h,(c)
97	a	61	ld h,c	bit 4,c	out (c),h
98	b	62	ld h,d	bit 4,d	sbc hl,hl
99	c	63	ld h,e	bit 4,e	ld (NN),hl
100	d	64	ld h,h	bit 4,h	
101	e	65	ld h,l	bit 4,l	
102	f	66	ld h,(hl)	bit 4,(hl)	
103	g	67	ld h,a	bit 4,a	rld
104	h	68	ld l,b	bit 5,b	in l,(c)
105	i	69	ld l,c	bit 5,c	out (c),l
106	j	6A	ld l,d	bit 5,d	adc hl,hl
107	k	6B	ld l,e	bit 5,e	ld hl,(NN)
108	l	6C	ld l,h	bit 5,h	
109	m	6D	ld l,l	bit 5,l	
110	n	6E	ld l,(hl)	bit 5,(hl)	
111	o	6F	ld l,a	bit 5,a	rld
112	p	70	ld (hl),b	bit 6,b	in f,(c)
113	q	71	ld (hl),c	bit 6,c	
114	r	72	ld (hl),d	bit 6,d	sbc hl,sp
115	s	73	ld (hl),e	bit 6,e	ld (NN),sp
116	t	74	ld (hl),h	bit 6,h	
117	u	75	ld (hl),l	bit 6,l	
118	v	76	halt	bit 6,(hl)	
119	w	77	ld (hl),a	bit 6,a	
120	x	78	ld a,b	bit 7,b	in a,(c)
121	y	79	ld a,c	bit 7,c	out (c),a
122	z	7A	ld a,d	bit 7,d	adc hl,sp
123	{	7B	ld a,e	bit 7,e	ld sp,(NN)
124		7C	ld a,h	bit 7,h	
125	}	7D	ld a,l	bit 7,l	

Appendix A

Code	Character	Hex	Z80 Assembler	– after CB	– after ED
126	~	7E	ld a,(hl)	bit 7,(hl)	
127	©	7F	ld a,a	bit 7,a	
128	☐	80	add a,b	res 0,b	
129	▣	81	add a,c	res 0,c	
130	▤	82	add a,d	res 0,d	
131	▥	83	add a,e	res 0,e	
132	▦	84	add a,h	res 0,h	
133	▧	85	add a,l	res 0,l	
134	▨	86	add a,(hl)	res 0,(hl)	
135	▩	87	add a,a	res 0,a	
136	▪	88	adc a,b	res 1,b	
137	▫	89	adc a,c	res 1,c	
138	▬	8A	adc a,d	res 1,d	
139	▭	8B	adc a,e	res 1,e	
140	▮	8C	adc a,h	res 1,h	
141	▯	8D	adc a,l	res 1,l	
142	▰	8E	adc a,(hl)	res 1,(hl)	
143	▱	8F	adc a,a	res 1,a	
144	(a)	90	sub b	res 2,b	
145	(b)	91	sub c	res 2,c	
146	(c)	92	sub d	res 2,d	
147	(d)	93	sub e	res 2,e	
148	(e)	94	sub h	res 2,h	
149	(f)	95	sub l	res 2,l	
150	(g)	96	sub (hl)	res 2,(hl)	
151	(h)	97	sub a	res 2,a	
152	(i)	98	sbc a,b	res 3,b	
153	(j)	99	sbc a,c	res 3,c	
154	(k)	9A	sbc a,d	res 3,d	
155	(l)	9B	sbc a,e	res 3,e	
156	(m)	9C	sbc a,h	res 3,h	
157	(n)	9D	sbc a,l	res 3,l	
158	(o)	9E	sbc a,(hl)	res 3,(hl)	
159	(p)	9F	sbc a,a	res 3,a	
160	(q)	A0	and b	res 4,b	ldi
161	(r)	A1	and c	res 4,c	cpi
162	(s)	A2	and d	res 4,d	ini
163	(t)	A3	and e	res 4,e	outi
164	(u)	A4	and h	res 4,h	
165	RND	A5	and l	res 4,l	
166	INKEY\$	A6	and (hl)	res 4,(hl)	
167	PI	A7	and a	res 4,a	
168	FN	A8	xor b	res 5,b	ldd
169	POINT	A9	xor c	res 5,c	cpd

user
graphics

<i>Code</i>	<i>Character</i>	<i>Hex</i>	<i>Z80 Assembler</i>	<i>– after CB</i>	<i>– after ED</i>
170	SCREEN\$	AA	xor d	res 5,d	ind
171	ATTR	AB	xor e	res 5,e	outd
172	AT	AC	xor h	res 5,h	
173	TAB	AD	xor l	res 5,l	
174	VAL\$	AE	xor (hl)	res 5,(hl)	
175	CODE	AF	xor a	res 5,a	
176	VAL	B0	or b	res 6,b	ldir
177	LEN	B1	or c	res 6,c	cpir
178	SIN	B2	or d	res 6,d	inir
179	COS	B3	or e	res 6,e	otir
180	TAN	B4	or h	res 6,h	
181	ASN	B5	or l	res 6,l	
182	ACS	B6	or (hl)	res 6,(hl)	
183	ATN	B7	or a	res 6,a	
184	LN	B8	cp b	res 7,b	lddr
185	EXP	B9	cp c	res 7,c	cpdr
186	INT	BA	cp d	res 7,d	indr
187	SQR	BB	cp e	res 7,e	otdr
188	SGN	BC	cp h	res 7,h	
189	ABS	BD	cp l	res 7,l	
190	PEEK	BE	cp (hl)	res 7,(hl)	
191	IN	BF	cp a	res 7,a	
192	USR	C0	ret nz	set 0,b	
193	STR\$	C1	pop bc	set 0,c	
194	CHR\$	C2	jp nz,NN	set 0,d	
195	NOT	C3	jp NN	set 0,e	
196	BIN	C4	call nz,NN	set 0,h	
197	OR	C5	push bc	set 0,l	
198	AND	C6	add a,N	set 0,(hl)	
199	<=	C7	rst 0	set 0,a	
200	>=	C8	ret z	set 1,b	
201	<>	C9	ret	set 1,c	
202	LINE	CA	jp z,NN	set 1,d	
203	THEN	CB		set 1,e	
204	TO	CC	call z,NN	set 1,h	
205	STEP	CD	call NN	set 1,l	
206	DEF FN	CE	adc a,N	set 1,(hl)	
207	CAT	CF	rst 8	set 1,a	
208	FORMAT	D0	ret nc	set 2,b	
209	MOVE	D1	pop de	set 2,c	
210	ERASE	D2	jp nc,NN	set 2,d	
211	OPEN #	D3	out (N),a	set 2,e	
212	CLOSE #	D4	call nc,NN	set 2,h	
213	MERGE	D5	push de	set 2,l	

Appendix A

<i>Code</i>	<i>Character</i>	<i>Hex</i>	<i>Z80 Assembler</i>	<i>– after CB</i>	<i>– after ED</i>
214	VERIFY	D6	sub N	set 2,(hl)	
215	BEEP	D7	rst 16	set 2,a	
216	CIRCLE	D8	ret c	set 3,b	
217	INK	D9	exx	set 3,c	
218	PAPER	DA	jp c,NN	set 3,d	
219	FLASH	DB	in a,(N)	set 3,e	
220	BRIGHT	DC	call c,NN	set 3,h	
221	INVERSE	DD	prefixes instructions using ix	set 3,l	
222	OVER	DE	sbc a,N	set 3,(hl)	
223	OUT	DF	rst 24	set 3,a	
224	LPRINT	E0	ret po	set 4,b	
225	LLIST	E1	pop hl	set 4,c	
226	STOP	E2	jp po,NN	set 4,d	
227	READ	E3	ex (sp),hl	set 4,e	
228	DATA	E4	call po,NN	set 4,h	
229	RESTORE	E5	push hl	set 4,l	
230	NEW	E6	and N	set 4,(hl)	
231	BORDER	E7	rst 32	set 4,a	
232	CONTINUE	E8	ret pe	set 5,b	
233	DIM	E9	jp (hl)	set 5,c	
234	REM	EA	jp pe,NN	set 5,d	
235	FOR	EB	ex de,hl	set 5,e	
236	GO TO	EC	call pe,NN	set 5,h	
237	GO SUB	ED		set 5,l	
238	INPUT	EE	xor N	set 5,(hl)	
239	LOAD	EF	rst 40	set 5,a	
240	LIST	F0	ret p	set 6,b	
241	LET	F1	pop af	set 6,c	
242	PAUSE	F2	jp p,NN	set 6,d	
243	NEXT	F3	di	set 6,e	
244	POKE	F4	call p,NN	set 6,h	
245	PRINT	F5	push af	set 6,l	
246	PLOT	F6	or N	set 6,(hl)	
247	RUN	F7	rst 48	set 6,a	
248	SAVE	F8	ret m	set 7,b	
249	RANDOMIZE	F9	ld sp,hl	set 7,c	
250	IF	FA	jp m,NN	set 7,d	
251	CLS	FB	ei	set 7,e	
252	DRAW	FC	call m,NN	set 7,h	
253	CLEAR	FD	prefixes instructions using iy	set 7,l	
254	RETURN	FE	cp N	set 7,(hl)	
255	COPY	FF	rst 56	set 7,a	

Reports

These appear at the bottom of the screen whenever the computer stops executing some BASIC, and explain why it stopped, whether for a natural reason, or because an error occurred.

The report has a code number or letter so that you can refer to the table here, a brief message explaining what happened and the line number and statement number within that line where it stopped. (A command is shown as line 0. Within a line, statement 1 is at the beginning, statement 2 comes after the first colon or **THEN**, and so on.)

The behaviour of **CONTINUE** depends very much on the reports. Normally, **CONTINUE** goes to the line and statement specified in the last report, but there are exceptions with reports 0, 9 and D (also see Appendix C).

Here is a table showing all the reports. It also tells you in what circumstances the report can occur, and this refers you to Appendix C. For instance error **A Invalid argument** can occur with **SQR, IN, ACS** and **ASN** and the entries for these in Appendix C tell you exactly what arguments are invalid.

<i>Code</i>	<i>Meaning</i>	<i>Situations</i>
0	OK Successful completion, or jump to a line number bigger than any existing. This report does not change the line and statement jumped to by CONTINUE .	Any
1	NEXT without FOR The control variable does not exist (it has not been set up by a FOR statement), but there is an ordinary variable with the same name.	NEXT
2	Variable not found For a simple variable this will happen if the variable is used before it has been assigned to in a LET, READ or INPUT statement or loaded from tape or set up in a FOR statement. For a subscripted variable it will happen if the variable is used before it has been dimensioned in a DIM statement or loaded from tape.	Any
3	Subscript wrong A subscript is beyond the dimension of the array, or there are the wrong number of subscripts. If the subscript is negative or bigger than 65535, then error B will result.	Subscripted variables, Substrings
4	Out of memory There is not enough room in the computer for what	LET, INPUT, FOR, DIM, GO SUB, LOAD,

Code Meaning

you are trying to do. If the computer really seems to be stuck in this state, you may have to clear out the command line using **DELETE** and then delete a program line or two (with the intention of putting them back afterwards) to give yourself room to manoeuvre with – say – **CLEAR**.

5 Out of screen

An **INPUT** statement has tried to generate more than 23 lines in the lower half of the screen. Also occurs with **PRINT AT 22, . . .**

6 Number too big

Calculations have led to a number greater than about 10^{38} .

7 RETURN without GO SUB

There has been one more **RETURN** than there were **GO SUBs**.

8 End of file

9 STOP statement

After this, **CONTINUE** will not repeat the **STOP**, but carries on with the statement after.

A Invalid argument

The argument for a function is no good for some reason.

B Integer out of range

When an integer is required, the floating point argument is rounded to the nearest integer. If this is outside a suitable range then error B results.

For array access, see also Error 3.

C Nonsense in BASIC

The text of the (string) argument does not form a valid expression.

D BREAK – CONT repeats

BREAK was pressed during some peripheral operation.

The behaviour of **CONTINUE** after this report is normal in that it repeats the statement. Compare with report L.

Situations

MERGE. Sometimes during expression evaluation

INPUT, PRINT AT

Any arithmetic

RETURN

Microdrive, etc, operations

STOP

SQR, LN, ASN, ACS, USR (with string argument)

RUN, RANDOMIZE, POKE, DIM, GO TO, GO SUB, LIST, LLIST, PAUSE, PLOT, CHR\$, PEEK, USR (with numeric argument)
Array access

VAL, VAL\$

LOAD, SAVE, VERIFY, MERGE, LPRINT, LLIST, COPY. Also when the computer asks **scroll?** and you type **N, SPACE** or **STOP**

<i>Code Meaning</i>	<i>Situations</i>
E Out of DATA You have tried to READ past the end of the DATA list.	READ
F invalid file name SAVE with name empty or longer than 10 characters.	SAVE
G No room for line There is not enough room left in memory to accommodate the new program line.	Entering a line into the program
H STOP in INPUT Some INPUT data started with STOP , or – for INPUT LINE – was pressed. Unlike the case with report 9, after report H CONTINUE will behave normally, by repeating the INPUT statement.	INPUT
I FOR without NEXT There was a FOR loop to be executed no times (e.g. FOR n=1 TO 0) and the corresponding NEXT statement could not be found.	FOR
J Invalid I/O device	Microdrive, etc, operations
K Invalid colour The number specified is not an appropriate value.	INK, PAPER, BORDER, FLASH, BRIGHT, INVERSE, OVER ; also after one of the corresponding control characters
L BREAK into program BREAK pressed, this is detected between two statements. The line and statement number in the report refer to the statement before BREAK was pressed, but CONTINUE goes to the statement after (allowing for any jumps to be done), so it does not repeat any statements.	Any
M RAMTOP no good The number specified for RAMTOP is either too big or too small.	CLEAR ; possibly in RUN
N Statement lost Jump to a statement that no longer exists.	RETURN, NEXT, CONTINUE
O Invalid stream	Microdrive, etc, operations

Appendix B

<i>Code</i>	<i>Meaning</i>	<i>Situations</i>
P	FN without DEF User-defined function	FN
Q	Parameter error Wrong number of arguments, or one of them is the wrong type (string instead of number or vice versa).	FN
R	Tape loading error A file on tape was found but for some reason could not be read in, or would not verify.	VERIFY LOAD or MERGE

A description of the ZX Spectrum for reference

The first section of this appendix is a repeat of that part of the Introduction concerning the keyboard and screen.

The keyboard

ZX Spectrum characters comprise not only the single *symbols* (letters, digits, etc), but also the compound *tokens* (keywords, function names, etc) and all these are entered from the keyboard rather than being spelled out. To obtain all these functions and commands some keys have five or more distinct meanings, given partly by shifting the keys (i.e. pressing either the **CAPS SHIFT** key or the **SYMBOL SHIFT** key at the same time as the required one) and partly by having the machine in different *modes*.

The mode is indicated by the *cursor*, a flashing letter that shows where the next character from the keyboard will be inserted.

K (for keywords) mode automatically replaces L mode when the machine is expecting a command or program line (rather than **INPUT** data), and from its position on the line it knows it should expect a line number or a keyword. This is at the beginning of the line, or just after **THEN**, or just after **:** (except in a string). If unshifted, the next key will be interpreted as either a keyword (written on the keys), or a digit.

L (for letters) mode normally occurs at all other times. If unshifted, the next key will be interpreted as the main symbol on that key, in lower case for letters.

In both K and L modes, **SYMBOL SHIFT** and a key will be interpreted as the subsidiary red character on the key and **CAPS SHIFT** with a digit key will be interpreted as the control function written in white above the key. **CAPS SHIFT** with other keys does not affect the keywords in K mode, and in L mode it converts lower case to capitals.

C (for capitals) mode is a variant of L mode in which all letters appear as capitals. **CAPS LOCK** causes a change from L mode to C mode or back again.

E (for extended) mode is used for obtaining further characters, mostly tokens. It occurs after both shift keys are pressed together, and lasts for one key depression only. In this mode, a letter gives one character or token (shown in green above it) if unshifted, and another (shown in red below it) if pressed with either shift. A digit key gives a token if pressed with **SYMBOL SHIFT**; otherwise it gives a colour control sequence.

G (for graphics) mode occurs after **GRAPHICS (CAPS SHIFT and 9)** is pressed, and lasts until it is pressed again. A digit key will give a mosaic graphic, quit **GRAPHICS** or **DELETE**, and each of the letter keys apart from V, W, X, Y and Z, will give a user-defined graphic.

If any key is held down for more than about 2 or 3 seconds, it will start repeating.

Keyboard input appears in the bottom half of the screen as it is typed, each character (single symbol or compound token) being inserted just before the cursor. The cursor can be moved left with **CAPS SHIFT** and **5**, or right with **CAPS SHIFT** and

8. The character before the cursor can be deleted with **DELETE (CAPS SHIFT and 0)**. (Note: the whole line can be deleted by typing **EDIT (CAPS SHIFT and 1)** followed by **ENTER**.)

When **ENTER** is pressed, the line is executed, entered into the program, or used as **INPUT** data as appropriate, unless it contains a syntax error. In this case a flashing **?** appears next to the error.

As program lines are entered, a listing is displayed in the top half of the screen. The manner in which the listing is produced is rather complicated, and explained more fully in Chapter 2. The last line entered is called the *current* line and is indicated by the symbol **▣**, but this can be changed by using the keys **◀ (CAPS SHIFT and 6)** and **▶ (CAPS SHIFT and 7)**. If **EDIT (CAPS SHIFT and 1)** is pressed, the current line is brought down to the bottom part of the screen and can be edited.

When a command is executed or a program run, output is displayed in the top half of the screen and remains until a program line is entered, or **ENTER** is pressed with an empty line, or **▶** or **◀** is pressed. In the bottom part appears a report giving a code (digit or letter) referring you to Appendix B, a brief verbal summary of what Appendix B says, the number of the line containing the last statement executed (or **0** for a command) and the position of the statement within the line. The report remains on the screen until a key is pressed (and indicates K mode).

In certain circumstances, **CAPS SHIFT** with the **SPACE** key acts as a **BREAK**, stopping the computer with report **D** or **L**. This is recognised

- (i) at the end of a statement while a program is running, or
- (ii) while the computer is using the cassette recorder or printer.

The television screen

This has 24 lines, each 32 characters long, and is divided into two parts. The top part is at most 22 lines and displays either a listing or program output. When printing in the top part has reached the bottom, it all scrolls up one line; if this would involve losing a line that you have not had a chance to see yet, then the computer stops with the message **scroll?**. Pressing the keys **N**, **SPACE** or **STOP** will make the program stop with report **D BREAK – CONT repeats**; any other key will let the scrolling continue. The bottom part is used for inputting commands, program lines, and **INPUT** data, and also for displaying reports. The bottom part starts off as two lines (the upper one blank), but it expands to accommodate whatever is typed in. When it reaches the current print position in the top half, further expansions will make the top half scroll up.

Each character position has *attributes* specifying its *paper* (background) and *ink* (foreground) colours, a two-level brightness, and whether it flashes or not. The available colours are black, blue, red, magenta, green, yellow and white.

The edge of the screen can be set to any of the colours using the border statement.

A character position is divided into 8×8 pixels and high resolution graphics are obtained by setting the pixels individually to show either the ink or paper colour for

that character position.

The attributes at a character position are adjusted whenever a character is written there or a pixel is plotted. The exact manner of the adjustment is determined by the *printing parameters*, of which there are two sets (called *permanent* and *temporary*) of six: the **PAPER, INK, FLASH, BRIGHT, INVERSE** and **OVER** parameters. Permanent parameters for the top part are set up by **PAPER, INK**, etc, statements, and last until further notice. (Initially they are black ink on white paper. With normal brightness, no flashing, normal video and no overprinting). Permanent parameters for the bottom part use the border colour as the paper colour, with a black or white contrasting ink colour, normal brightness, no flashing, normal video and no overprinting.

Temporary parameters are set up by **PAPER, INK**, etc, items, which are embedded in **PRINT, LPRINT, INPUT, PLOT, DRAW** and **CIRCLE** statements, and also by **PAPER, INK**, etc control characters when they are printed to the television – they are followed by a further byte to specify the parameter value. Temporary parameters last only to the end of the **PRINT** (or whatever) statement, or, in **INPUT** statements, until some **INPUT** data is needed from the keyboard, when they are replaced by the permanent parameters.

PAPER and **INK** parameters are in the range 0 to 9. Parameters 0 to 7 are the colours used when a character is printed:

- 0 black
- 1 blue
- 2 red
- 3 magenta
- 4 green
- 5 cyan
- 6 yellow
- 7 white

Parameter 8 ('transparent') specifies that the colour on the screen is to be left unchanged when a character is printed.

Parameter 9 ('contrast') specifies that the colour in question (paper or ink) is to be made either white or black to show up against the other colour.

FLASH and **BRIGHT** parameters are 0, 1 or 8: 1 means that flashing or brightness is turned on, 0 that it is turned off, and 8 ('transparent') that it is left unchanged at any character position.

OVER and **INVERSE** parameters are 0 or 1.

OVER 0 new characters obliterate old ones

OVER 1 the bit patterns of the old and new characters are combined using an 'exclusive or' operation (*overprinting*)

INVERSE 0 new characters are printed as ink colour on paper colour (*normal video*)

INVERSE 1 new characters are printed as paper colour on ink colour (*inverse video*)

When a **TAB** control character is received by the television, two more bytes are expected to specify a tab stop n (less significant byte first). This is reduced modulo 32 to n_0 (say), and then sufficient spaces are printed to move the printing position into column n_0 .

When a comma control character is received, then sufficient spaces (at least one) are printed to move the printing position into column 0 or column 16.

When an **ENTER** control character is received, the printing position is moved on to the next line.

The printer

Output to the ZX printer is via a buffer one line (32 characters) long, and a line is sent to the printer

- (i) when printing spills over from one line to the next,
- (ii) when an **ENTER** character is received,
- (iii) at the end of the program, if there is anything left unprinted,
- (iv) when a **TAB** control or comma control moves the printing position on to a new line.

TAB controls and comma controls output spaces in the same way as on the television.

The **AT** control changes the printing position using the column number, and ignores the line number.

The printer is affected by **INVERSE** and **OVER** controls (and also statements) in the same way as the screen is, but not by **PAPER**, **INK**, **FLASH** or **BRIGHT**.

The printer will stop with error B if **BREAK** is pressed.

If the printer is absent the output will simply be lost.

The BASIC

Numbers are stored to an accuracy of 9 or 10 digits. The largest number you can get is about 10^{38} , and the smallest (positive) number is about $4 * 10^{-39}$.

A number is stored in the ZX Spectrum in floating point binary with one exponent byte e ($1 \leq e \leq 255$), and four mantissa bytes m ($\frac{1}{2} \leq m < 1$). This represents the number $m * 2^{e-128}$.

Since $\frac{1}{2} \leq m < 1$, the most significant bit of the mantissa m is always 1. Therefore in actual fact we can replace it with a bit to show the sign – 0 for positive numbers, 1 for negative.

Small integers have a special representation in which the first byte is 0, the second is a sign byte (0 or FFh) and the third and fourth are the integer in twos complement form, the less significant byte first.

Numeric variables have names of arbitrary length, starting with a letter and continuing with letters and digits. Spaces and colour controls are ignored and all letters are converted to lower-case letters.

Control variables of **FOR-NEXT** loops have names a single letter long.

Numeric arrays have names a single letter long, which may be the same as the name of a simple variable. They may have arbitrarily many dimensions of arbitrary size. Subscripts start at 1.

Strings are completely flexible in length. The name of a string consists of a single letter followed by \$.

String arrays can have arbitrarily many dimensions of arbitrary size. The name is a single letter followed by \$ and may not be the same as the name of a string. All the strings in a given array have the same fixed length, which is specified as an extra, final dimension in the **DIM** statement. Subscripts start at 1.

Slicing: Substrings of strings may be specified using *slicers*. A slicer can be

- (i) empty
- or
- (ii) numerical expression
- or
- (iii) optional numerical expression **TO** optional numerical expression

and is used in expressing a substring either by

- (a) string expression (slicer)
- (b) string array variable (subscript,..., subscript, slicer)

which means the same as

string array variable (subscript....., subscript) (slicer)

In (a), suppose the string expression has the value $s\$$.

If the slicer is empty, the result is $s\$$ considered as a substring of itself.

If the slicer is a numerical expression with value m , then the result is the m th character of $s\$$ (a substring of length 1).

If the slicer has the form (iii), then suppose the first numerical expression has the value m (the default value is 1), and the second, n (the default value is the length of $s\$$).

If $1 \leq m \leq n \leq \text{the length of } s\$$ then the result is the substring of $s\$$ starting with the m th character and ending with the n th.

If $0 < n < m$ then the result is the empty string.

Otherwise, error 3 results.

Slicing is performed before functions or operations are evaluated, unless brackets dictate otherwise.

Substrings can be assigned to (see **LET**).

If a string quote is to be written in a string literal, then it must be doubled.

Functions

The argument of a function does not need brackets if it is a constant or a (possibly subscripted or sliced) variable.

<i>Function</i>	<i>Type of argument</i> (x)	<i>Result</i>
ABS	number	Absolute magnitude
ACS	number	Arccosine in radians. Error A if x not in the range -1 to $+1$
AND	binary operation, right operand always a number. Numeric left operand: String left operand:	$A \text{ AND } B = \begin{cases} A & \text{if } B \neq 0 \\ 0 & \text{if } B = 0 \end{cases}$ $A\$ \text{ AND } B = \begin{cases} A\$ & \text{if } B \neq 0 \\ "" & \text{if } B = 0 \end{cases}$
ASN	number	Arcsine in radians. Error A if x not in the range -1 to $+1$
ATN	number	Arctangent in radians
ATTR	two arguments, x and y , both numbers; enclosed in brackets	A number whose binary form codes the attributes of line x , column y on the television. Bit 7 (most significant) is 1 for flashing, 0 for not flashing. Bit 6 is 1 for bright, 0 for normal. Bits 5 to 3 are the paper colour. Bits 2 to 0 are the ink colour. Error B unless $0 \leq x \leq 23$ and $0 \leq y \leq 31$
BIN		This is not really a function, but an alternative notation for numbers: BIN followed by a sequence of 0s and 1s is the number with such a representation in binary

<i>Function</i>	<i>Type of argument</i>	<i>Result</i>
CHR\$	number	The character whose code is x, rounded to the nearest integer
CODE	string	The code of the first character in x (or 0 if x is the empty string)
COS	number (in radians)	Cosine x
EXP	number	e^x
FN		FN followed by a letter calls up a user-defined function (see DEF). The arguments must be enclosed in brackets; even if there are no arguments the brackets must still be present.
IN	number	The result of inputting at processor level from port x ($0 \leq x \leq \text{FFFFh}$) (loads the bc register pair with x and does the assembly language instruction in a(c))
INKEY\$	none	Reads the keyboard. The result is the character representing (in L or C mode) the key pressed if there is exactly one, else the empty string.
INT	number	Integer part (always rounds down)
LEN	string	Length
LN	number	Natural logarithm (to base e). Error A if $x \leq 0$
NOT	number	0 if $x < > 0$, 1 if $x = 0$. NOT has priority 4
OR	binary operation, both operands numbers	$a \text{ OR } b = \begin{cases} 1 & \text{if } b < > 0 \\ a & \text{if } b = 0 \end{cases}$ OR has priority 2
PEEK	number	The value of the byte in memory whose address is x (rounded to the nearest integer). Error B if x is not in the range 0 to 65535
PI	none	π (3.14159265...)
POINT	Two arguments, x and y, both numbers; enclosed in brackets	1 if the pixel at (x,y) is ink colour. 0 if it is paper colour. Error B unless $0 \leq x \leq 255$ and $0 \leq y \leq 175$
RND	none	The next pseudorandom number in a sequence generated by taking the powers of 75 modulo 65537, subtracting 1 and dividing by 65536. $0 \leq y < 1$
SCREEN\$	Two arguments, x and y, both numbers; enclosed in brackets	The character that appears, either normally or inverted, on the television at line x, column y. Gives the empty string, if the character is not

<i>Function</i>	<i>Type of argument</i>	<i>Result</i>
		recognised. Error B unless $0 \leq x \leq 23$ and $0 \leq y \leq 31$
SGN	number	Signum: the sign (-1 for negative, 0 for zero or +1 for positive) of x
SIN	number (in radians)	Sine x
SQR	number	Square root. Error A if $x < 0$
STR\$	number	The string of characters that would be displayed if x were printed
TAN	number (in radians)	Tangent
USR	number	Calls the machine code subroutine whose starting address is x. On return, the result is the contents of the bc register pair
USR	string	The address of the bit pattern for the user-defined graphic corresponding to x. Error A if x is not a single letter between a and u, or a user-defined graphic
VAL	string	Evaluates x (without its bounding quotes) as a numerical expression. Error C if x contains a syntax error, or gives a string value. Other errors possible, depending on the expression
VAL\$	string	Evaluates x (without its bounding quotes) as a string expression. Error C if x contains a syntax error or gives a numeric value. Other errors possible, as for VAL
-	number	Negation

The following are binary operations:

+	Addition (on numbers), or concatenation (on strings)	
-	Subtraction	
*	Multiplication	
/	Division	
↑	Raising to a power. Error B if the left operand is negative	
=	Equals	} Both operands must be of the same type. The result is a number 1, if the comparison holds and 0 if it does not
>	Greater than	
<	Less than	
<=	Less than or equal to	
>=	Greater than or equal to	
<>	Not equal to	

Functions and operations have the following priorities:

<i>Operation</i>	<i>Priority</i>
Subscripting and slicing	12
All functions except NOT and unary minus	11
↑	10
Unary minus (i.e. minus just used to negate something)	9
*, /	8
+, - (minus used to subtract one number from another)	6
=, >, <, <=, >=, <>	5
NOT	4
AND	3
OR	2

Statements

In this list,

α	represents a single letter
v	represents a variable
x, y, z	represent numerical expressions
m, n	represent numerical expressions that are rounded to the nearest integer
e	represents an expression
f	represents a string valued expression
s	represents a sequence of statements separated by colons :
c	represents a sequence of colour items, each terminated by commas , or semi-colons ;. A colour item has the form of a PAPER, INK, FLASH, BRIGHT, INVERSE or OVER statement.

Note that arbitrary expressions are allowed everywhere (except for the line number at the beginning of a statement).

All statements except **INPUT, DEF** and **DATA** can be used either as commands or in programs (although they be more sensible in one than the other). A command or program line can have several statements, separated by colons (:). There is no restriction on whereabouts in a line any particular statement can occur – although see **IF** and **REM**.

BEEP x, y

Sounds a note through the loudspeaker for x seconds at a pitch y semitones above middle C (or below if y is negative)

BORDER m

Sets the colour of the border of the screen and also the paper colour for the lower part of the screen.

Error K if m not in the range 0 to 7

BRIGHT	Sets brightness of characters subsequently printed. n=0 for normal, 1 for bright, 8 for transparent. Error K if n not 0, 1 or 8
CAT	Does not work without Microdrive, etc
CIRCLE x, y, z	Draws an arc of a circle, centre (x,y), radius z
CLEAR	Deletes all variables, freeing the space they occupied. Does RESTORE and CLS , resets the PLOT position to the bottom left-hand corner and clears the GO SUB stack
CLEAR n	Like CLEAR , but if possible changes the system variable RAMTOP to n and puts the new GO SUB stack there
CLOSE #	Does not work without Microdrive, etc
CLS	(Clear Screen). Clears the display file
CONTINUE	Continues the program, starting where it left off last time it stopped with report other than 0. If the report was 9 or L, then continues with the following statement (taking jumps into account); otherwise repeats the one where the error occurred. If the last report was in a command line then CONTINUE will attempt to continue the command line and will either go into a loop if the error was in 0:1, give report 0 if it was in 0:2, or give error N if it was 0:3 or greater. CONTINUE appears as CONT on the keyboard
COPY	Sends a copy of the top 22 lines of display to the printer, if attached; otherwise does nothing. Note that COPY can not be used to print the automatic listings that appear on the screen. Report D if BREAK pressed
DATA e ₁ , e ₂ , e ₃ , ...	Part of the DATA list. Must be in a program
DEF FN α(α ₁ ,...,α _k)=e	User-defined function definition; must be in a program. Each of α and α ₁ to α _k is either a single letter or a single letter followed by '\$' for string argument or result. Takes the form DEF FN α()=e if no arguments
DELETE f	Does not work without Microdrive, etc
DIM α(n ₁ ,...,n _k)	Deletes any array with the name α, and sets up an array α of numbers with k dimensions n ₁ ,...,n _k . Initialises all the values to 0
DIM α\$(n ₁ ,...,n _k)	Deletes any array or string with the name α\$, and sets

up an array of characters with k dimensions n_1, \dots, n_k . Initialises all the values to " ". This can be considered as an array of strings of fixed length n_k , with $k-1$ dimensions n_1, \dots, n_{k-1} .

Error 4 occurs if there is no room to fit the array in. An array is undefined until it is dimensioned in a **DIM** statement

DRAW x,y

DRAW $x,y,0$

DRAW x,y,z

Draws a line from the current plot position moving x horizontally and y vertically relative to it while turning through an angle z .

Error B if it runs off the screen

ERASE

Does not work without Microdrive, etc.

FLASH

Defines whether characters will be flashing or steady. $n=0$ for steady, $n=1$ for flash, $n=8$ for no change.

FOR $\alpha=x$ **TO** y

FOR $\alpha=x$ **TO** y **STEP** 1

FOR $\alpha=x$ **TO** y **STEP** z

Deletes any simple variable α and sets up a control variable with value x , limit y , step z , and looping address referring to the statement after the **FOR** statement. Checks if the initial value is greater (if $\text{step} \geq 0$) or less (if $\text{step} < 0$) than the limit, and if so then skips to statement **NEXT** α , giving error 1 if there is none. See **NEXT**.

Error 4 occurs if there is no room for the control variable

FORMAT f

Does not work without the Microdrive, etc

GOSUB n

Pushes the line number of the **GOSUB** statement onto a stack; then as **GO TO** n .

Error 4 can occur if there are not enough **RETURNS**

GO TO n

Jumps to line n (or, if there is none, the first line after that)

IF x **THEN** s

If x true (non-zero) then s is executed. Note that s comprises all the statements to the end of the line. The form '**IF** x **THEN** line number' is not allowed

INK n

Sets the ink (foreground) colour of characters subsequently printed. n is in the range 0 to 7 for a colour, $n=8$ for transparent or 9 for contrast. See *The television screen* – Appendix B.

Error K if n not in the range 0 to 9

INPUT ...

The '...' is a sequence of **INPUT** items, separated as in a **PRINT** statement by commas, semicolons or apostrophes. An **INPUT** item can be

- (i) Any **PRINT** item not beginning with a letter
- (ii) A variable name, or
- (iii) **LINE**, then a string type variable name.

The **PRINT** items and separators in (i) are treated exactly as in **PRINT**, except that everything is printed in the lower part of the screen.

For (ii) the computer stops and waits for input of an expression from the keyboard; the value of this is assigned to the variable. The input is echoed in the usual way and syntax errors give the flashing **?**. For string type expressions, the input buffer is initialised to contain two string quotes (which can be erased if necessary). If the first character in the input is **STOP**, the program stops with error H. (iii) is like (ii) except that the input is treated as a string literal without quotes, and the **STOP** mechanism doesn't work; to stop it you must type **↵** instead

INVERSE n

Controls inversion of characters subsequently printed. If $n=0$, characters are printed in *normal video*, as ink colour on paper colour.

If $n=1$, characters are printed in *inverse video*, i.e. paper colour on ink colour. See *The television screen* – Appendix B.

Error K if n is not 0 or 1

LET v=e

Assigns the value of e to the variable v . **LET** cannot be omitted. A simple variable is undefined until it is assigned to in a **LET**, **READ** or **INPUT** statement. If v is a subscripted string variable, or a sliced string variable (substring), then the assignment is *Procrustean* (fixed length): the string value of e is either truncated or filled out with spaces on the right, to make it the same length as the variable v

LIST

LIST n

LIST 0
Lists the program to the upper part of the screen, starting at the first line whose number is at least n , and makes n the current line

LLIST

LLIST n

Like **LIST**, but using the printer

LOAD f

Loads program and variables

LOAD f **DATA** ()

Loads a numeric array

LOAD f **DATA** \$()

Loads character array \$

LOAD f **CODE** m,n

Loads at most n bytes, starting at address m

LOAD f CODE m	Loads bytes starting at address m
LOAD f CODE	Loads bytes back to the address they were saved from
LOAD f SCREEN\$	LOAD f CODE 16384,6912. Searches for file of the right sort on cassette tape and loads it, deleting previous versions in memory. See Chapter 20
LPRINT	Like PRINT but using the printer
MERGE f	Like LOAD f , but does not delete old program lines and variables except to make way for new ones with the same line number or name
MOVE f₁,f₂	Does not work without the Microdrive, etc
NEW	Starts the BASIC system off anew, deleting program and variables, and using the memory up to and including the byte whose address is in the system variable RAMBOT and preserves the system variables UDG, P RAMT, RASP and PIP
NEXT α	(i) Finds the control variable α (ii) Adds its step to its value (iii) If the step ≥ 0 and the value > the limit; or if the step < 0 and the value < the limit, then jumps to the looping statement. Error 2 if there is no variable α. Error 1 if there is one, but it's not α control variable
OPEN #	Does not work without the Microdrive, etc
OUT m,n	Outputs byte n at port m at the processor level. (Loads the bc register pair with m, the a register with n, and does the assembly language instruction: out (c),a.) 0 ≤ m ≤ 65535, -255 ≤ n ≤ 255, else error B
OVER n	Controls overprinting for characters subsequently printed. If n = 0, characters obliterate previous characters at that position. If n = 1, then new characters are mixed in with old characters to give ink colour wherever either (but not both) had ink colour, and paper colour if they were both paper or both ink colour. See <i>The television screen</i> – Appendix B. Error K if n not 0 or 1
PAPER n	Like INK , but controlling the paper (background) colour
PAUSE n	Stops computing and displays the display file for n frames (at 50 frames per second or 60 frames per second in North America) or until a key is pressed.

$0 \leq n \leq 65535$, else error B. If $n=0$ then the pause is not timed, but lasts until a key is pressed

PLOT c;m,n

Prints an ink spot (subject to **OVER** and **INVERSE**) at the pixel ($|m|$, $|n|$); moves the **PLOT** position.

Unless the colour items c specify otherwise, the ink colour at the character position containing the pixel is changed to the current permanent ink colour, and the other (paper colour, flashing and brightness) are left unchanged.

$0 \leq |m| \leq 255$, $0 \leq |n| \leq 175$, else error B

POKE m,n

Writes the value n to the byte in store with address m.

$0 \leq m \leq 65535$, $-255 \leq n \leq 255$, else error B

PRINT ...

The '...' is a sequence of **PRINT** items, separated by commas ,, semicolons ; or apostrophes ' and they are written to the display file for output to the television.

A semicolon ; between two items has no effect: it is used purely to separate the items. A comma , outputs the comma control character, and an apostrophe ' outputs the **ENTER** character.

At the end of the **PRINT** statement, if it does not end in a semicolon, or comma, or apostrophe, an **ENTER** character is output.

A **PRINT** item can be

- (i) empty, i.e. nothing.
- (ii) a numerical expression

First a minus sign is printed if the value is negative. Now let x be the modulus of value.

If $x \leq 10^{-5}$ or $x \geq 10^{13}$, then it is printed using scientific notation. The mantissa part has up to eight digits (with no trailing zeros), and the decimal point (absent if only one digit) is after the first. The exponent part is E, followed by + or -, followed by one or two digits.

Otherwise x is printed in ordinary decimal notation with up to eight significant digits, and no trailing zeros after the decimal point. A decimal point right at the beginning is always followed by a zero, so for instance .03 and 0.3 are printed as such.

0 is printed as a single digit 0.

- (iii) a string expression

The tokens in the string are expanded, possibly with a space before or after.

Control characters have their control effect.

Unrecognized characters print as **?**.

- (iv) **AT** m,n
Outputs an **AT** control character followed by a byte for m (the line number) and a byte for n (the column number).
- (v) **TAB** n
Outputs a **TAB** control character followed by two bytes for n (less significant byte first), the **TAB** stop.
- (vi) A colour item, which takes the form of a **PAPER, INK, FLASH, BRIGHT, INVERSE** or **OVER** statement

RANDOMIZE
RANDOMIZE n

RANDOMIZE 0

Sets the system variable (called SEED) used to generate the next value of **RND**. If $n \neq 0$, SEED is given the value n; if $n = 0$ then it is given the value of another system variable (called FRAMES) that counts the frames so far displayed on the television, and so should be fairly random.

RANDOMIZE appears as **RAND** on the keyboard.
Error B occurs if n is not in the range 0 to 65535

READ V_1, V_2, \dots, V_k

Assigns to the variables using successive expressions in the **DATA** list.

Error C if an expression is the wrong type.

Error E if there are variables left to be read when the **DATA** list is exhausted

REM ...

No effect. '...' can be any sequence of characters except **ENTER**. This can include :, so no statements are possible after the **REM** statement on the same line

RESTORE
RESTORE n

RESTORE 0

Restores the **DATA** pointer to the first **DATA** statement in a line with number at least n: the next **READ** statement will start reading there

RETURN

Takes a reference to a statement off the **GO SUB** stack, and jumps to the line after it.

Error 7 occurs when there is no statement reference on the stack. There is some mistake in your program; **GO SUBs** are not properly balanced by **RETURNs**

RUN
RUN n
SAVE f

RUN 0

CLEAR, and then **GO TO** n

Saves the program and variables

SAVE f LINE m	Saves the program and variables so that if they are loaded there is an automatic jump to line m
SAVE f DATA ()	Saves the numeric array
SAVE f DATA \$()	Saves the character array \$
SAVE f CODE m,n	Saves n bytes starting at address m
SAVE f SCREEN\$	SAVE f CODE 16384,6912. Saves information on cassette, giving it the name f. Error F if f is empty or has length eleven or more. See Chapter 20
STOP	Stops the program with report 9. CONTINUE will resume with the following statement
VERIFY	The same as LOAD except that the data is not loaded into RAM, but compared against what is already there. Error R if one of the comparisons shows different bytes

Example programs

This appendix contains some example programs to demonstrate the abilities of the ZX Spectrum.

The first of these programs requires a date to be input and gives the day of the week which corresponds to this date.

```

10 REM convert date to day
20 DIM d$(7,6): REM days of week
30 FOR n=1 TO 7: READ d$(n): NEXT n
40 DIM m(12): REM lengths of months
50 FOR n=1 TO 12: READ m(n): NEXT n
100 REM input date
110 INPUT "day?";day
120 INPUT "month?";month
130 INPUT "year (20th century only)?";year
140 IF year<1901 THEN PRINT "20th century starts at 1901":
    GO TO 100
150 IF year>2000 THEN PRINT "20th century ends at 2000":
    GO TO 100
160 IF month<1 THEN GO TO 210
170 IF month>12 THEN GO TO 210
180 IF year/4-INT(year/4)=0 THEN LET m(2)=29: REM leap year
190 IF day>m(month) THEN PRINT "This month has only ";
    m(month);" days.": GO TO 500
200 IF day>0 THEN GO TO 300
210 PRINT "Stuff and nonsense. Give me a real date."
220 GO TO 500
300 REM convert date to number of days since start of century
310 LET y=year-1901
320 LET b=365*y+INT (y/4): REM number of days to start of year
330 FOR n=1 TO month-1: REM add on previous months
340 LET b=b+m(n): NEXT n
350 LET b=b+day
400 REM convert to day of week
410 LET b=b-7* INT (b/7)+1
420 PRINT day;" ";month;" ";year
430 FOR n=6 TO 3 STEP -1: REM remove trailing spaces
440 IF d$(b,n) <> " " THEN GO TO 460
450 NEXT n
460 LET e$=d$(b, TO n)
470 PRINT" is a "; e$; "day"
500 LET m(2)=28: REM restore February
510 INPUT "again?", a$
520 IF a$="n" THEN GO TO 540

```

```

530 IF a$ <> "N" THEN GO TO 100
1000 REM days of week
1010 DATA "Mon", "Tues", "Wednes"
1020 DATA "Thurs", "Fri", "Satur", "Sun"
1100 REM lengths of months
1110 DATA 31, 28, 31, 30, 31, 30
1120 DATA 31, 31, 30, 31, 30, 31

```

This program handles yards, feet and inches.

```

10 INPUT "yards?",yd,"feet?",ft, "inches?",in
40 GO SUB 2000: REM print the values
50 PRINT "" = "";
70 GO SUB 1000: REM the adjustment
80 GO SUB 2000: REM print the adjusted values
90 PRINT
100 GO TO 10
1000 REM subroutine to adjust yd, ft, in to the normal form for
yards, feet and inches
1010 LET in=36*yd+12*ft+in: REM now everything is in inches
1030 LET s=SGN in: LET in=ABS in: REM we work with in
positive, holding its sign in s
1060 LET ft=INT (in/12): LET in=(in-12*ft)*s: REM now in is ok
1080 LET yd=INT (ft/3)*s: LET ft=ft*s-3*yd: RETURN
2000 REM subroutine to print yd, ft and in
2010 PRINT yd;"yd";ft;"ft";in;"in";: RETURN

```

Here is a program to throw coins for the I Ching. (Unfortunately it produces the patterns upside down, but you might not worry about this.)

```

5 RANDOMIZE
10 FOR m=1 TO 6: REM for 6 throws
20 LET c=0: REM initialize coin total to 0
30 FOR n=1 TO 3: REM for 3 coins
40 LET c=c+2+INT (2*RND)
50 NEXT n
60 PRINT " ";
70 FOR n=1 TO 2: REM 1st for the thrown hexagram, 2nd for
the changes
80 PRINT "___";
90 IF c=7 THEN PRINT "-";
100 IF c=8 THEN PRINT " ";
110 IF c=6 THEN PRINT "X";: LET c=7
120 IF c=9 THEN PRINT "0";: LET c=8
130 PRINT "___ ";
140 NEXT n
150 PRINT
160 INPUT a$
170 NEXT m: NEW

```

To use this, type it in and run it, and then press **ENTER** five times to get the two hexagrams. Look these up in a copy of the Chinese Book of Changes. The text will describe a situation and the courses of action appropriate to it, and you must ponder deeply to discover the parallels between that and your own life. Press **ENTER** a sixth time, and the program will erase itself – this is to discourage you from using it frivolously.

Many people find the texts are always more apt than they would expect on grounds of chance; this may or may not be the case with your ZX Spectrum. In general, computers are pretty godless creatures.

Here is a program to play 'Pangolins'. You think up an animal, and the computer tries to guess what it is, by asking you questions that can be answered 'yes' or 'no'. If it's never heard of your animal before, it asks you to give it some question that it can use next time to find out whether someone's given it your new animal.

```

5 REM pangolins
10 LET nq=100: REM number of questions and animals
15 DIM q$(nq,50): DIM a(nq,2): DIM r$(1)
20 LET qf=8
30 FOR n=1 TO qf/2-1
40 READ q$(n): READ a(n,1): READ a(n,2)
50 NEXT n
60 FOR n=n TO qf-1
70 READ q$(n): NEXT n

100 REM start playing
110 PRINT "Think of an animal.,""Press any key to continue."
120 PAUSE 0
130 LET c=1: REM start with 1st question
140 IF a(c,1)=0 THEN GO TO 300
150 LET p$q=q$(c): GO SUB 910
160 PRINT "?": GO SUB 1000
170 LET in=1: IF r$="y" THEN GO TO 210
180 IF r$="Y" THEN GO TO 210
190 LET in=2: IF r$="n" THEN GO TO 210
200 IF r$<>"N" THEN GO TO 150
210 LET c=a(c,in): GO TO 140

300 REM animal
310 PRINT "Are you thinking of"
320 LET p$q=q$(c): GO SUB 900: PRINT "?"
330 GO SUB 1000
340 IF r$="y" THEN GO TO 400
350 IF r$="Y" THEN GO TO 400
360 IF r$="n" THEN GO TO 500
370 IF r$="N" THEN GO TO 500

```

380 PRINT "Answer me properly when I'm","talking to you.": GO
TO 300

400 REM guessed it

410 PRINT "I thought as much.": GO TO 800

500 REM new animal

510 IF qf>nq-1 THEN PRINT "I'm sure your animal is very",
"interesting, but I don't have","room for it just now.": GO TO 800

520 LET q\$(qf)=q\$(c): REM move old animal

530 PRINT "What is it, then?": INPUT q\$(qf+1)

540 PRINT "Tell me a question which dist-","inguishes
between "

550 LET p\$=q\$(qf): GO SUB 900: PRINT " and"

560 LET p\$=q\$(qf+1): GO SUB 900: PRINT " "

570 INPUT s\$: LET b=LEN s\$

580 IF s\$(b)="? " THEN LET b=b-1

590 LET q\$(c)=s\$(TO b): REM insert question

600 PRINT "What is the answer for"

610 LET p\$=q\$(qf+1): GO SUB 900: PRINT "?"

620 GO SUB 1000

630 LET in=1: LET io=2: REM answers for new and old animals

640 IF r\$="y" THEN GO TO 700

650 IF r\$="Y" THEN GO TO 700

660 LET in=2: LET io=1

670 IF r\$="n" THEN GO TO 700

680 IF r\$="N" THEN GO TO 700

690 PRINT "That's no good. ": GO TO 600

700 REM update answers

710 LET a(c,in)=qf+1: LET a(c,io)=qf

720 LET qf=qf+2: REM next free animal space

730 PRINT "That fooled me."

800 REM again?

810 PRINT "Do you want another go?": GO SUB 1000

820 IF r\$="y" THEN GO TO 100

830 IF r\$="Y" THEN GO TO 100

840 STOP

900 REM print without trailing spaces

905 PRINT " ";

910 FOR n=50 TO 1 STEP -1

920 IF p\$(n)<>" " THEN GO TO 940

```

930 NEXT n
940 PRINT p$(TO n);: RETURN

1000 REM get reply
1010 INPUT r$: IF r$="" THEN RETURN
1020 LET r$=r$(1): RETURN

2000 REM initial animals
2010 DATA "Does it live in the sea",4,2
2020 DATA "Is it scaly",3,5
2030 DATA "Does it eat ants",6,7
2040 DATA "a whale", "a blanchmange", "a pangolin", "an ant"

```

Here is a program to draw a Union Flag.

```

5 REM union flag
10 LET r=2: LET w=7: LET b=1
20 BORDER 0: PAPER b: INK w: CLS
30 REM black in bottom of screen
40 INVERSE 1
50 FOR n=40 TO 0 STEP -8
60 PLOT PAPER 0;7,n: DRAW PAPER 0;241,0
70 NEXT n: INVERSE 0
100 REM draw in white parts
105 REM St. George
110 FOR n=0 TO 7
120 PLOT 104+n,175: DRAW 0,-35
130 PLOT 151-n,175: DRAW 0,-35
140 PLOT 151-n,48: DRAW 0,35
150 PLOT 104+n,48: DRAW 0,35
160 NEXT n
200 FOR n=0 TO 11
210 PLOT 0,139-n: DRAW 111,0
220 PLOT 255,139-n: DRAW -111,0
230 PLOT 255,84+n: DRAW -111,0
240 PLOT 0,84+n: DRAW 111,0
250 NEXT n
300 REM St. Andrew
310 FOR n=0 TO 35
320 PLOT 1+2*n,175-n: DRAW 32,0
330 PLOT 224-2*n,175-n: DRAW 16,0
340 PLOT 254-2*n,48+n: DRAW -32,0
350 PLOT 17+2*n,48+n: DRAW 16,0
360 NEXT n
370 FOR n=0 TO 19

```

```

380 PLOT 185+2*n,140+n: DRAW 32,0
390 PLOT 200+2*n,83-n: DRAW 16,0
400 PLOT 39-2*n,83-n: DRAW 32,0
410 PLOT 54-2*n,140+n: DRAW -16,0
420 NEXT n
425 REM fill in extra bits
430 FOR n=0 TO 15
440 PLOT 255,160+n: DRAW 2*n-30,0
450 PLOT 0,63-n: DRAW 31-2*n,0
460 NEXT n
470 FOR n=0 TO 7
480 PLOT 0,160+n: DRAW 14-2*n,0
485 PLOT 255,63-n: DRAW 2*n-15,0
490 NEXT n
500 REM red stripes
510 INVERSE 1
520 REM St. George
530 FOR n=96 TO 120 STEP 8
540 PLOT PAPER r;7,n: DRAW PAPER r;241,0
550 NEXT n
560 FOR n=112 TO 136 STEP 8
570 PLOT PAPER r;n,168: DRAW PAPER r;0,-113
580 NEXT n
600 REM St. Patrick
610 PLOT PAPER r;170,140: DRAW PAPER r;70,35
620 PLOT PAPER r;179,140: DRAW PAPER r;70,35
630 PLOT PAPER r;199,83: DRAW PAPER r;56,-28
640 PLOT PAPER r;184,83: DRAW PAPER r;70,-35
650 PLOT PAPER r;86,83: DRAW PAPER r;-70,-35
660 PLOT PAPER r;72,83: DRAW PAPER r;-70,-35
670 PLOT PAPER r;56,140: DRAW PAPER r;-56,28
680 PLOT PAPER r;71,140: DRAW PAPER r;-70,35
690 INVERSE 0: PAPER 0: INK 7

```

If you're not British, have a go at drawing your own flag. Tricolours are fairly easy, although some of the colours – for instance the orange in the Irish flag – might present difficulties. If you're an American, you might be able to fit the character * in.

Here is a program to play hangman. One player enters a word, and the other guesses.

```

5 REM Hangman
10 REM set up screen
20 INK 0: PAPER 7: CLS
30 LET x=240: GO SUB 1000: REM draw man

```

```

40 PLOT 238,128: DRAW 4,0: REM mouth
100 REM set up word
110 INPUT w$: REM word to guess
120 LET b=LEN w$: LET v$=""
130 FOR n=2 TO b: LET v$=v$+" "
140 NEXT n: REM v$=word guessed so far
150 LET c=0: LET d=0: REM guess & mistake counts
160 FOR n=0 TO b-1
170 PRINT AT 20,n;"-";
180 NEXT n: REM write -'s instead of letters
200 INPUT "Guess a letter: ";g$
210 IF g$="" THEN GO TO 200
220 LET g$=g$(1): REM 1st letter only
230 PRINT AT 0,c:g$
240 LET c=c+1: LET u$=v$
250 FOR n=1 TO b: REM update guessed word
260 IF w$(n)=g$ THEN LET v$(n)=g$
270 NEXT n
280 PRINT AT 19,0;v$
290 IF v$=w$ THEN GO TO 500: REM word guessed
300 IF v$<>u$ THEN GO TO 200: REM guess was right
400 REM draw next part of gallows
410 IF d=8 THEN GO TO 600: REM hanged
420 LET d=d+1
430 READ x0,y0,x,y
440 PLOT x0,y0: DRAW x,y
450 GO TO 200
500 REM free man
510 OVER 1: REM rub out man
520 LET x=240: GO SUB 1000
530 PLOT 238,128: DRAW 4,0: REM mouth
540 OVER 0: REM redraw man
550 LET x=146: GO SUB 1000
560 PLOT 143,129: DRAW 6,0,PI/2: REM smile
570 GO TO 800
600 REM hang man
610 OVER 1: REM rub out floor
620 PLOT 255,65: DRAW -48,0
630 DRAW 0,-48: REM open trapdoor
640 PLOT 238,128: DRAW 4,0: REM rub out mouth
650 REM move limbs
655 REM arms
660 PLOT 255,117: DRAW -15,-15: DRAW -15,15
670 OVER 0
680 PLOT 236,81: DRAW 4,21: DRAW 4,-21

```

```
690 OVER 1: REM legs
700 PLOT 255,66: DRAW -15,15: DRAW -15,-15
710 OVER 0
720 PLOT 236,60: DRAW 4,21: DRAW 4,-21
730 PLOT 237,127: DRAW 6,0, -PI/2: REM frown
740 PRINT AT 19,0;w$
800 INPUT "again? ";a$
810 IF a$="" THEN GO TO 850
820 LET a$=a$(1)
830 IF a$="n" THEN STOP
840 IF a$(1)="N" THEN STOP
850 RESTORE : GO TO 5
1000 REM draw man at column x
1010 REM head
1020 CIRCLE x,132,8
1030 PLOT x+4,134: PLOT x-4,134: PLOT x,131
1040 REM body
1050 PLOT x,123: DRAW 0,-20
1055 PLOT x,101: DRAW 0,-19
1060 REM legs
1070 PLOT x-15,66: DRAW 15,15: DRAW 15,-15
1080 REM arms
1090 PLOT x-15,117: DRAW 15,-15: DRAW 15,15
1100 RETURN
2000 DATA 120,65,135,0,184,65,0,91
2010 DATA 168,65,16,16,184,81,16,-16
2020 DATA 184,156,68,0,184,140,16,16
2030 DATA 204,156,-20,-20,240,156,0,-16
```

Binary and hexadecimal

This appendix describes how computers count, using the binary system.

Most European languages count using a more or less regular pattern of tens – in English, for example, although it starts off a bit erratically, it soon settles down into regular groups:

twenty, twenty one, twenty two,.....twenty nine
 thirty, thirty one, thirty two,.....thirty nine
 forty, forty one, forty two,.....forty nine

and so on, and this is made even more systematic with the Arabic numerals that we use. However, the only reason for using ten is that we happen to have ten fingers and thumbs.

Instead of using the *decimal* system, with ten as its base, computers use a form of binary called *hexadecimal* (or *hex*, for short), based on sixteen. As there are only ten digits available in our number system we need six extra digits to do the counting. So we use A, B, C, D, E and F. And what comes after F? Just as we, with ten fingers, write 10 for ten, so computers write 10 for sixteen. Their number system starts off:

<i>Hex</i>	<i>English</i>
0	nought
1	one
2	two
:	:
:	:
9	nine

just as ours does, but then it carries on

A	ten
B	eleven
C	twelve
D	thirteen
E	fourteen
F	fifteen
10	sixteen
11	seventeen
:	:
:	:
19	twenty five
1A	twenty six
1B	twenty seven
:	:
:	:
1F	thirty one
20	thirty two

21	thirty three
:	:
:	:
9E	one hundred and fifty eight
9F	one hundred and fifty nine
A0	one hundred and sixty
A1	one hundred and sixty one
:	:
B4	one hundred and eighty
:	:
FE	two hundred and fifty four
FF	two hundred and fifty five
100	two hundred and fifty six

If you are using hex notation and you want to make the fact quite plain, then write 'h' at the end of the number, and say 'hex'. For instance, for one hundred and fifty eight, write '9Eh' and say 'nine E hex'.

You will be wondering what all this has to do with computers. In fact, computers behave as though they had only two digits, represented by a low voltage, or off (0), and a high voltage, or on (1). This is called the *binary* system, and the two binary digits are called *bits*: so a bit is either 0 or 1.

In the various systems, counting starts off

<i>English</i>	<i>Decimal</i>	<i>Hexadecimal</i>	<i>Binary</i>
nought	0	0	0 or 0000
one	1	1	1 or 0001
two	2	2	10 or 0010
three	3	3	11 or 0011
four	4	4	100 or 0100
five	5	5	101 or 0101
six	6	6	110 or 0110
seven	7	7	111 or 0111
eight	8	8	1000
nine	9	9	1001
ten	10	A	1010
eleven	11	B	1011
twelve	12	C	1100
thirteen	13	D	1101
fourteen	14	E	1110
fifteen	15	F	1111
sixteen	16	10	10000

The important point is that sixteen is equal to two raised to the fourth power, and this makes converting between hex and binary very easy.

To convert hex to binary, change each hex digit into four bits, using the table above.

To convert binary to hex, divide the binary number into groups of four bits, starting on the right, and then change each group into the corresponding hex digit.

For this reason, although strictly speaking computers use a pure binary system, humans often write the numbers stored inside a computer using hex notation.

The bits inside the computer are mostly grouped into sets of eight, or *bytes*. A single byte can represent any number from nought to two hundred and fifty five (11111111 binary or FF hex), or alternatively any character in the ZX Spectrum character set. Its value can be written with two hex digits.

Two bytes can be grouped together to make what is technically called a word. A word can be written using sixteen bits or four hex digits, and represents a number from 0 to (in decimal) $2^{16}-1=65535$.

A byte is always eight bits, but words vary in length from computer to computer.

The **BIN** notation in Chapter 14 provides a means of writing numbers in binary on the ZX Spectrum: '**BIN 0**' represents nought, '**BIN 1**' represents one, '**BIN 10**' represents two, and so on.

You can only use 0's and 1's for this, so the number must be a non-negative whole number; for instance you can't write '**BIN -11**' for minus three – you must write '**-BIN 11**' instead. The number must also be no greater than decimal 65535 – i.e. it can't have more than sixteen bits.

ATTR really was binary. If you convert the result from **ATTR** into binary, you can write it in eight bits.

The first is 1 for flashing, 0 for steady.

The second is 1 for bright, 0 for normal.

The next three are the code for the paper colour, written in binary.

The last three are the code for the ink colour, written in binary.

The colour codes also use binary: each code written in binary can be written in three bits, the first for green, the second for red and the third for blue.

Black has no light at all, so all the bits are 0 (off). Therefore the code for black is 000 in binary, or nought.

The pure colours, green, red and blue have just one bit 1 (on) out of the three. Their codes are 100, 010 and 001 in binary, or four, two and one.

The other colours are mixtures of these, so their codes in binary have two or more bits 1.

Index

This index includes the keys on the keyboard and how to obtain them (the mode – **K**, **L**, **E**, **C** or **G** – and which shift key where appropriate).

Usually an entry is referenced only once per chapter, so having found one reference, look through the rest of the chapter including the exercises.

A

ABS	E , on G.	59
accuracy		47
ACS	E , shifted W.	70
addition of strings		53, 58
address		143
– of a byte		143, 163
port address		159
return address		37
alphabetical order		25, 95
AND	K , L or C , SYMBOL SHIFT Y.	85
apostrophe		17, 101
argument		57, 159
arithmetic expression		45
array		79, 142
string array		80
ASCII		91
ASN	E , shifted Q.	70
assembler		179
assembly language		179
assign		52
AT	K , L or C , SYMBOL SHIFT I.	101, 196
ATN	E , shifted E.	65, 70
ATTR	E , shifted L.	116, 164, 219
attributes		110, 195
automatic listing		19

B

background		110
BASIC		7, 26, 51
BEEP	E , shifted Z.	7, 130, 135
BIN	E , on B	93, 124
		221

Index

binary	93, 166, 197, 217
– operation	198
– scale	169
– system	218
bit	159
BORDER	K , on B. 7, 113
bottom of screen	9
bracket	53, 57
BREAK	CAPS SHIFT and SPACE. 8, 19, 34, 151
BRIGHT	E , shifted B. 110, 125
brightness	110
buffer	164, 196
byte	143, 159, 163

C

C mode	8
call	37
capitals	8
– mode	8
CAPS LOCK	K or L , CAPS SHIFT 2. 8
CAPS SHIFT	7, 19, 91
cassette recorder	8, 19, 141
CAT	E , SYMBOL SHIFT 9. 155
character	7, 91
– set	91, 183
control character	94, 105, 114
CHR\$	E , on U. 91, 105, 114
CIRCLE	E , shifted H. 121, 195
CLEAR	K on X 168
click	137
CLOSE #	E , SYMBOL SHIFT 5. 155
CLS	K , on V. 25, 37, 103
CODE	E , on I. 91, 143
code	91, 143, 219
machine code	179
colon	17, 26
colour	109, 195
ink colour	92, 109
paper colour	92, 109
primary colours	111
– codes	219
comma	17, 41
command	7, 25
comparison	25

condition		25
CONTINUE	K , on C	19, 26, 33
contrast		111
control		193
– character		105, 114
– variable		32
coordinate		121
COPY	K , on Z.	151
COS	E , on W.	67
counting variable		32
current line		8, 14
cursor		7, 14, 193
C cursor		8
E cursor		8
G cursor		8
K cursor		7, 16
L cursor		14
hidden cursor		15
program cursor (▶)		8, 14

D

data		13
DATA	E , on D.	41, 79, 142
– list		41
– statement		41
decimal system		217
DEF FN	E , SYMBOL SHIFT 1.	60
degree		70
DELETE	C or G on 0, K , L , C or G , CAPS SHIFT 0.	8, 15, 91, 193
DIM	K , on D.	79
dimension		79
dots		110
double quotes		47
DRAW	K on W.	121, 195
duration		135

E

E mode		8
EDIT	K , L or C , CAPS SHIFT 1.	8, 14
element		79, 121

Index

empty string 47, 198
ENTER 8, 14, 194
ERASE **E**, SYMBOL SHIFT 7. 155
EXP **E**, on X. 65
exponent 46, 166
exponential growth 66
expression
 arithmetic expression 45
 logical expression 85
 mathematical expression 45
 numeric expression 41, 46, 58, 101, 197
 string expression 41, 53, 101, 197
extended mode 8, 67, 114

F

false 25, 85
FLASH **E**, shifted V. 109, 122
floating point 46, 197
FN **E**, SYMBOL SHIFT 2. 60
foreground 110
FOR **K**, on F. 31, 38, 197
FOR – NEXT loop 31, 41, 197
FORMAT **E**, SYMBOL SHIFT 0. 155
function 7, 57, 198

G

G mode 8, 193
GO SUB **K**, on H. 37, 168
 – stack 37, 168
GO TO **K**, on G. 16, 25, 31, 37
graph 125
graphics 8, 121
 – symbol 91
 – mode 8, 91, 193
 user-defined graphics 8, 92
GRAPHICS **K**, **L** or **C**, CAPS SHIFT 0. 8, 91, 119, 193

H

hex 217

hexadecimal 217
hidden cursor 15

I

IF
IN
initial value
INK
ink colour
INKEY\$
INPUT
– data
– item
INT
integer
INVERSE
inverse
I/O ports
item
 INPUT item
 PRINT item

K, on U. 25, 31, 85
E, shifted I. 159
E, shifted X. 109, 122, 195
92, 109
E, on N. 131
K, on I. 7, 16, 25, 31, 195
103
E, on R. 104
59, 73
E, shifted M. 112, 122, 195
67
159
101
104
101

K

K mode 7
key 135
keyboard 7, 115, 193
keyword 7, 193
– mode 7, 193

L

L mode 7, 193
LEFT\$ 61
LEN
LET
letter mode 7, 13, 31, 38
limit 7, 193
32
LINE
line 105, 144, 181
7
– number 13, 26

Index

current line	8, 14
program line	7, 13
top line	20
LIST	K , on K.
listing	8, 13
automatic listing	19
LLIST	E , on V.
LN	E , on Z.
LOAD	K , on J.
logarithmic function	67
logical expression	85
loop	33, 197
-ing	32
FOR – NEXT loop	31, 41, 197
lower case	7
LPRINT	E , on C.
	151, 195
M	
machine code	179
mantissa	47, 166
mathematical expressions	45
memory	159, 163
– address	159
menu	147
MERGE	E , shifted T.
Microdrive	155
MID\$	61
mnemonics	179, 183
mode	7
capitals mode	8
extended mode	8
graphics mode	8, 91, 193
keyword mode	7, 193
letter mode	7, 193
modulo	103
MOVE	E , SYMBOL SHIFT 6.
music	155
	135
N	
name	45
– of a variable	45

- of a program 141
 - nesting 33
 - network 155
 - NEW** **K**, on Al. 16, 25
 - NEXT** **K**, on N. 31, 41, 197
 - NOT** **K**, **L** or **C**, SYMBOL SHIFT S. 85
 - null string 47
 - numeric
 - expression 41, 46, 58, 101, 197
 - variable 32
- O**
- octave 135
 - OPEN #** **E**, SYMBOL SHIFT 4. 155
 - operation 45
 - arithmetic operation 45
 - binary operation 198
 - OR** **K**, **L** or **C**, SYMBOL SHIFT U. 85
 - OUT** **E**, shifted O. 159
 - OVER** **E**, shifted N. 112, 122, 195
 - overprinting 113
- P**
- PAPER** **E**, shifted C. 7, 109, 122, 195
 - paper colour 92, 109
 - PAUSE** **K**, on M. 129
 - PEEK** **E**, on O. 94, 129, 163
 - PI** **E**, on M. 67
 - pitch 135
 - pixel 121
 - PLOT** **K**, on Q. 121, 195
 - POINT** **E**, SYMBOL SHIFT 8. 123, 164
 - POKE** **K**, on O. 94, 124, 159, 163
 - port address 159
 - power 65
 - primary colours 111
 - PRINT** **K**, on P. 7, 13, 25, 31, 37, 195
 - item 101
 - position 9
 - separators 101
 - printer 8, 19, 151, 196

Index

priority	45, 65, 85, 201
processor	159
Procrustean assignment	52, 80
program	7, 13, 141
– cursor	8, 14
– line	7, 13
pseudorandom	117
punctuation	17

Q

quote	18, 47
double quotes	47
string quotes	18, 47

R

radian	70
RAM	159, 163
RAMTOP	168
RANDOMIZE	K , on T. 73
random	73
READ	E , on A. 41
recursive	38
register	179
relation	25, 85, 95
REM	K , on E. 16, 25, 31
repeat	8
report	8, 16, 26, 189
RESTORE	E , on S. 41
result	57
RETURN	K , on Y. 37
return address	37
RIGHT\$	61
RND	E , on T. 73
ROM	159, 163
rounding	47, 97
RS232	155
RUN	K , on R. 14

S

SAVE	K , on S. 141, 180
-------------	---------------------------

scientific notation		46
screen		8
– full		20
bottom of screen		8
top of screen		8
SCREEN\$	E , shifted K.	143, 164
scroll?		8, 20, 104
scrolling		20, 103
semicolon		17
SGN	E , on F.	59
shift		7
–ed key		7
CAPS SHIFT		7, 19, 91
SYMBOL SHIFT		7, 25, 32
sign, signum		59
simple variable		79
SIN	E , on Q.	67
slice		51, 81, 197
slicer		197
SPACE		8
space		45
SQR	E , on H.	60
stack		37, 168
calculator stack		168
GO SUB stack		37, 168
machine stack		168
statement		41
stave		135
STEP	K , L or C , SYMBOL SHIFT D.	32
STOP	K , L or C , SYMBOL SHIFT A.	8, 16, 25, 34
STR\$	E , on Y.	58
string		51
– addition		53, 58
– array		80
– expression		41, 51, 101, 197
– input		18
– quote		18
– slicing		51
– variable		18
subroutine		37
subscript		51, 79
–ed variable		79
substring		51
symbol		7
SYMBOL SHIFT		7, 25, 32

Index

syntax error 8
system variable 164, 173

T

TAB **E**, on P. 103, 196
TAN **E**, on E. 67
television 8, 109
THEN **K**, **L** or **C**, SYMBOL SHIFT G. 7, 25, 85
TL\$ 61
TO **K**, **L** or **C**, SYMBOL SHIFT F. 32, 51
token 7, 91
top line 20
trigonometrical function 65
true 25, 85

U

undefined variable 19
USR **E**, on L. 93, 124, 180

V

VAL **E**, on J. 58
VAL\$ **E**, shifted J. 59
value
 initial value 32
variable 15, 31, 141
 – name 45
 control variable 32
 counting variable 32
 numeric variable 32
 simple variable 79
 string variable 18
 subscripted variable 79
 system variable 164, 173
 undefined variable 19
VERIFY **E**, shifted R. 141

X

x-axis 68
x-coordinate 119

Y

y-axis

68

y-coordinate

119

Z

Z80

179

!	K , L or C	SYMBOL SHIFT 1.	18
"	K , L or C	SYMBOL SHIFT P.	16
#	K , L or C	SYMBOL SHIFT 3.	
\$	K , L or C	SYMBOL SHIFT 4.	18
%	K , L or C	SYMBOL SHIFT 5.	
&	K , L or C	SYMBOL SHIFT 6.	
'	K , L or C	SYMBOL SHIFT 7.	17
(K , L or C	SYMBOL SHIFT 8.	16
)	K , L or C	SYMBOL SHIFT 9.	16
*	K , L or C	SYMBOL SHIFT B.	16
+	K , L or C	SYMBOL SHIFT K.	14
,	K , L or C	SYMBOL SHIFT H.	16
-	K , L or C	SYMBOL SHIFT J.	16
.	K , L or C	SYMBOL SHIFT M.	58
/	K , L or C	SYMBOL SHIFT V.	16
:	K , L or C	SYMBOL SHIFT Z.	17
;	K , L or C	SYMBOL SHIFT O.	17
<	K , L or C	SYMBOL SHIFT R.	25
=	K , L or C	SYMBOL SHIFT L.	13
>	K , L or C	SYMBOL SHIFT T.	25
?	K , L or C	SYMBOL SHIFT C.	47
@	K , L or C	SYMBOL SHIFT 2.	
[E	shifted Y.	
\	E	shifted D.	
]	E	shifted U.	
↑	K , L or C	SYMBOL SHIFT H.	65
—	K , L or C	SYMBOL SHIFT 0.	
£	K , L or C	SYMBOL SHIFT X.	
{	E	shifted F.	
	E	shifted S.	
}	E	shifted G.	
~	E	shifted A.	
©	E	shifted P.	
<=	K , L or C	SYMBOL SHIFT Q.	25
>=	K , L or C	SYMBOL SHIFT E.	25

<>	K , L or C , SYMBOL SHIFT W.	25
↔	K , L or C , CAPS SHIFT 5.	
↔	K , L or C , CAPS SHIFT 8.	14
↔	K , L or C , CAPS SHIFT 6.	8
↔	K , L or C , CAPS SHIFT 7.	8

*Printed by
The Legrave Press Ltd
Luton and London*

Sinclair Research Limited

25 Willis Road
Cambridge CB1 2AQ
England