



Joist Hanger Detail (Not to Scale)



Restraint straps should be fixed to at least three rafterss with two steel screws or two 75x4mm (8SWG) round nails to each timber member. Rafters should NOT be notched to make the straps flush with the rafter. Straps should go under rafters & over ceiling joists. The turn down should be on a substantial piece of blockwork, preferably the centre of an uncut block.

## Roof Strap Detail (Not to Scale)



Ridge vent at 3m centres. Vent to be fixed to ridge timbers with proprietory clips and/or screws Avoid bedding on mortar. Follow manufacturers detailed

Dry Ridge Detail (Not to Scale)

В	27/01/21	Structural steelwork added.	GG	
Α	07/12/20	First Floor Layout Amended	GG	
REV	DATE	AMENDMENT	BY	CHKD

## **HNA**architects

Architecture | Planning | Design

PROJECT:	Land adjacent 615 Swanlow Lane, Winsford							
CLIENT:	Linear Living							
DRAWING:	Plot two - First floor plan							
DRAWN BY:	YQ	CHECKED BY:		DATE:	SCALE	SCALE:		
				Nov 2020	1:50 @ A3			
STATUS:	Technical design			DRAWING No:	REVISION:			
				1301/C/105	В			

DO NOT SCALE.
COPYRIGHT REMAINS WITH HNA ARCHITECTS Ltd.

HOLLINWOOD BUSINESS CENTRE, ALBERT STREET, OLDHAM, OL8 3QL

TEL: 0161.688 1820
E-MAIL: garry@hna-architects.co.uk : mlchael@hna-architects.co.uk



NB: All steelwork to be intumescently painted to provide min. 1 hour fire resistance unless encased in fireboarding.